

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

MICHAEL F. EASLEY
GOVERNOR

LYNDO TIPPETT SECRETARY

June 30, 2008

Addendum No. 1

RE: Contract ID: C201857
WBS# 34912.3.3
F. A. No. STP-0701(16)
Alamance County (U-3304)
Grand Oaks Boulevard Extension From SR-1146 (Kirkpatrick Road)
To NC-62 (Alamance Road) In Burlington

July 15, 2008 Letting

To Whom It May Concern:

Reference is made to the proposal form recently furnished to you on this project.

The following revisions have been made to the proposal:

On Page No. 41, the first sentence of the project special provision entitled "Shallow Undercut" has been revised to correct the depth of undercut. Please void Page No. 41 in your proposal and staple the revised Page No. 41 thereto.

Sincerely,

R. A. Garris, PE Contract Officer

RAG/jag/blr Attachments

Page 2

RE: Contract ID: C201857 **Alamance County (U-3304)**

Cc: Mr. W. S. Varnedoe, PE

Mr. E. C. Powell, PE

Mr. J. M. Mills, PE

Ms. D.M. Barbour, PE

Mr. Art McMillan, PE

Mr. J. V. Barbour, PE

Mr. Njorge Wainaina, PE

Mr. Mark Staley (2)

Mr. Robert Memory

Mr. R. E. Davenport, Jr., PE

Ms. Norma Smith

Mr. Ronnie Higgins

Mr. Larry Strickland

Ms. Lori Strickland

Project File (2)

41



per cubic yard for *Unclassified Excavation*. Pavement that is removed will be measured and will be paid for at the contract unit price per square yard for *Removal of Existing Pavement*. Pipe culverts that are removed will be measured and will be paid for at the contract unit price per linear foot for *Pipe Removal*. Such prices and payments will be full compensation for the work of removing, salvaging, and stockpiling aggregate base course; removing pipe culverts; and for placing earth material and pavement in embankments or disposing of earth material and pavement in waste areas.

SHALLOW UNDERCUT:

(9-18-07)

SP2 R35 A

Description

Undercut to a depth of 6 to 24 inches and place fabric for soil stabilization and Class IV Subgrade Stabilization at locations shown on the plans or as directed by the Engineer.

Materials

Refer to Division 10 of the Standard Specifications.

Item	Section
Select Material, Class IV	1016
Fabric for Soil Stabilization, Type 4	1056

Use Class IV Select Material for Class IV Subgrade Stabilization. If Class IV Subgrade Stabilization does not meet the requirements of Article 1010-2 of the *Standard Specifications*, the Engineer, at his discretion, may consider the material reasonably acceptable in accordance with Article 105-3 of the *Standard Specifications*.

Construction Methods

Perform undercut excavation in accordance with Section 225 of the *Standard Specifications*. Place fabric for soil stabilization in accordance with Article 270-3 of the *Standard Specifications* before backfilling. Backfill with Class IV Subgrade Stabilization by end dumping subgrade stabilization material on the fabric. Do not operate heavy equipment on the fabric until it is covered with Class IV Subgrade Stabilization. Compact subgrade stabilization material to 92% of AASHTO T180 as modified by the Department or to the highest density that can be reasonably obtained.

Maintain Class IV Subgrade Stabilization in an acceptable condition and minimize the use of heavy equipment on subgrade stabilization material in order to avoid damaging the backfill. Provide and maintain drainage ditches and drains as required to prevent entrapment of water in backfill.

Measurement and Payment

Class IV Subgrade Stabilization will be measured and paid for at the contract unit price per ton. The quantity to be paid for will be the actual number of tons of subgrade stabilization material that has been incorporated into the completed and accepted work. The material will be measured