

County : Clay

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (19+01.00-L-)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	50 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	50 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	290 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	50 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	50 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	40 TON		
0011	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	68 LF		
0012	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	260 LF		
0013	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	52 LF		
0014	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0015	0995000000-E	340	PIPE REMOVAL	30 LF		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	650 TON		
0017	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	360 TON		
0018	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	52 TON		

County : Clay

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2000000000-N	806	RIGHT OF WAY MARKERS	25 EA		
0020	2022000000-E	815	SUBDRAIN EXCAVATION	30 CY		
0021	2033000000-E	815	SUBDRAIN FINE AGGREGATE	20 CY		
0022	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0023	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0024	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0025	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0026	2264000000-E	840	PIPE PLUGS	0.13 CY		
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	7 EA		
0028	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	1 EA		
0029	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0030	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	1 EA		
0031	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	2 EA		
0032	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	160 LF		
0033	2556000000-E	846	SHOULDER BERM GUTTER	248 LF		
0034	3030000000-E	862	STEEL BM GUARDRAIL	250 LF		
0035	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	56.25 LF		
0036	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		

County : Clay

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0038	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0039	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0040	3649000000-E	876	RIP RAP, CLASS B	20 TON		
0041	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	450 SY		
0042	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0043	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	762 SF		
0044	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	112 SF		
0045	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	190 SF		
0046	4430000000-N	1130	DRUMS	50 EA		
0047	4445000000-E	1145	BARRICADES (TYPE III)	170 LF		
0048	4450000000-N	1150	FLAGGER	320 HR		
0049	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	18,020 LF		
0050	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	70 LF		
0051	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	200 LF		
0052	6000000000-E	1605	TEMPORARY SILT FENCE	800 LF		
0053	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	150 TON		
0054	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	230 TON		

County : Clay

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	6012000000-E	1610	SEDIMENT CONTROL STONE	210 TON		
0056	6015000000-E	1615	TEMPORARY MULCHING	6 ACR		
0057	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0058	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1 TON		
0059	6024000000-E	1622	TEMPORARY SLOPE DRAINS	70 LF		
0060	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0061	6029000000-E	SP	SAFETY FENCE	200 LF		
0062	6030000000-E	1630	SILT EXCAVATION	1,110 CY		
0063	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,600 SY		
0064	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	250 SY		
0065	6042000000-E	1632	1/4" HARDWARE CLOTH	100 LF		
0066	6070000000-N	SP	SPECIAL STILLING BASINS	4 EA		
0067	6071030000-E	SP	COIR FIBER BAFFLES	310 LF		
0068	6084000000-E	1660	SEEDING & MULCHING	6 ACR		
0069	6087000000-E	1660	MOWING	3.5 ACR		
0070	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0071	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0072	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	150 LB		
0073	6108000000-E	1665	FERTILIZER TOPDRESSING	4.25 TON		
0074	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		

County : Clay

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
<b>STRUCTURE ITEMS</b>						
0076	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (18+20.00-L-)	Lump Sum	L.S.	
0077	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18+20.00-L-)	Lump Sum	L.S.	
0078	8105520000-E	SP	3'-0" DIA DRILLED PIERS IN SO IL	21.75 LF		
0079	8105620000-E	SP	3'-0" DIA DRILLED PIERS NOT IN SOIL	20 LF		
0080	8111200000-E	SP	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	19.75 LF		
0081	8113000000-N	SP	SID INSPECTION	1 EA		
0082	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0083	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (18+20.00-L-)	Lump Sum	L.S.	
0084	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	56.3 CY		
0085	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18+20.00-L-)	Lump Sum	L.S.	
0086	8217000000-E	425	REINFORCING STEEL (BRIDGE)	14,486 LB		
0087	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	775 LB		
0088	8364000000-E	450	HP12X53 STEEL PILES	120 LF		
0089	8365000000-E	450	HP12X53 GALVANIZED STEEL PILES	160 LF		

County : Clay

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0090	8503000000-E	460	CONCRETE BARRIER RAIL	319.25		
				LF		
0091	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	116		
				TON		
0092	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	137		
				SY		
0093	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0094	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	1,755.88		
				LF		
0095	8892000000-E	SP	GENERIC STRUCTURE ITEM 18" GALVANIZED STEEL SHEET PI LES	1,370		
				SF		
1055/Jun09/Q48136.31/D424943570000/E95			Total Amount Of Bid For Entire Project :			

**Contract No**     **C201875**

**County (ies):**   **Clay**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General