

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (14 + 15.50)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	500 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	40 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
001C	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	30 TON		
0011	0343000000-E	310	15" SIDE DRAIN PIPE	68 LF		
0012	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	208 LF		
0013	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	298 TON		
0015	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	181 TON		
0016	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	25 TON		
0017	2022000000-E	815	SUBDRAIN EXCAVATION	224 CY		
0018	2033000000-E	815	SUBDRAIN FINE AGGREGATE	168 CY		

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,000 LF		
0020	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	30 EA		
0021	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0022	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0023	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5 EA		
0024	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2 EA		
0025	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0026	2535000000-E	846	***X *** CONCRETE CURB (8" X 18")	630 LF		
0027	2556000000-E	846	SHOULDER BERM GUTTER	137 LF		
0028	2612000000-E	848	6" CONCRETE DRIVEWAY	30 SY		
0029	3030000000-E	862	STEEL BM GUARDRAIL	187.5 LF		
0030	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	137.5 LF		
0031	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0032	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (B-77 SHOP CURVED)	2 EA		
0033	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	1 EA		
0034	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0035	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	2 EA		

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	3628000000-E	876	RIP RAP, CLASS I	30 TON		
0037	3649000000-E	876	RIP RAP, CLASS B	3 TON		
003E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	235 SY		
003E	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	69 SF		
004C	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	128 LF		
0041	4102000000-N	904	SIGN ERECTION, TYPE E	19 EA		
0042	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	7 EA		
004E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	96 SF		
0044	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	208 SF		
004E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	36 SF		
004E	4430000000-N	1130	DRUMS	40 EA		
0047	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		
004E	4455000000-N	1150	FLAGGER	16 MD		
004E	4480000000-N	1165	TMIA	2 EA		
005C	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	9,474 LF		
0051	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	90 LF		
0052	6000000000-E	1605	TEMPORARY SILT FENCE	910 LF		
005E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	110 TON		

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	300 TON		
005E	6012000000-E	1610	SEDIMENT CONTROL STONE	130 TON		
005E	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0057	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
005E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
005E	6029000000-E	SP	SAFETY FENCE	250 LF		
006C	6030000000-E	1630	SILT EXCAVATION	860 CY		
0061	6036000000-E	1631	MATTING FOR EROSION CONTROL	510 SY		
0062	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	120 SY		
006E	6042000000-E	1632	1/4" HARDWARE CLOTH	100 LF		
0064	6071030000-E	SP	COIR FIBER BAFFLES	280 LF		
006E	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
006E	6087000000-E	1660	MOWING	1 ACR		
0067	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
006E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
006E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
007C	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
0071	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0072	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	27 EA		

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0073	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (14 + 15.50-L-)	Lump Sum	L.S.	
0074	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14 + 15.50-L-)	Lump Sum	L.S.	
0075	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	3,379 SF		
0076	8161000000-E	420	GROOVING BRIDGE FLOORS	3,110 SF		
0077	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	27.8 CY		
0078	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14 + 15.50-L-)	Lump Sum	L.S.	
0079	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,080 LB		
008C	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	119,895 LS		
0081	8364000000-E	450	HP12X53 STEEL PILES	490 LF		
0082	8503000000-E	460	CONCRETE BARRIER RAIL	244.67 LF		
0083	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	170 TON		
0084	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	190 SY		
008E	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1539/Jun02/Q152381.97/D359937130000/E85

Total Amount Of Bid For Entire Project :

Contract No **C201832**

County (ies): **Jackson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General