

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (13+44)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	10 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	250 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	30 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	250 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	40 TON		
0011	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	44 LF		
0012	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	20 LF		
0013	0995000000-E	340	PIPE REMOVAL	20 LF		
0014	1220000000-E	545	INCIDENTAL STONE BASE	25 TON		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	360 TON		
0016	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	220 TON		
0017	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	240 TON		

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	42	TON	
001E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	20	TON	
002C	2000000000-N	806	RIGHT OF WAY MARKERS	30	EA	
0021	2022000000-E	815	SUBDRAIN EXCAVATION	25	CY	
0022	2033000000-E	815	SUBDRAIN FINE AGGREGATE	20	CY	
0023	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100	LF	
0024	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3	EA	
0025	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1	EA	
002E	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6	LF	
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5	EA	
002E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	5	EA	
002E	2556000000-E	846	SHOULDER BERM GUTTER	40	LF	
003C	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	230	LF	
0031	3030000000-E	862	STEEL BM GUARDRAIL	100	LF	
0032	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	2	EA	
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0034	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4	EA	
003E	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4	EA	

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	3635000000-E	876	RIP RAP, CLASS II	55 TON		
0037	3649000000-E	876	RIP RAP, CLASS B	8 TON		
003E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	560 SY		
003E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	58 LF		
004C	4078000000-E	903	SUPPORTS, 2-LB STEEL U-CHANNEL	3 EA		
0041	4102000000-N	904	SIGN ERECTION, TYPE E	9 EA		
0042	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	8 EA		
0043	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	407 SF		
0044	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
004E	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
004E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	7,480 LF		
0047	6000000000-E	1605	TEMPORARY SILT FENCE	1,170 LF		
004E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	135 TON		
004E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	165 TON		
005C	6012000000-E	1610	SEDIMENT CONTROL STONE	290 TON		
0051	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0052	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0053	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		
0054	6029000000-E	SP	SAFETY FENCE	250 LF		

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6030000000-E	1630	SILT EXCAVATION	660 CY		
005E	6036000000-E	1631	MATTING FOR EROSION CONTROL	720 SY		
0057	6042000000-E	1632	1/4" HARDWARE CLOTH	100 LF		
005E	6070000000-N	SP	SPECIAL STILLING BASINS	8 EA		
005E	6071030000-E	SP	COIR FIBER BAFFLES	260 LF		
006C	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
0061	6087000000-E	1660	MOWING	1 ACR		
0062	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0063	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0064	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
006E	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
006E	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0067	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		

***** BEGIN SCHEDULE AA *****
***** (3 ALTERNATES) *****

006E AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	320 LF		
-------------	--------------	-----	---------------------------------	-----------	--	--

*** OR ***

006E AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	248 LF		
-------------	--------------	-----	---------------------------------	-----------	--	--

007C AA2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	72 LF		
-------------	--------------	----	--	----------	--	--

*** OR ***

0071 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	248 LF		
-------------	--------------	-----	---------------------------------	-----------	--	--

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072 AA3	0536000000-E	SP	**** HDPE PIPE CULVERTS (15", 0.064")	72 LF		
***** END SCHEDULE AA *****						
STRUCTURE ITEMS						
0073	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (13+44.00-L-)	Lump Sum	L.S.	
0074	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (13+44.00-L-)	Lump Sum	L.S.	
0075	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	75 LF		
0076	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	33 LF		
0077	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	72 LF		
0078	8113000000-N	SP	SID INSPECTION	1 EA		
0079	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0080	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (13+44.00-L-)	Lump Sum	L.S.	
0081	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	4,296 SF		
0082	8161000000-E	420	GROOVING BRIDGE FLOORS	3,966 SF		
0083	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	105.7 CY		
0084	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (13+44.00-L-)	Lump Sum	L.S.	
0085	8217000000-E	425	REINFORCING STEEL (BRIDGE)	21,465 LB		

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	3,077 LB		
0087	8259000000-E	430	36" PRESTRESSED CONCRETE GIR- DERS	569.33 LF		
008E	8364000000-E	450	HP12X53 STEEL PILES	400 LF		
008E	8503000000-E	460	CONCRETE BARRIER RAIL	293.77 LF		
009C	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	509 TON		
0091	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	570 SY		
0092	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
009E	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1422/May30/Q51761.55/D400294710000/E93

Total Amount Of Bid For Entire Project :

Contract No **C201867**

County (ies): **McDowell**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General