

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+00.00)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	50 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	250 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	250 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	1,000 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,000 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	51 TON		
0011	0343000000-E	310	15" SIDE DRAIN PIPE	32 LF		
0012	0344000000-E	310	18" SIDE DRAIN PIPE	24 LF		
0013	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	80 LF		
0014	1220000000-E	545	INCIDENTAL STONE BASE	25 TON		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	805 TON		
0016	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	485 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	67 TON		
0018	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2000000000-N	806	RIGHT OF WAY MARKERS	25 EA		
0020	2022000000-E	815	SUBDRAIN EXCAVATION	115 CY		
0021	2033000000-E	815	SUBDRAIN FINE AGGREGATE	85 CY		
0022	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0023	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
0024	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0025	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0026	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5 EA		
0027	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2 EA		
0028	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0029	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	2 EA		
0030	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	130 LF		
0031	2556000000-E	846	SHOULDER BERM GUTTER	110 LF		
0032	3030000000-E	862	STEEL BM GUARDRAIL	325 LF		
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0034	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0035	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0036	3649000000-E	876	RIP RAP, CLASS B	285 TON		
0037	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,100 SY		

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	215	SF	
0039	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96	SF	
0040	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	126	SF	
0041	4430000000-N	1130	DRUMS	46	EA	
0042	4435000000-N	1135	CONES	25	EA	
0043	4445000000-E	1145	BARRICADES (TYPE III)	96	LF	
0044	4450000000-N	1150	FLAGGER	320	HR	
0045	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	16,660	LF	
0046	6000000000-E	1605	TEMPORARY SILT FENCE	1,725	LF	
0047	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	165	TON	
0048	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	190	TON	
0049	6012000000-E	1610	SEDIMENT CONTROL STONE	180	TON	
0050	6015000000-E	1615	TEMPORARY MULCHING	7.5	ACR	
0051	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	300	LB	
0052	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	2	TON	
0053	6024000000-E	1622	TEMPORARY SLOPE DRAINS	100	LF	
0054	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	3	EA	
0055	6029000000-E	SP	SAFETY FENCE	300	LF	
0056	6030000000-E	1630	SILT EXCAVATION	675	CY	

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,350	SY	
0058	6037000000-E	SP	COIR FIBER MAT	25	SY	
0059	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	800	SY	
0060	6042000000-E	1632	1/4" HARDWARE CLOTH	450	LF	
0061	6071030000-E	SP	COIR FIBER BAFFLES	200	LF	
0062	6071050000-E	SP	*** SKIMMER (1-1/2")	1	EA	
0063	6071050000-E	SP	*** SKIMMER (2")	2	EA	
0064	6084000000-E	1660	SEEDING & MULCHING	8	ACR	
0065	6087000000-E	1660	MOWING	4.5	ACR	
0066	6090000000-E	1661	SEED FOR REPAIR SEEDING	100	LB	
0067	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0068	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	200	LB	
0069	6108000000-E	1665	FERTILIZER TOPDRESSING	5.5	TON	
0070	6114000000-N	SP	SPECIALIZED HAND MOWING	2	HR	
0071	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	
0072	6123000000-E	1670	REFORESTATION	0.5	ACR	

***** BEGIN SCHEDULE AA *****
 ***** (3 ALTERNATES) *****

AA1	0073 0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	340	LF	
*** OR ***						
AA2	0074 0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	104	LF	

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	236 LF		
*** OR ***						
0076 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	104 LF		
0077 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	236 LF		
***** END SCHEDULE AA *****						
STRUCTURE ITEMS						
0078	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+20.00-L-)	Lump Sum	L.S.	
0079	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	5,198 SF		
0080	8161000000-E	420	GROOVING BRIDGE FLOORS	5,108 SF		
0081	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	71 CY		
0082	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+20.00-L-)	Lump Sum	L.S.	
0083	8217000000-E	425	REINFORCING STEEL (BRIDGE)	10,490 LB		
0084	8259000000-E	430	36" PRESTRESSED CONCRETE GIR- DERS	580.9 LF		
0085	8364000000-E	450	HP12X53 STEEL PILES	420 LF		
0086	8387000000-E	450	PP 18 X 0.50 GALVANIZED STEEL PILES	373 LF		
0087	8503000000-E	460	CONCRETE BARRIER RAIL	294.92 LF		
0088	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	186 TON		
0089	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	207 SY		
0090	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
1148/Jun10/Q55213.07/D376979230000/E91			Total Amount Of Bid For Entire Project :			

Contract No **C201871**

County (ies): **McDowell**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General