

County : New Hanover

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0005	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0006	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0007	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	525 TON		
0008	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	1,944 LF		
0009	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	168 LF		
0010	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	84 LF		
0011	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	12 LF		
0012	0995000000-E	340	PIPE REMOVAL	252 LF		
0013	1220000000-E	545	INCIDENTAL STONE BASE	250 TON		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,590 TON		
0015	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	1,290 TON		
0016	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	4,470 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	400 TON		
0018	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	200 TON		

County : New Hanover

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2022000000-E	815	SUBDRAIN EXCAVATION	22.4 CY		
0020	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8 CY		
0021	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0022	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0023	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0024	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0025	2190000000-N	828	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE	24 EA		
0026	2253000000-E	840	PIPE COLLARS	0.798 CY		
0027	2275000000-E	SP	FLOWABLE FILL	10 CY		
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	39 EA		
0029	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	9.74 LF		
0030	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	9 EA		
0031	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0032	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0033	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	3 EA		
0034	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	10 EA		
0035	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	13 EA		

County : New Hanover

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	2396000000-N	840	FRAME WITH COVER, STD 840.54	2 EA		
0037	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	3,710 LF		
0038	2591000000-E	848	4" CONCRETE SIDEWALK	2,630 SY		
0039	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	22 EA		
0040	2612000000-E	848	6" CONCRETE DRIVEWAY	470 SY		
0041	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	1,190 SY		
0042	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	1 EA		
0043	2830000000-N	858	ADJUSTMENT OF MANHOLES	9 EA		
0044	3030000000-E	862	STEEL BM GUARDRAIL	200 LF		
0045	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	62.5 LF		
0046	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0047	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	3 EA		
0048	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0049	3360000000-E	863	REMOVE EXISTING GUARDRAIL	245 LF		
0050	3536000000-E	866	CHAIN LINK FENCE, 48" FABRIC	200 LF		
0051	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	15 EA		
0052	3548000000-E	866	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	4 EA		
0053	3649000000-E	876	RIP RAP, CLASS B	10 TON		
0054	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	425 SY		

County : New Hanover

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	3984000000-E	SP	GENERIC WALL ITEM SOUND BARRIER WALL	1,262 SF		
0056	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	436 SF		
0057	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	852 SF		
0058	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	135 SF		
0059	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	3 EA		
0060	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	5 EA		
0061	4430000000-N	1130	DRUMS	250 EA		
0062	4435000000-N	1135	CONES	25 EA		
0063	4445000000-E	1145	BARRICADES (TYPE III)	216 LF		
0064	4450000000-N	1150	FLAGGER	1,800 HR		
0065	4480000000-N	1165	TMIA	3 EA		
0066	4510000000-N	SP	POLICE	300 HR		
0067	4516000000-N	1180	SKINNY DRUM	50 EA		
0068	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	44 EA		
0069	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	23,545 LF		
0070	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	2,009 LF		
0071	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	477 LF		
0072	4840000000-N	1205	PAINT PAVEMENT MARKING CHARAC- TER	24 EA		
0073	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	78 EA		

County : New Hanover

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4" *****) (STANDARD GLASS BEADS)	13,023	LF	
0075	4847110000-E	1205	POLYUREA PAVEMENT MARKING LINES (8" *****) (STANDARD GLASS BEADS)	1,909	LF	
0076	4847140000-E	1205	POLYUREA PAVEMENT MARKING LINES (24" *****) (STANDARD GLASS BEADS)	877	LF	
0077	4847200000-N	1205	POLYUREA PAVEMENT MARKING CHARACTER (*****) (STANDARD GLASS BEADS)	24	EA	
0078	4847220000-N	1205	POLYUREA PAVEMENT MARKING SYMBOL (*****) (STANDARD GLASS BEADS)	80	EA	
0079	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	7,655	LF	
0080	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	625	LF	
0081	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	324	LF	
0082	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	43	EA	
0083	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	30	EA	
0084	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	330	EA	
0085	5325200000-E	1510	2" WATER LINE	163.9	LF	
0086	5325600000-E	1510	6" WATER LINE	195.7	LF	
0087	5325800000-E	1510	8" WATER LINE	666.1	LF	
0088	5326200000-E	1510	12" WATER LINE	178.5	LF	
0089	5326600000-E	1510	16" WATER LINE	1,951.3	LF	
0090	5536000000-E	1515	2" VALVE	3	EA	

County : New Hanover

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	5540000000-E	1515	6" VALVE	3 EA		
0092	5546000000-E	1515	8" VALVE	4 EA		
0093	5558000000-E	1515	12" VALVE	3 EA		
0094	5558600000-E	1515	16" VALVE	10 EA		
0095	5648000000-N	1515	RELOCATE WATER METER	18 EA		
0096	5666000000-E	1515	FIRE HYDRANT	1 EA		
0097	5672000000-N	1515	RELOCATE FIRE HYDRANT	8 EA		
0098	5775000000-E	1525	4' DIA UTILITY MANHOLE	23 EA		
0099	5781000000-E	1525	UTILITY MANHOLE WALL, 4' DIA	39 LF		
0100	5800000000-E	1530	ABANDON 6" UTILITY PIPE	264 LF		
0101	5801000000-E	1530	ABANDON 8" UTILITY PIPE	1,745 LF		
0102	5804000000-E	1530	ABANDON 12" UTILITY PIPE	1,052 LF		
0103	5810000000-E	1530	ABANDON 16" UTILITY PIPE	952 LF		
0104	5816000000-N	1530	ABANDON UTILITY MANHOLE	13 EA		
0105	5835800000-E	1540	18" ENCASEMENT PIPE	284.6 LF		
0106	5836000000-E	1540	24" ENCASEMENT PIPE	91.2 LF		
0107	5836200000-E	1540	30" ENCASEMENT PIPE	256.2 LF		
0108	5872000000-E	1550	TRENCHLESS INSTALLATION OF 18" IN SOIL	142.3 LF		
0109	5872010000-E	1550	TRENCHLESS INSTALLATION OF 18" NOT IN SOIL	142.3 LF		
0110	5872200000-E	1550	TRENCHLESS INSTALLATION OF 24" IN SOIL	45.6 LF		

County : New Hanover

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0111	5872210000-E	1550	TRENCHLESS INSTALLATION OF 24" NOT IN SOIL	45.6 LF		
0112	5872300000-E	1550	TRENCHLESS INSTALLATION OF 30" IN SOIL	128.1 LF		
0113	5872310000-E	1550	TRENCHLESS INSTALLATION OF 30" NOT IN SOIL	128.1 LF		
0114	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE SANITARY SEWER CLEANOUT	10 EA		
0115	5888000000-E	SP	GENERIC UTILITY ITEM 16" PVC WATER PIPE (C905), DR18	369 LF		
0116	5888000000-E	SP	GENERIC UTILITY ITEM 8" DI SEWER PIPE, PC 350	1,132.7 LF		
0117	5888000000-E	SP	GENERIC UTILITY ITEM 8" PVC GRAVITY SEWER PIPE, (C900), DR 18	1,013 LF		
0118	6000000000-E	1605	TEMPORARY SILT FENCE	2,150 LF		
0119	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	125 TON		
0120	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	110 TON		
0121	6012000000-E	1610	SEDIMENT CONTROL STONE	300 TON		
0122	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0123	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0124	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0125	6030000000-E	1630	SILT EXCAVATION	2,650 CY		
0126	6036000000-E	1631	MATTING FOR EROSION CONTROL	475 SY		
0127	6037000000-E	SP	COIR FIBER MAT	10 SY		

County : New Hanover

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0128	6042000000-E	1632	1/4" HARDWARE CLOTH	1,325	LF	
0129	6071030000-E	SP	COIR FIBER BAFFLES	60	LF	
0130	6084000000-E	1660	SEEDING & MULCHING	0.5	ACR	
0131	6087000000-E	1660	MOWING	0.5	ACR	
0132	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0133	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0134	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0135	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25	TON	
0136	6114000000-N	SP	SPECIALIZED HAND MOWING	2	HR	
0137	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	
0138	7000000000-E	1705	PEDESTRIAN SIGNAL HEAD (***, ** SECTION) (16", 1 SECT WITH COUNTDOWN)	4	EA	
0139	7060000000-E	1705	SIGNAL CABLE	6,480	LF	
0140	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	42	EA	
0141	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	9	EA	
0142	7252000000-E	1710	MESSENGER CABLE (1/4")	1,280	LF	
0143	7264000000-E	1710	MESSENGER CABLE (3/8")	1,160	LF	
0144	7279000000-E	1715	TRACER WIRE	455	LF	
0145	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2")	1,910	LF	
0146	7301000000-E	1715	DIRECTIONAL DRILL (***** (1, 2")	455	LF	

County : New Hanover

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0147	7301000000-E	1715	DIRECTIONAL DRILL (***** (2, 2")	860 LF		
0148	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	22 EA		
0149	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEAVY DUTY)	8 EA		
0150	7360000000-N	1720	WOOD POLE	8 EA		
0151	7372000000-N	1721	GUY ASSEMBLY	20 EA		
0152	7432000000-E	1722	2" RISER WITH HEAT SHRINK TUBING	3 EA		
0153	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	3,525 LF		
0154	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	5,045 LF		
0155	7481000000-N	SP	SITE SURVEY	2 EA		
0156	7481200000-N	SP	LUMINAIRE ARM FOR VIDEO SYSTEM	8 EA		
0157	7481240000-N	SP	CAMERA WITHOUT INTERNAL LOOP EMULATOR PROCESSING UNIT	8 EA		
0158	7481260000-N	SP	EXTERNAL LOOP EMULATOR PROCESSING UNIT	2 EA		
0159	7516000000-E	1730	COMMUNICATIONS CABLE (**FIBER) (24)	1,610 LF		
0160	7566000000-N	1733	DELINEATOR MARKER	8 EA		
0161	7568000000-N	SP	FURNISH FIBER-OPTIC RESTORATION KIT	1 EA		
0162	7570000000-N	SP	FURNISH FIBER-OPTIC POWER METER	1 EA		
0163	7572000000-N	SP	FURNISH OPTICAL LIGHT GENERATOR	1 EA		
0164	7575142000-N	SP	900MHZ WIRELESS RADIO SYSTEM	2 EA		

County : New Hanover

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0165	7588000000-N	SP	METAL POLE WITH SINGLE MAST ARM	3 EA		
0166	7590000000-N	SP	METAL POLE WITH DUAL MAST ARM	2 EA		
0167	7613000000-N	SP	SOIL TEST	6 EA		
0168	7614100000-E	SP	DRILLED PIER FOUNDATION	46 CY		
0169	7624000000-N	1743	SIGNAL PEDESTAL WITH FOUNDATION	2 EA		
0170	7631000000-N	SP	MAST ARM WITH METAL POLE DESIGN	5 EA		
0171	7636000000-N	1745	SIGN FOR SIGNALS	3 EA		
0172	7684000000-N	1750	SIGNAL CABINET FOUNDATION	2 EA		
0173	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	2 EA		
0174	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	24 EA		
0175	7901000000-N	1753	CABINET BASE EXTENDER	2 EA		
0176	7960000000-N	SP	METAL POLE FOUNDATION REMOVAL	7 EA		
0177	7972000000-N	SP	METAL POLE REMOVAL	6 EA		
0178	7980000000-N	SP	GENERIC SIGNAL ITEM ANTENNA TRANSFER	2 EA		
0179	7980000000-N	SP	GENERIC SIGNAL ITEM FURNISH WIRELESS RADIO LIGHTNING ARRESTOR	2 EA		
0180	7980000000-N	SP	GENERIC SIGNAL ITEM FURNISH WIRELESS RADIO MODEM	1 EA		
0181	7980000000-N	SP	GENERIC SIGNAL ITEM POWER COAT FOR DUAL MAST ARM W/ METAL POLE	2 EA		
0182	7980000000-N	SP	GENERIC SIGNAL ITEM POWER COAT FOR SINGLE MAST ARM W/ METAL POLE	3 EA		

County : New Hanover

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0183	7980000000-N	SP	GENERIC SIGNAL ITEM RELOCATE EXISTING METAL POLE	1 EA		

1044/Jun10/Q118900.688/D904374772000/E183

Total Amount Of Bid For Entire Project :

Contract No **C201847**

County (ies): **New Hanover**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General