

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (18+10.00)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	220 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	10 TON		
0010	0344000000-E	310	18" SIDE DRAIN PIPE	48 LF		
0011	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	32 LF		
0012	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0013	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	450 TON		
0015	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	275 TON		
0016	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	350 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	55 TON		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2000000000-N	806	RIGHT OF WAY MARKERS	8 EA		
001E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
002C	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0021	2556000000-E	846	SHOULDER BERM GUTTER	70 LF		
0022	3030000000-E	862	STEEL BM GUARDRAIL	487.5 LF		
0023	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50 LF		
0024	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
002E	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
002E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0027	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
002E	3649000000-E	876	RIP RAP, CLASS B	95 TON		
002E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	365 SY		
003C	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	421 SF		
0031	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	128 SF		
0032	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	114 SF		
0033	4435000000-N	1135	CONES	50 EA		
0034	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
003E	4450000000-N	1150	FLAGGER	160 HR		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	31,200	LF	
0037	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	14	EA	
003E	6000000000-E	1605	TEMPORARY SILT FENCE	225	LF	
003E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75	TON	
004C	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	150	TON	
0041	6012000000-E	1610	SEDIMENT CONTROL STONE	30	TON	
0042	6015000000-E	1615	TEMPORARY MULCHING	1.5	ACR	
0043	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0044	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25	TON	
004E	6029000000-E	SP	SAFETY FENCE	275	LF	
004E	6030000000-E	1630	SILT EXCAVATION	665	CY	
0047	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,000	SY	
004E	6037000000-E	SP	COIR FIBER MAT	50	SY	
004E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	745	SY	
005C	6042000000-E	1632	1/4" HARDWARE CLOTH	40	LF	
0051	6071030000-E	SP	COIR FIBER BAFFLES	260	LF	
0052	6071050000-E	SP	*** SKIMMER (1-1/2")	8	EA	
0053	6084000000-E	1660	SEEDING & MULCHING	2.5	ACR	

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6087000000-E	1660	MOWING	1 ACR		
005E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
005E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0057	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
005E	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
005E	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
006C	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
STRUCTURE ITEMS						
0061	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18 + 10.00-L-)	Lump Sum	L.S.	
0062	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (18 + 10.00-L-)	Lump Sum	L.S.	
0063	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	3,072 SF		
0064	8161000000-E	420	GROOVING BRIDGE FLOORS	3,419 SF		
006E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	36.6 CY		
006E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18 + 10.00-L-)	Lump Sum	L.S.	
0067	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,334 LB		
006E	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	86,500 LS		
006E	8364000000-E	450	HP12X53 STEEL PILES	270 LF		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007C	8503000000-E	460	CONCRETE BARRIER RAIL	156.54 LF		
0071	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	261 TON		
0072	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	290 SY		
0073	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
1508/Jun03/Q139079.14/D329308180000/E73			Total Amount Of Bid For Entire Project :			

Contract No **C201873**

County (ies): **Randolph**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General