

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (BRIDGE #100)	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (BRIDGE #162)	Lump Sum	L.S.	
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (BRIDGE #54)	Lump Sum	L.S.	
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	921 LF		
0007	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	38 EA		
0008	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0009	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 2")	1,620 SY		
0010	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	690 TON		
0011	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	780 TON		
0012	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,240 TON		
0013	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	201 TON		
0014	2264000000-E	840	PIPE PLUGS	2.1 CY		
0015	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	32 EA		
0016	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0017	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	28 EA		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	2556000000-E	846	SHOULDER BERM GUTTER	1,390 LF		
0019	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	90 SY		
0020	3030000000-E	862	STEEL BM GUARDRAIL	6,050 LF		
0021	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	62.5 LF		
0022	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0023	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (BP)	12 EA		
0024	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0025	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	15 EA		
0026	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0027	3345000000-E	864	REMOVE & RESET EXISTING GUARD- RAIL	2,800 LF		
0028	3360000000-E	863	REMOVE EXISTING GUARDRAIL	2,787.5 LF		
0029	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	2,275 SF		
0030	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	602 SF		
0031	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	126 SF		
0032	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0033	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
0034	4430000000-N	1130	DRUMS	410 EA		
0035	4435000000-N	1135	CONES	50 EA		
0036	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4450000000-N	1150	FLAGGER	480 HR		
0038	4480000000-N	1165	TMIA	1 EA		
0039	4507000000-E	SP	WATER FILLED BARRIER	40 LF		
0040	4508000000-E	SP	RESET WATER FILLED BARRIER	200 LF		
0041	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0042	6084000000-E	1660	SEEDING & MULCHING	1.6 ACR		
STRUCTURE ITEMS						
0043	8161000000-E	420	GROOVING BRIDGE FLOORS	16,571 SF		
0044	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	179.3 CY		
0045	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (BRIDGE #100)	Lump Sum	L.S.	
0046	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (BRIDGE #162)	Lump Sum	L.S.	
0047	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (BRIDGE #54)	Lump Sum	L.S.	
0048	8217000000-E	425	REINFORCING STEEL (BRIDGE)	24,884 LB		
0049	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	14,794 LS		
0050	8503000000-E	460	CONCRETE BARRIER RAIL	539 LF		
0051	8538000000-E	SP	CLASS I, SURFACE PREPARATION	1,906 SY		
0052	8559000000-E	SP	CLASS II, SURFACE PREPARATION	142 SY		
0053	8573000000-E	SP	LATEX MODIFIED CONC OVERLAY	64.8 CY		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	8580000000-E	SP	PLACING & FINISHING OF LATEX MODIFIED CONC OVERLAY	1,863 SY		
0055	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0056	8678000000-E	SP	EPOXY RESIN INJECTION	260 LF		
0057	8685000000-E	SP	EPOXY MORTAR REPAIRS	49 SF		
0058	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0059	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	3,861.74 LF		
0060	8860000000-N	SP	GENERIC STRUCTURE ITEM BRIDGE JACKING (BRIDGE #100)	Lump Sum	L.S.	
0061	8860000000-N	SP	GENERIC STRUCTURE ITEM BRIDGE JACKING (BRIDGE #54)	Lump Sum	L.S.	
0062	8860000000-N	SP	GENERIC STRUCTURE ITEM PARTIAL REMOVAL OF EXISTING STRUCTURE (BRIDGE #100)	Lump Sum	L.S.	
0063	8860000000-N	SP	GENERIC STRUCTURE ITEM PARTIAL REMOVAL OF EXISTING STRUCTURE (BRIDGE #151)	Lump Sum	L.S.	
0064	8860000000-N	SP	GENERIC STRUCTURE ITEM PARTIAL REMOVAL OF EXISTING STRUCTURE (BRIDGE #162)	Lump Sum	L.S.	
0065	8860000000-N	SP	GENERIC STRUCTURE ITEM PARTIAL REMOVAL OF EXISTING STRUCTURE (BRIDGE #167)	Lump Sum	L.S.	
0066	8860000000-N	SP	GENERIC STRUCTURE ITEM PARTIAL REMOVAL OF EXISTING STRUCTURE (BRIDGE #169)	Lump Sum	L.S.	
0067	8860000000-N	SP	GENERIC STRUCTURE ITEM PARTIAL REMOVAL OF EXISTING STRUCTURE (BRIDGE #54)	Lump Sum	L.S.	
0068	8867000000-E	SP	GENERIC STRUCTURE ITEM CONCRETE BRIDGE RAIL	319.25 LF		

Contract No **C202079**

County (ies): **Robeson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General