

County : Robeson, Cumberland, Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (BRIDGE #100)	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (BRIDGE #155)	Lump Sum	L.S.	
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (BRIDGE #162)	Lump Sum	L.S.	
0005	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (BRIDGE #54)	Lump Sum	L.S.	
0006	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (BRIDGE #81)	Lump Sum	L.S.	
0007	0043000000-N	226	GRADING	Lump Sum	L.S.	
0008	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	1,466 LF		
0009	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	64 EA		
0010	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0011	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO *****" DEPTH (0" TO 2")	2,700 SY		
0012	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	4,420 TON		
0013	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	2,090 TON		
0014	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	4,290 TON		
0015	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	546 TON		

County : Robeson, Cumberland, Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0016	2264000000-E	840	PIPE PLUGS	4.2 CY		
0017	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	48 EA		
001E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
001E	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	44 EA		
002C	2556000000-E	846	SHOULDER BERM GUTTER	1,607 LF		
0021	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	90 SY		
0022	3030000000-E	862	STEEL BM GUARDRAIL	9,425 LF		
002E	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	250 LF		
0024	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	20 EA		
002E	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (BP)	20 EA		
002E	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	4 EA		
0027	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	28 EA		
002E	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
002E	3345000000-E	864	REMOVE & RESET EXISTING GUARD- RAIL	2,800 LF		
003C	3360000000-E	863	REMOVE EXISTING GUARDRAIL	5,037.5 LF		
0031	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	4,314 SF		
0032	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	996 SF		

County : Robeson, Cumberland, Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0033	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	220 SF		
0034	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	3 EA		
0035	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	5 EA		
0036	4430000000-N	1130	DRUMS	659 EA		
0037	4435000000-N	1135	CONES	100 EA		
0038	4445000000-E	1145	BARRICADES (TYPE III)	176 LF		
0039	4450000000-N	1150	FLAGGER	520 HR		
0040	4480000000-N	1165	TMIA	2 EA		
0041	4507000000-E	SP	WATER FILLED BARRIER	80 LF		
0042	4508000000-E	SP	RESET WATER FILLED BARRIER	320 LF		
0043	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0044	6084000000-E	1660	SEEDING & MULCHING	3.1 ACR		
<b>STRUCTURE ITEMS</b>						
0045	8161000000-E	420	GROOVING BRIDGE FLOORS	16,571 SF		
0046	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	296.3 CY		
0047	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (BRIDGE #100)	Lump Sum	L.S.	
0048	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (BRIDGE #155)	Lump Sum	L.S.	

County : Robeson, Cumberland, Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0049	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (BRIDGE #162)	Lump Sum	L.S.	
0050	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (BRIDGE #54)	Lump Sum	L.S.	
0051	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (BRIDGE #81)	Lump Sum	L.S.	
0052	8217000000-E	425	REINFORCING STEEL (BRIDGE)	40,754 LB		
0053	8280000000-E	440	APPROX ..... LBS STRUCTURAL STEEL	38,904 LS		
0054	8503000000-E	460	CONCRETE BARRIER RAIL	539 LF		
0055	8538000000-E	SP	CLASS I, SURFACE PREPARATION	1,906 SY		
0056	8559000000-E	SP	CLASS II, SURFACE PREPARATION	142 SY		
0057	8573000000-E	SP	LATEX MODIFIED CONC OVERLAY	64.8 CY		
0058	8580000000-E	SP	PLACING & FINISHING OF LATEX MODIFIED CONC OVERLAY	1,863 SY		
0059	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0060	8678000000-E	SP	EPOXY RESIN INJECTION	478 LF		
0061	8685000000-E	SP	EPOXY MORTAR REPAIRS	59 SF		
0062	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0063	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	6,201.74 LF		
0064	8860000000-N	SP	GENERIC STRUCTURE ITEM BRIDGE JACKING (BRIDGE #100)	Lump Sum	L.S.	
0065	8860000000-N	SP	GENERIC STRUCTURE ITEM BRIDGE JACKING (BRIDGE #155)	Lump Sum	L.S.	

County : Robeson, Cumberland, Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
006E	8860000000-N	SP	GENERIC STRUCTURE ITEM BRIDGE JACKING (BRIDGE #54)	Lump Sum	L.S.	
0067	8860000000-N	SP	GENERIC STRUCTURE ITEM BRIDGE JACKING (BRIDGE #81)	Lump Sum	L.S.	
006E	8860000000-N	SP	GENERIC STRUCTURE ITEM PARTIAL REMOVAL OF EXISTING ST RUCTURE (BRIDGE #100)	Lump Sum	L.S.	
006E	8860000000-N	SP	GENERIC STRUCTURE ITEM PARTIAL REMOVAL OF EXISTING ST RUCTURE (BRIDGE #151)	Lump Sum	L.S.	
007C	8860000000-N	SP	GENERIC STRUCTURE ITEM PARTIAL REMOVAL OF EXISTING ST RUCTURE (BRIDGE #153)	Lump Sum	L.S.	
0071	8860000000-N	SP	GENERIC STRUCTURE ITEM PARTIAL REMOVAL OF EXISTING ST RUCTURE (BRIDGE #154)	Lump Sum	L.S.	
0072	8860000000-N	SP	GENERIC STRUCTURE ITEM PARTIAL REMOVAL OF EXISTING ST RUCTURE (BRIDGE #155)	Lump Sum	L.S.	
0073	8860000000-N	SP	GENERIC STRUCTURE ITEM PARTIAL REMOVAL OF EXISTING ST RUCTURE (BRIDGE #162)	Lump Sum	L.S.	
0074	8860000000-N	SP	GENERIC STRUCTURE ITEM PARTIAL REMOVAL OF EXISTING ST RUCTURE (BRIDGE #167)	Lump Sum	L.S.	
007E	8860000000-N	SP	GENERIC STRUCTURE ITEM PARTIAL REMOVAL OF EXISTING ST RUCTURE (BRIDGE #169)	Lump Sum	L.S.	
007E	8860000000-N	SP	GENERIC STRUCTURE ITEM PARTIAL REMOVAL OF EXISTING ST RUCTURE (BRIDGE #54)	Lump Sum	L.S.	

County : Robeson, Cumberland, Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0077	8860000000-N	SP	GENERIC STRUCTURE ITEM PARTIAL REMOVAL OF EXISTING ST RUCTURE (BRIDGE #81)	Lump Sum	L.S.	
007E	8867000000-E	SP	GENERIC STRUCTURE ITEM CONCRETE BRIDGE RAIL	788.25 LF		
1527/Jun12/Q151055.89/D411376100000/E78			Total Amount Of Bid For Entire Project :			

**Contract No**     **C202118**

**County (ies):**    **Robeson, Harnett, Cumberland**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General