

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (21 + 68.50)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	400 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	1,000 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,000 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	30 TON		
0009	0343000000-E	310	15" SIDE DRAIN PIPE	36 LF		
0010	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	108 LF		
0011	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	36 LF		
0012	0995000000-E	340	PIPE REMOVAL	126 LF		
0013	1121000000-E	520	AGGREGATE BASE COURSE	1,200 TON		
0014	1220000000-E	545	INCIDENTAL STONE BASE	30 TON		
0015	1275000000-E	600	PRIME COAT	878.5 GAL		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	390 TON		
0017	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	330 TON		
0018	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	860 TON		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	84 TON		
002C	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	20 TON		
0021	2000000000-N	806	RIGHT OF WAY MARKERS	10 EA		
0022	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
0023	2033000000-E	815	SUBDRAIN FINE AGGREGATE	34 CY		
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
002E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
002E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0027	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
002E	2253000000-E	840	PIPE COLLARS	0.6 CY		
0029	2264000000-E	840	PIPE PLUGS	0.1 CY		
003C	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0031	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	1 EA		
0032	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0033	2556000000-E	846	SHOULDER BERM GUTTER	33 LF		
0034	3030000000-E	862	STEEL BM GUARDRAIL	575 LF		
003E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
003E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4	EA	
003E	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	825	LF	
003E	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)	4	EA	
004C	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	6	EA	
0041	3635000000-E	876	RIP RAP, CLASS II	85	TON	
0042	3649000000-E	876	RIP RAP, CLASS B	10	TON	
004E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	315	SY	
0044	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1	EA	
004E	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	9	SF	
004E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	15	LF	
0047	4102000000-N	904	SIGN ERECTION, TYPE E	1	EA	
004E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	7	EA	
004E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	48	SF	
005C	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96	SF	
0051	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	40	SF	
0052	4430000000-N	1130	DRUMS	70	EA	
005E	4435000000-N	1135	CONES	30	EA	
0054	4445000000-E	1145	BARRICADES (TYPE III)	72	LF	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	4450000000-N	1150	FLAGGER	80	HR	
005E	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	40	EA	
0057	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,600	LF	
005E	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,600	LF	
005E	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	440	LF	
006C	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	22,400	LF	
0061	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	500	LF	
0062	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	20	EA	
006E	6000000000-E	1605	TEMPORARY SILT FENCE	1,620	LF	
0064	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	90	TON	
006E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	540	TON	
006E	6012000000-E	1610	SEDIMENT CONTROL STONE	240	TON	
0067	6015000000-E	1615	TEMPORARY MULCHING	2.5	ACR	
006E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
006E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5	TON	
007C	6029000000-E	SP	SAFETY FENCE	250	LF	
0071	6030000000-E	1630	SILT EXCAVATION	1,620	CY	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,260	SY	
0073	6042000000-E	1632	1/4" HARDWARE CLOTH	250	LF	
0074	6071030000-E	SP	COIR FIBER BAFFLES	370	LF	
0075	6084000000-E	1660	SEEDING & MULCHING	3	ACR	
0076	6087000000-E	1660	MOWING	1.5	ACR	
0077	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0078	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0079	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0080	6108000000-E	1665	FERTILIZER TOPDRESSING	2	TON	
0081	6114000000-N	SP	SPECIALIZED HAND MOWING	4.5	HR	
0082	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	27	EA	
0083	6123000000-E	1670	REFORESTATION	1	ACR	

\*\*\*\*\* BEGIN SCHEDULE AA \*\*\*\*\*  
 \*\*\*\*\* ( 3 ALTERNATES ) \*\*\*\*\*

0084	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	84	LF	
AA1						

\*\*\* OR \*\*\*

0085	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	76	LF	
AA2						

0086	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	8	LF	
AA2						

\*\*\* OR \*\*\*

0087	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	76	LF	
AA3						

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	8 LF		

\*\*\*\*\* END SCHEDULE AA \*\*\*\*\*

STRUCTURE ITEMS

008S	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (21 + 68.50-L-)	Lump Sum	L.S.	
009C	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (21 + 68.50-L-)	Lump Sum	L.S.	
0091	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (21 + 68.50-L-)	Lump Sum	L.S.	
0092	8156000000-E	SP	CONCRETE WEARING SURFACE	3,568 SF		
0093	8161000000-E	420	GROOVING BRIDGE FLOORS	4,821 SF		
0094	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	44.9 CY		
009E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (21 + 68.50-L-)	Lump Sum	L.S.	
009E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,688 LB		
0097	8364000000-E	450	HP12X53 STEEL PILES	680 LF		
009E	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	270 LF		
009E	8393000000-N	450	PILE REDRIVES	12 EA		
010C	8475000000-E	460	TWO BAR METAL RAIL	180.5 LF		
0101	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 2'-11 1/4")	195.5 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0102	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	465 TON		
0103	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	510 SY		
0104	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0105	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0106	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,269.14 LF		

1051/Jun10/Q63220.49/D440987430000/E106

Total Amount Of Bid For Entire Project :

**Contract No**     **C201830**

**County (ies):**   **Wake**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General