

County : Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+87.50)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	300 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	2,700 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	182 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	250 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	250 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	166 TON		
0012	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	400 LF		
0013	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	296 LF		
0014	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	108 LF		
0015	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	44 LF		
0016	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	44 LF		
0017	0995000000-E	340	PIPE REMOVAL	62 LF		
0018	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		

County : Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	500 TON		
002C	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	350 TON		
0021	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	350 TON		
0022	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	65 TON		
0023	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	150 TON		
0024	2264000000-E	840	PIPE PLUGS	0.13 CY		
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	15 EA		
002E	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	0.2 LF		
0027	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	4 EA		
002E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	3 EA		
0029	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	3 EA		
003C	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	4 EA		
0031	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0032	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	1,000 LF		
0033	2591000000-E	848	4" CONCRETE SIDEWALK	605 SY		
0034	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	3 EA		
003E	2612000000-E	848	6" CONCRETE DRIVEWAY	60 SY		

County : Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	3030000000-E	862	STEEL BM GUARDRAIL	112.5 LF		
0037	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	62.5 LF		
003E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
003E	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
004C	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0041	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0042	3566000000-E	867	WOVEN WIRE FENCE RESET	200 LF		
0043	3628000000-E	876	RIP RAP, CLASS I	85 TON		
0044	3649000000-E	876	RIP RAP, CLASS B	80 TON		
004E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	475 SY		
004E	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	15.25 SF		
0047	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	46 LF		
004E	4102000000-N	904	SIGN ERECTION, TYPE E	2 EA		
004E	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	3 EA		
005C	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	8 EA		
0051	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	1 EA		
0052	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	279 SF		
0053	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	64 SF		

County : Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94	SF	
0055	4430000000-N	1130	DRUMS	15	EA	
0056	4435000000-N	1135	CONES	15	EA	
0057	4445000000-E	1145	BARRICADES (TYPE III)	64	LF	
005E	4450000000-N	1150	FLAGGER	240	HR	
005E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	4,700	LF	
006C	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	26	LF	
0061	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	100	LF	
0062	5326200000-E	1510	12" WATER LINE	665	LF	
0063	5558000000-E	1515	12" VALVE	2	EA	
0064	5648000000-N	1515	RELOCATE WATER METER	3	EA	
006E	5691700000-E	1520	18" SANITARY GRAVITY SEWER	118	LF	
006E	5804000000-E	1530	ABANDON 12" UTILITY PIPE	600	LF	
0067	6000000000-E	1605	TEMPORARY SILT FENCE	480	LF	
006E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	105	TON	
006E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	75	TON	
007C	6012000000-E	1610	SEDIMENT CONTROL STONE	115	TON	
0071	6015000000-E	1615	TEMPORARY MULCHING	1	ACR	
0072	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	

County : Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25	TON	
0074	6024000000-E	1622	TEMPORARY SLOPE DRAINS	90	LF	
0075	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2	EA	
0076	6029000000-E	SP	SAFETY FENCE	320	LF	
0077	6030000000-E	1630	SILT EXCAVATION	330	CY	
0078	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,120	SY	
0079	6037000000-E	SP	COIR FIBER MAT	25	SY	
0080	6042000000-E	1632	1/4" HARDWARE CLOTH	300	LF	
0081	6071030000-E	SP	COIR FIBER BAFFLES	115	LF	
0082	6071050000-E	SP	*** SKIMMER (1-1/2")	4	EA	
0083	6084000000-E	1660	SEEDING & MULCHING	1.5	ACR	
0084	6087000000-E	1660	MOWING	1	ACR	
0085	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0086	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0087	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0088	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75	TON	
0089	6114000000-N	SP	SPECIALIZED HAND MOWING	2	HR	
0090	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	

County : Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0091	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17 + 87.50-EL-)	Lump Sum	L.S.	
0092	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVATION	749 CY		
0093	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	4,358 SF		
0094	8161000000-E	420	GROOVING BRIDGE FLOORS	3,316 SF		
0095	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	54 CY		
0096	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17 + 87.50-EL-)	Lump Sum	L.S.	
0097	8217000000-E	425	REINFORCING STEEL (BRIDGE)	7,623 LB		
0098	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	130,400 LS		
0099	8364000000-E	450	HP12X53 STEEL PILES	500 LF		
0100	8433000000-E	SP	*** STEEL SHEET PILES (18")	1,802 SF		
0101	8482000000-E	460	THREE BAR METAL RAIL	181.22 LF		
0102	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	207 TON		
0103	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	231 SY		
0104	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
<hr/> <p>0955/Jul07/Q169183.55/D436122580000/E104 Total Amount Of Bid For Entire Project :</p>						

Contract No **C201836**

County (ies): **Catawba**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General