

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	75 TON		
0006	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	548 LF		
0007	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	132 LF		
0008	1220000000-E	545	INCIDENTAL STONE BASE	20 TON		
0009	1330000000-E	607	INCIDENTAL MILLING	100 SY		
001C	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	7,200 TON		
0011	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	2,875 TON		
0012	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	7,050 TON		
0013	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	445 TON		
0014	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	425 TON		
0015	2264000000-E	840	PIPE PLUGS	0.2 CY		
001E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	8 EA		
0017	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	2 LF		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	7 EA		
001E	2396000000-N	840	FRAME WITH COVER, STD 840.54	4 EA		
002C	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	2,630 SY		
0021	2905000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX	5 EA		
0022	3030000000-E	862	STEEL BM GUARDRAIL	250 LF		
0023	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	62.5 LF		
0024	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
002E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	1 EA		
002E	3360000000-E	863	REMOVE EXISTING GUARDRAIL	361 LF		
0027	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	400 SF		
002E	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (F)	210 SF		
002E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	1,300 LF		
003C	4102000000-N	904	SIGN ERECTION, TYPE E	62 EA		
0031	4108000000-N	904	SIGN ERECTION, TYPE F	12 EA		
0032	4154000000-N	907	STOCKPILE SIGN SYSTEM, U-CHANNEL	37 EA		
003E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	80 SF		
0034	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	503 SF		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	64	SF	
003E	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2	EA	
0037	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2	EA	
003E	4430000000-N	1130	DRUMS	239	EA	
003E	4445000000-E	1145	BARRICADES (TYPE III)	32	LF	
004C	4480000000-N	1165	TMIA	2	EA	
0041	4510000000-N	SP	POLICE	50	HR	
0042	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	36,950	LF	
004E	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	11,650	LF	
0044	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	550	LF	
004E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	36	EA	
004E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	15,279	LF	
0047	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	460	LF	
004E	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	21	EA	
004E	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	5,200	LF	
005C	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	250	LF	
0051	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	350	EA	
0052	6000000000-E	1605	TEMPORARY SILT FENCE	900	LF	

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	5	TON	
0054	6012000000-E	1610	SEDIMENT CONTROL STONE	50	TON	
005E	6030000000-E	1630	SILT EXCAVATION	130	CY	
0056	6042000000-E	1632	1/4" HARDWARE CLOTH	630	LF	
0057	6084000000-E	1660	SEEDING & MULCHING	7	ACR	
005E	6090000000-E	1661	SEED FOR REPAIR SEEDING	300	LB	
005E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5	TON	
006C	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	900	LB	
0061	6108000000-E	1665	FERTILIZER TOPDRESSING	25	TON	

0840/Jun30/Q98898.2/D217262500000/E61

Total Amount Of Bid For Entire Project :

**Contract No**     **C201845**

**County (ies):**   **Cumberland**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General