

County : Gaston

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|---|------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0029000000-N | SP | REINFORCED BRIDGE APPROACH FILL, STATION ***** (14+57.00) | Lump Sum | L.S. | |
| 0003 | 0043000000-N | 226 | GRADING | Lump Sum | L.S. | |
| 0004 | 0050000000-E | 226 | SUPPLEMENTARY CLEARING & GRUB- BING | 1 ACR | | |
| 0005 | 0057000000-E | 226 | UNDERCUT EXCAVATION | 700 CY | | |
| 0006 | 0134000000-E | 240 | DRAINAGE DITCH EXCAVATION | 100 CY | | |
| 0007 | 0195000000-E | 265 | SELECT GRANULAR MATERIAL | 750 CY | | |
| 0008 | 0196000000-E | 270 | FABRIC FOR SOIL STABILIZATION | 500 SY | | |
| 0009 | 0318000000-E | 300 | FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS | 20 TON | | |
| 0010 | 0372000000-E | 310 | 18" RC PIPE CULVERTS, CLASS III | 48 LF | | |
| 0011 | 0378000000-E | 310 | 24" RC PIPE CULVERTS, CLASS III | 116 LF | | |
| 0012 | 0995000000-E | 340 | PIPE REMOVAL | 48 LF | | |
| 0013 | 1121000000-E | 520 | AGGREGATE BASE COURSE | 400 TON | | |
| 0014 | 1220000000-E | 545 | INCIDENTAL STONE BASE | 100 TON | | |
| 0015 | 1275000000-E | 600 | PRIME COAT | 220 GAL | | |
| 0016 | 1489000000-E | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0B | 600 TON | | |
| 0017 | 1525000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE SF9.5A | 450 TON | | |
| 0018 | 1560000000-E | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 | 56 TON | | |

County : Gaston

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|----------|-----------|--------|
| 0019 | 1693000000-E | 654 | ASPHALT PLANT MIX, PAVEMENT REPAIR | 25 | TON | |
| 0020 | 2286000000-N | 840 | MASONRY DRAINAGE STRUCTURES | 1 | EA | |
| 0021 | 2367000000-N | 840 | FRAME WITH TWO GRATES, STD 840.29 | 1 | EA | |
| 0022 | 2556000000-E | 846 | SHOULDER BERM GUTTER | 60 | LF | |
| 0023 | 3030000000-E | 862 | STEEL BM GUARDRAIL | 675 | LF | |
| 0024 | 3150000000-N | 862 | ADDITIONAL GUARDRAIL POSTS | 5 | EA | |
| 0025 | 3270000000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE 350 | 4 | EA | |
| 0026 | 3317000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE B-77 | 4 | EA | |
| 0027 | 3559000000-E | 866 | ** STRAND BARBED WIRE FENCE WITH POSTS (4) | 305 | LF | |
| 0028 | 3575000000-E | SP | GENERIC FENCING ITEM ELECTRIC FENCE WITH POST | 815 | LF | |
| 0029 | 3635000000-E | 876 | RIP RAP, CLASS II | 10 | TON | |
| 0030 | 3649000000-E | 876 | RIP RAP, CLASS B | 60 | TON | |
| 0031 | 3656000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 290 | SY | |
| 0032 | 3659000000-N | SP | PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON | 1 | EA | |
| 0033 | 4400000000-E | 1110 | WORK ZONE SIGNS (STATIONARY) | 330 | SF | |
| 0034 | 4405000000-E | 1110 | WORK ZONE SIGNS (PORTABLE) | 96 | SF | |
| 0035 | 4410000000-E | 1110 | WORK ZONE SIGNS (BARRICADE MOUNTED) | 50 | SF | |
| 0036 | 4435000000-N | 1135 | CONES | 15 | EA | |

County : Gaston

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|----------|-----------|--------|
| 0037 | 4445000000-E | 1145 | BARRICADES (TYPE III) | 64 | LF | |
| 003E | 4450000000-N | 1150 | FLAGGER | 80 | HR | |
| 003E | 4810000000-E | 1205 | PAINT PAVEMENT MARKING LINES (4") | 8,800 | LF | |
| 004C | 6000000000-E | 1605 | TEMPORARY SILT FENCE | 1,820 | LF | |
| 0041 | 6006000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS A | 120 | TON | |
| 0042 | 6009000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS B | 470 | TON | |
| 0043 | 6012000000-E | 1610 | SEDIMENT CONTROL STONE | 145 | TON | |
| 0044 | 6015000000-E | 1615 | TEMPORARY MULCHING | 2 | ACR | |
| 004E | 6018000000-E | 1620 | SEED FOR TEMPORARY SEEDING | 100 | LB | |
| 004E | 6021000000-E | 1620 | FERTILIZER FOR TEMPORARY SEED- ING | 0.5 | TON | |
| 0047 | 6024000000-E | 1622 | TEMPORARY SLOPE DRAINS | 130 | LF | |
| 004E | 6027000000-N | 1622 | INLET PROTECTION AT TEMPORARY SLOPE DRAINS | 3 | EA | |
| 004E | 6029000000-E | SP | SAFETY FENCE | 600 | LF | |
| 005C | 6030000000-E | 1630 | SILT EXCAVATION | 1,360 | CY | |
| 0051 | 6036000000-E | 1631 | MATTING FOR EROSION CONTROL | 640 | SY | |
| 0052 | 6038000000-E | SP | PERMANENT SOIL REINFORCEMENT MAT | 1,930 | SY | |
| 0053 | 6042000000-E | 1632 | 1/4" HARDWARE CLOTH | 20 | LF | |
| 0054 | 6071030000-E | SP | COIR FIBER BAFFLES | 460 | LF | |
| 005E | 6084000000-E | 1660 | SEEDING & MULCHING | 2 | ACR | |

County : Gaston

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|------------------------|--------------|-------|--|---------------|-----------|--------|
| 005E | 6087000000-E | 1660 | MOWING | 1.5 ACR | | |
| 0057 | 6090000000-E | 1661 | SEED FOR REPAIR SEEDING | 50 LB | | |
| 005E | 6093000000-E | 1661 | FERTILIZER FOR REPAIR SEEDING | 0.25 TON | | |
| 005E | 6096000000-E | 1662 | SEED FOR SUPPLEMENTAL SEEDING | 50 LB | | |
| 006C | 6108000000-E | 1665 | FERTILIZER TOPDRESSING | 1.5 TON | | |
| 0061 | 6114000000-N | SP | SPECIALIZED HAND MOWING | 2 HR | | |
| 0062 | 6117000000-N | SP | RESPONSE FOR EROSION CONTROL | 12 EA | | |
| STRUCTURE ITEMS | | | | | | |
| 006E | 8035000000-N | 402 | REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+57.00-L-) | Lump Sum | L.S. | |
| 0064 | 8121000000-N | 412 | UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (14+57.00-L-) | Lump Sum | L.S. | |
| 006E | 8147000000-E | 420 | REINFORCED CONCRETE DECK SLAB | 3,594 SF | | |
| 006E | 8161000000-E | 420 | GROOVING BRIDGE FLOORS | 3,473 SF | | |
| 0067 | 8182000000-E | 420 | CLASS A CONCRETE (BRIDGE) | 35 CY | | |
| 006E | 8210000000-N | 422 | BRIDGE APPROACH SLABS, STATION ***** (14+57.00-L-) | Lump Sum | L.S. | |
| 006E | 8217000000-E | 425 | REINFORCING STEEL (BRIDGE) | 6,166 LB | | |
| 007C | 8280000000-E | 440 | APPROX LBS STRUCTURAL STEEL | 108,200 LS | | |
| 0071 | 8364000000-E | 450 | HP12X53 STEEL PILES | 600 LF | | |

County : Gaston

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|---|--------------|-------|--|----------|-----------|--------|
| 0072 | 8503000000-E | 460 | CONCRETE BARRIER RAIL | 226.67 | | |
| | | | | LF | | |
| 0073 | 8608000000-E | 876 | RIP RAP CLASS II (2'-0" THICK) | 223 | | |
| | | | | TON | | |
| 0074 | 8622000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 248 | | |
| | | | | SY | | |
| 0075 | 8692000000-N | SP | EVAZOTE JOINT SEALS | Lump Sum | L.S. | |
| 1308/Jul03/Q146492.42/D333023130000/E75 | | | Total Amount Of Bid For Entire Project : | | | |

Contract No **C201894**

County (ies): **Gaston**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General