

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	1,600 CY		
0005	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA-TION	600 TON		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE-RIAL, MINOR STRS	25 TON		
0009	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	56 LF		
0010	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	8 LF		
0011	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	36 LF		
0012	0995000000-E	340	PIPE REMOVAL	81 LF		
0013	1121000000-E	520	AGGREGATE BASE COURSE	105 TON		
0014	1220000000-E	545	INCIDENTAL STONE BASE	25 TON		
0015	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 4")	630 SY		
0016	1330000000-E	607	INCIDENTAL MILLING	65 SY		
0017	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	655 TON		

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	352	TON	
001E	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	720	TON	
002C	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	45	TON	
0021	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	44	TON	
0022	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	20	TON	
0023	2000000000-N	806	RIGHT OF WAY MARKERS	14	EA	
0024	2022000000-E	815	SUBDRAIN EXCAVATION	115	CY	
002E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	85	CY	
002E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500	LF	
0027	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15	EA	
002E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1	EA	
002E	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6	LF	
003C	2253000000-E	840	PIPE COLLARS	1	CY	
0031	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	8	EA	
0032	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2	EA	
003E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	1	EA	
0034	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	2	EA	

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	2	EA	
003E	2396000000-N	840	FRAME WITH COVER, STD 840.54	1	EA	
0037	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	1,100	LF	
003E	2612000000-E	848	6" CONCRETE DRIVEWAY	95	SY	
003E	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	2	EA	
004C	3030000000-E	862	STEEL BM GUARDRAIL	175	LF	
0041	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	100	LF	
0042	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0043	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1	EA	
0044	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3	EA	
004E	3628000000-E	876	RIP RAP, CLASS I	125	TON	
004E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	790	SY	
0047	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	257	SF	
004E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96	SF	
004E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	164	SF	
005C	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	1	EA	
0051	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	1	EA	
0052	4430000000-N	1130	DRUMS	80	EA	
0053	4435000000-N	1135	CONES	80	EA	

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4445000000-E	1145	BARRICADES (TYPE III)	88 LF		
005E	4450000000-N	1150	FLAGGER	40 HR		
005E	4480000000-N	1165	TMIA	1 EA		
0057	4510000000-N	SP	POLICE	40 HR		
005E	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	3,112 LF		
005E	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	200 LF		
006C	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	150 LF		
0061	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	24 EA		
0062	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	6,172 LF		
006E	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	320 LF		
0064	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	240 LF		
006E	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	28 EA		
006E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	105 EA		
0067	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
006E	5319000000-E	1505	CLASS B CONCRETE FOR ENCASING UTILITY LINES	12 CY		
006E	5691700000-E	1520	18" SANITARY GRAVITY SEWER	169 LF		
007C	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	2 EA		
0071	5775000000-E	1525	4' DIA UTILITY MANHOLE	1 EA		

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	5781000000-E	1525	UTILITY MANHOLE WALL, 4' DIA	18 LF		
0073	5804000000-E	1530	ABANDON 12" UTILITY PIPE	56 LF		
0074	5811000000-E	1530	ABANDON 18" UTILITY PIPE	66 LF		
0075	5816000000-N	1530	ABANDON UTILITY MANHOLE	1 EA		
0076	5882000000-N	SP	GENERIC UTILITY ITEM 4' DIA PRECAST CONCRETE FALSE BOTTOM MH, 0-6' DEPTH	1 EA		
0077	5900000000-E	SP	GENERIC UTILITY ITEM FOUNDATION CONDITION MTL	30 TON		
0078	6000000000-E	1605	TEMPORARY SILT FENCE	800 LF		
0079	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	285 TON		
0080	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	100 TON		
0081	6012000000-E	1610	SEDIMENT CONTROL STONE	300 TON		
0082	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0083	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0084	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25 TON		
0085	6029000000-E	SP	SAFETY FENCE	550 LF		
0086	6030000000-E	1630	SILT EXCAVATION	385 CY		
0087	6036000000-E	1631	MATTING FOR EROSION CONTROL	350 SY		
0088	6037000000-E	SP	COIR FIBER MAT	200 SY		
0089	6042000000-E	1632	1/4" HARDWARE CLOTH	325 LF		
0090	6070000000-N	SP	SPECIAL STILLING BASINS	6 EA		

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	6071010000-E	SP	WATTLE	25 LF		
0092	6071020000-E	SP	POLYACRYLAMIDE (PAM)	10 LB		
0093	6071030000-E	SP	COIR FIBER BAFFLES	125 LF		
0094	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
0095	6084000000-E	1660	SEEDING & MULCHING	2 ACR		
0096	6087000000-E	1660	MOWING	1 ACR		
0097	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0098	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0099	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0100	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
0101	6111000000-E	SP	IMPERVIOUS DIKE	225 LF		
0102	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0103	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0104	6120000000-E	SP	CULVERT DIVERSION CHANNEL	160 CY		
0105	6123000000-E	1670	REFORESTATION	0.1 ACR		
0106	7288000000-E	1715	PAVED TRENCHING (***** (1, 2")	70 LF		
0107	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2")	210 LF		
0108	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	3 EA		
0109	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	950 LF		

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0110	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	800	LF	
0111	7684000000-N	1750	SIGNAL CABINET FOUNDATION	1	EA	
0112	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	1	EA	
0113	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	6	EA	
0114	7901000000-N	1753	CABINET BASE EXTENDER	1	EA	

\*\*\*\*\* BEGIN SCHEDULE AA \*\*\*\*\*  
\*\*\*\*\* ( 3 ALTERNATES ) \*\*\*\*\*

0115 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	68	LF	
0116 AA1	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	60	LF	

\*\*\* OR \*\*\*

0117 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	48	LF	
0118 AA2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	20	LF	
0119 AA2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (24", 0.064")	60	LF	

\*\*\* OR \*\*\*

0120 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	48	LF	
0121 AA3	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	20	LF	
0122 AA3	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	60	LF	

\*\*\*\*\* END SCHEDULE AA \*\*\*\*\*

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>CULVERT ITEMS</b>						
0123	8049000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (11 + 13.00-L1-)	Lump Sum	L.S.	
0124	8126000000-N	414	CULVERT EXCAVATION, STA ***** (11 + 13.00-L1-)	Lump Sum	L.S.	
0125	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	218 TON		
0126	8196000000-E	420	CLASS A CONCRETE (CULVERT)	324 CY		
0127	8245000000-E	425	REINFORCING STEEL (CULVERT)	62,211 LB		
<b>0803/Jul03/Q90024.35/D516398910000/E127</b>				<b>Total Amount Of Bid For Entire Project :</b>		

**Contract No**     **C201895**

**County (ies):**    **McDowell**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General