

County : Perquimans

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1330000000-E	607	INCIDENTAL MILLING	2,500 SY		
0003	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	80 TON		
0004	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	480 TON		
0005	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	35 TON		
0006	3595000000-E	869	RELAPPING GUARDRAIL	250 LF		
0007	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	150 SY		
0008	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	914 SF		
0009	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	265 SF		
0010	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	78 SF		
0011	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0012	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
0013	4430000000-N	1130	DRUMS	351 EA		
0014	4445000000-E	1145	BARRICADES (TYPE III)	120 LF		
0015	4520000000-N	1266	TUBULAR MARKERS (FIXED)	313 EA		
0016	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	460 EA		
0017	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	31,660 LF		
0018	4795000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (24") (IV)	12 LF		

County : Perquimans

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL, TYPE ** (IV)	6	EA	
002C	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (HIGHLY REFLECTIVE ELEMENTS)	13,095	LF	
0021	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	13,095	LF	
0022	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	6	EA	
0023	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	146	EA	
0024	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	50	TON	
0025	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	16	TON	
0026	6012000000-E	1610	SEDIMENT CONTROL STONE	4	TON	
0027	6084000000-E	1660	SEEDING & MULCHING	1	ACR	
002E	8161000000-E	420	GROOVING BRIDGE FLOORS	72,035	SF	
0029	8573000000-E	SP	LATEX MODIFIED CONC OVERLAY	470	CY	
003C	8580000000-E	SP	PLACING & FINISHING OF LATEX MODIFIED CONC OVERLAY	9,010	SY	
0031	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0032	8860000000-N	SP	GENERIC STRUCTURE ITEM HYDRO-DEMOLITION OF BRIDGE DECK	Lump Sum	L.S.	
0033	8860000000-N	SP	GENERIC STRUCTURE ITEM SCARIFYING BRIDGE DECK	Lump Sum	L.S.	

County : Perquimans

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0034	8882000000-E	SP	GENERIC STRUCTURE ITEM EPOXY MORTAR REPAIRS	75 CF		

1520/Jul14/Q145685.0/D171805100000/E34

Total Amount Of Bid For Entire Project :

Contract No **C202133**

County (ies): **Perquimans**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General