

County : Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (18+07.50)	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (38+37.00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	28 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0009	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL	100 CY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	90 TON		
0011	0343000000-E	310	15" SIDE DRAIN PIPE	68 LF		
0012	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	628 LF		
0013	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	116 LF		
0014	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK (15", 0.064")	6 EA		
0015	1121000000-E	520	AGGREGATE BASE COURSE	210 TON		
0016	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,430 TON		

County : Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	570 TON		
0019	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,160 TON		
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	160 TON		
0021	2022000000-E	815	SUBDRAIN EXCAVATION	25 CY		
0022	2033000000-E	815	SUBDRAIN FINE AGGREGATE	20 CY		
0023	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0024	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0025	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0026	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	8 EA		
0028	2355000000-N	840	FRAME WITH GRATE, STD 840.29	8 EA		
0029	2556000000-E	846	SHOULDER BERM GUTTER	695 LF		
0030	3030000000-E	862	STEEL BM GUARDRAIL	1,325 LF		
0031	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0032	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	8 EA		
0033	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	8 EA		
0034	3649000000-E	876	RIP RAP, CLASS B	29 TON		
0035	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	445 SY		
0036	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	3 EA		

County : Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	320 SF		
0038	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	57 SF		
0039	4430000000-N	1130	DRUMS	10 EA		
0040	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
0041	4450000000-N	1150	FLAGGER	8 HR		
0042	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (STANDARD GLASS BEADS)	14,400 LF		
0043	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	50 EA		
0044	6000000000-E	1605	TEMPORARY SILT FENCE	2,900 LF		
0045	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	100 TON		
0046	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	200 TON		
0047	6012000000-E	1610	SEDIMENT CONTROL STONE	155 TON		
0048	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
0049	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0050	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		
0051	6024000000-E	1622	TEMPORARY SLOPE DRAINS	500 LF		
0052	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	15 EA		
0053	6029000000-E	SP	SAFETY FENCE	1,275 LF		
0054	6030000000-E	1630	SILT EXCAVATION	5,030 CY		
0055	6036000000-E	1631	MATTING FOR EROSION CONTROL	725 SY		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6037000000-E	SP	COIR FIBER MAT	60 SY		
0057	6042000000-E	1632	1/4" HARDWARE CLOTH	450 LF		
0058	6071030000-E	SP	COIR FIBER BAFFLES	275 LF		
0059	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0060	6087000000-E	1660	MOWING	2 ACR		
0061	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0062	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0063	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0064	6108000000-E	1665	FERTILIZER TOPDRESSING	2.25 TON		
0065	6114000000-N	SP	SPECIALIZED HAND MOWING	4 HR		
0066	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		

STRUCTURE ITEMS

0067	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18+07.50 -L-)	Lump Sum	L.S.	
0068	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (38+37.00 -L-)	Lump Sum	L.S.	
0069	8112730000-N	SP	PDA TESTING	3 EA		
0070	8112740000-N	SP	PDA ASSISTANCE	3 EA		
0071	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION (38+37.00 -L-)	1,780 CY		
0072	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (18+07.50 -L-)	Lump Sum	L.S.	

County : Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	8156000000-E	SP	CONCRETE WEARING SURFACE	17,100 SF		
0074	8161000000-E	420	GROOVING BRIDGE FLOORS	17,533 SF		
0075	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	189.3 CY		
0076	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18+07.50 -L-)	Lump Sum	L.S.	
0077	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (38+37.00 -L-)	Lump Sum	L.S.	
0078	8217000000-E	425	REINFORCING STEEL (BRIDGE)	29,407 LB		
0079	8364000000-E	450	HP12X53 STEEL PILES	1,605 LF		
0080	8365000000-E	450	HP12X53 GALVANIZED STEEL PILES	1,125 LF		
0081	8385200000-E	450	PP ** X **** GALVANIZED STEEL PILES (24" X 0.500")	440 LF		
0082	8385200000-E	450	PP ** X **** GALVANIZED STEEL PILES (30" X 0.500")	480 LF		
0083	8392000000-N	450	PIPE PILE PLATES	16 EA		
0084	8393000000-N	450	PILE REDRIVES	36 EA		
0085	8503000000-E	460	CONCRETE BARRIER RAIL	929.47 LF		
0086	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	1,285 TON		
0087	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,425 SY		
0088	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0089	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

County : Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0090	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	6,229.01 LF		

0755/Jul11/Q114080.28/D425793000000/E90

Total Amount Of Bid For Entire Project :

Contract No **C201605**

County (ies): **Sampson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General