

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (12+68.90)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	400 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	750 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	62 TON		
0009	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	12 LF		
0010	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	500 TON		
0011	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	290 TON		
0012	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	40 TON		
0013	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	28 TON		
0014	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0015	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0016	2556000000-E	846	SHOULDER BERM GUTTER	22 LF		
0017	3030000000-E	862	STEEL BM GUARDRAIL	550 LF		
0018	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4	EA	
0020	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4	EA	
0021	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	300	LF	
0022	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	20	EA	
0023	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	10	EA	
0024	3563000000-E	SP	TEMP *** WOVEN WIRE FENCE, COMPLETE W/POSTS (47")	300	LF	
0025	3649000000-E	876	RIP RAP, CLASS B	35	TON	
0026	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	265	SY	
0027	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	191	LF	
0028	4096000000-N	904	SIGN ERECTION, TYPE D	2	EA	
0029	4102000000-N	904	SIGN ERECTION, TYPE E	3	EA	
0030	4108000000-N	904	SIGN ERECTION, TYPE F	3	EA	
0031	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	12	EA	
0032	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	334	SF	
0033	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96	SF	
0034	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	109	SF	
0035	4445000000-E	1145	BARRICADES (TYPE III)	96	LF	
0036	4450000000-N	1150	FLAGGER	16	HR	
0037	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,370	LF	

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,370 LF		
0039	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	10 LF		
0040	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	360 LF		
0041	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	8 EA		
0042	5326200000-E	1510	12" WATER LINE	932 LF		
0043	5558000000-E	1515	12" VALVE	4 EA		
0044	5666000000-E	1515	FIRE HYDRANT	1 EA		
0045	5804000000-E	1530	ABANDON 12" UTILITY PIPE	700 LF		
0046	5871700000-E	1550	TRENCHLESS INSTALLATION OF 12" IN SOIL	300 LF		
0047	5871710000-E	1550	TRENCHLESS INSTALLATION OF 12" NOT IN SOIL	100 LF		
0048	6000000000-E	1605	TEMPORARY SILT FENCE	770 LF		
0049	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0050	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	65 TON		
0051	6012000000-E	1610	SEDIMENT CONTROL STONE	25 TON		
0052	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0053	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0054	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		
0055	6029000000-E	SP	SAFETY FENCE	730 LF		

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6030000000-E	1630	SILT EXCAVATION	335 CY		
0057	6036000000-E	1631	MATTING FOR EROSION CONTROL	470 SY		
0058	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	75 SY		
0059	6042000000-E	1632	1/4" HARDWARE CLOTH	20 LF		
0060	6071030000-E	SP	COIR FIBER BAFFLES	65 LF		
0061	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
0062	6087000000-E	1660	MOWING	0.5 ACR		
0063	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0064	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0065	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0066	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0067	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0068	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
<b>STRUCTURE ITEMS</b>						
0069	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (12+68.90-L-)	Lump Sum	L.S.	
0070	8112730000-N	SP	PDA TESTING	2 EA		
0071	8112740000-N	SP	PDA ASSISTANCE	2 EA		
0072	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (12+68.90-L-)	Lump Sum	L.S.	
0073	8156000000-E	SP	CONCRETE WEARING SURFACE	2,908 SF		

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	8161000000-E	420	GROOVING BRIDGE FLOORS	4,084 SF		
0075	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	38.4 CY		
0076	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (12+68.90-L-)	Lump Sum	L.S.	
0077	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,788 LB		
0078	8364000000-E	450	HP12X53 STEEL PILES	1,300 LF		
0079	8475000000-E	460	TWO BAR METAL RAIL	160.5 LF		
0080	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2"X2'-11 1/2")	175.5 LF		
0081	8590000000-E	876	RIP RAP, CLASS ** (1, 2'-0" THICK)	156 TON		
0082	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	173 SY		
0083	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0084	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0085	8753200000-E	430	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	1,053 LF		

1508/Jul14/Q28762.9/D418369410000/E85

Total Amount Of Bid For Entire Project :

**Contract No**     **C201896**

**County (ies):**   **Scotland**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General