

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0005	0134000000-E	240	DRAINAGE DITCH EXCAVATION	1,235 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0008	0199000000-E	SP	TEMPORARY SHORING	610 SF		
0009	0241000000-E	SP	GENERIC GRADING ITEM ROCK PLATING	250 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	40 TON		
0011	0342000000-E	310	*** SIDE DRAIN PIPE (30")	40 LF		
0012	0408000000-E	310	54" RC PIPE CULVERTS, CLASS III	128 LF		
0013	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (84", 0.168")	156 LF		
0014	0594000000-E	310	24" CS PIPE CULVERTS, 0.064" THICK	20 LF		
0015	0600000000-E	310	30" CS PIPE CULVERTS, 0.079" THICK	24 LF		
0016	0995000000-E	340	PIPE REMOVAL	240 LF		
0017	1077000000-E	SP	#57 STONE	25 TON		
0018	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1330000000-E	607	INCIDENTAL MILLING	260 SY		
0020	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,300 TON		
0021	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	425 TON		
0022	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	875 TON		
0023	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	125 TON		
0024	2000000000-N	806	RIGHT OF WAY MARKERS	13 EA		
0025	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
0026	2033000000-E	815	SUBDRAIN FINE AGGREGATE	34 CY		
0027	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0028	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0029	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0030	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0031	2220000000-E	838	REINFORCED ENDWALLS	10.5 CY		
0032	3030000000-E	862	STEEL BM GUARDRAIL	612.5 LF		
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0034	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0035	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	300 LF		
0036	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	4 EA		
0037	3628000000-E	876	RIP RAP, CLASS I	464 TON		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3649000000-E	876	RIP RAP, CLASS B	718 TON		
0039	3651000000-E	SP	BOULDERS	80 TON		
0040	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	3,086 SY		
0041	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	128 SF		
0042	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0043	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	36 SF		
0044	4430000000-N	1130	DRUMS	40 EA		
0045	4445000000-E	1145	BARRICADES (TYPE III)	32 LF		
0046	4450000000-N	1150	FLAGGER	480 HR		
0047	4480000000-N	1165	TMIA	1 EA		
0048	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	30 EA		
0049	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,200 LF		
0050	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,200 LF		
0051	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	25,200 LF		
0052	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	400 LF		
0053	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	15 EA		
0054	6000000000-E	1605	TEMPORARY SILT FENCE	1,500 LF		
0055	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	150 TON		
0056	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	325 TON		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6012000000-E	1610	SEDIMENT CONTROL STONE	200 TON		
0058	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
0059	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0060	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.5 TON		
0061	6029000000-E	SP	SAFETY FENCE	1,200 LF		
0062	6030000000-E	1630	SILT EXCAVATION	840 CY		
0063	6036000000-E	1631	MATTING FOR EROSION CONTROL	925 SY		
0064	6037000000-E	SP	COIR FIBER MAT	25 SY		
0065	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	850 SY		
0066	6042000000-E	1632	1/4" HARDWARE CLOTH	25 LF		
0067	6045000000-E	SP	*** TEMPORARY PIPE (15")	100 LF		
0068	6045000000-E	SP	*** TEMPORARY PIPE (18")	210 LF		
0069	6070000000-N	SP	SPECIAL STILLING BASINS	5 EA		
0070	6071030000-E	SP	COIR FIBER BAFFLES	135 LF		
0071	6071050000-E	SP	*** SKIMMER (1-1/2")	3 EA		
0072	6084000000-E	1660	SEEDING & MULCHING	3.5 ACR		
0073	6087000000-E	1660	MOWING	2 ACR		
0074	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0075	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0076	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0077	6108000000-E	1665	FERTILIZER TOPDRESSING	2 TON		
0078	6111000000-E	SP	IMPERVIOUS DIKE	160 LF		
0079	6114000000-N	SP	SPECIALIZED HAND MOWING	3 HR		
0080	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0081	6123000000-E	1670	REFORESTATION	0.6 ACR		

CULVERT ITEMS

0082	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (20+04.00-L-)	Lump Sum	L.S.	
0083	8126000000-N	414	CULVERT EXCAVATION, STA ***** (20+04.00-L-)	Lump Sum	L.S.	
0084	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	82 TON		
0085	8196000000-E	420	CLASS A CONCRETE (CULVERT)	175.6 CY		
0086	8245000000-E	425	REINFORCING STEEL (CULVERT)	27,562 LB		

1518/Jul14/Q77529.95/D331936280000/E86

Total Amount Of Bid For Entire Project :

Contract No **C201897**

County (ies): **Wake**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General