

County : Alleghany

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	475 TON		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	5 TON		
0010	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	26 LF		
0011	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0012	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	282 TON		
0013	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	239 TON		
0014	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	28 TON		
0015	2000000000-N	806	RIGHT OF WAY MARKERS	16 EA		
0016	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
0017	2033000000-E	815	SUBDRAIN FINE AGGREGATE	35 CY		
0018	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		

County : Alleghany

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0020	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0021	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0022	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0023	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0024	2556000000-E	846	SHOULDER BERM GUTTER	15 LF		
0025	3030000000-E	862	STEEL BM GUARDRAIL	75 LF		
0026	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	125 LF		
0027	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0028	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (TL-2)	1 EA		
0029	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (B-77, SHOP CURVED)	1 EA		
0030	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0031	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	3 EA		
0032	3559000000-E	866	** STRAND BARBED WIRE FENCE WITH POSTS (6)	40 LF		
0033	3649000000-E	876	RIP RAP, CLASS B	5 TON		
0034	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	160 SY		
0035	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		

County : Allegheny

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	13 LF		
0037	4102000000-N	904	SIGN ERECTION, TYPE E	1 EA		
003E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	4 EA		
003E	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	5 EA		
004C	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	312 SF		
0041	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0042	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
004E	4430000000-N	1130	DRUMS	24 EA		
0044	4435000000-N	1135	CONES	24 EA		
004E	4445000000-E	1145	BARRICADES (TYPE III)	88 LF		
004E	4450000000-N	1150	FLAGGER	480 HR		
0047	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	6,400 LF		
004E	6000000000-E	1605	TEMPORARY SILT FENCE	850 LF		
004E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
005C	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	205 TON		
0051	6012000000-E	1610	SEDIMENT CONTROL STONE	65 TON		
0052	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
005E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0054	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		

County : Alleghany

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	30 LF		
005E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1 EA		
0057	6029000000-E	SP	SAFETY FENCE	300 LF		
005E	6030000000-E	1630	SILT EXCAVATION	340 CY		
005E	6036000000-E	1631	MATTING FOR EROSION CONTROL	390 SY		
006C	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	110 SY		
0061	6042000000-E	1632	1/4" HARDWARE CLOTH	20 LF		
0062	6071030000-E	SP	COIR FIBER BAFFLES	100 LF		
006E	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
0064	6087000000-E	1660	MOWING	1 ACR		
006E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
006E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0067	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
006E	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
006E	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
007C	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		

STRUCTURE ITEMS

0071	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (15+99.00-L-)	Lump Sum	L.S.	
------	--------------	----	---	----------	------	--

County : Alleghany

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+99.00-L-)	Lump Sum	L.S.	
0073	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	4,063 SF		
0074	8161000000-E	420	GROOVING BRIDGE FLOORS	3,844 SF		
0075	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	33 CY		
0076	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15+99.00-L-)	Lump Sum	L.S.	
0077	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,522 LB		
0078	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	174,300 LS		
0079	8364000000-E	450	HP12X53 STEEL PILES	240 LF		
0080	8503000000-E	460	CONCRETE BARRIER RAIL	256.67 LF		
0081	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	248 TON		
0082	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	441 SY		
0083	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0084	8860000000-N	SP	GENERIC STRUCTURE ITEM REINF BRIDGE APPR FILL FOR INTEGRAL ABUTMENTS, STA 15+99.00-L-	Lump Sum	L.S.	
0085	8874000000-E	SP	GENERIC STRUCTURE ITEM SCOUR PROTECTION STONE	150 TON		

Contract No **C201922**

County (ies): **Alleghany**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General