

County : Bladen, Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0000960000-E	SP	GENERIC MISCELLANEOUS ITEM ROCK PLATING	500 SY		
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (14+95.00)	Lump Sum	L.S.	
0005	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (15+40.50)	Lump Sum	L.S.	
0006	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+56.00)	Lump Sum	L.S.	
0007	0043000000-N	226	GRADING	Lump Sum	L.S.	
0008	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	2 ACR		
0009	0057000000-E	226	UNDERCUT EXCAVATION	1,200 CY		
0010	0134000000-E	240	DRAINAGE DITCH EXCAVATION	10 CY		
0011	0195000000-E	265	SELECT GRANULAR MATERIAL	300 CY		
0012	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0013	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	49 TON		
0014	0344000000-E	310	18" SIDE DRAIN PIPE	24 LF		
0015	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	60 LF		
0016	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	64 LF		
0017	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (72", 0.138")	112 LF		

County : Bladen, Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	124 LF		
0019	0738000000-E	310	42" BIT COAT CS PIPE CULVERTS, TYPE B 0.109" THICK	64 LF		
0020	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0021	0995000000-E	340	PIPE REMOVAL	297 LF		
0022	1121000000-E	520	AGGREGATE BASE COURSE	2,051 TON		
0023	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0024	1275000000-E	600	PRIME COAT	1,210 GAL		
0025	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	440 TON		
0026	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	300 TON		
0027	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	800 TON		
0028	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	435 TON		
0029	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	115 TON		
0030	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	100 TON		
0031	2000000000-N	806	RIGHT OF WAY MARKERS	8 EA		
0032	2022000000-E	815	SUBDRAIN EXCAVATION	46 CY		
0033	2033000000-E	815	SUBDRAIN FINE AGGREGATE	34 CY		
0034	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0035	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		

County : Bladen, Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0037	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0038	2199000000-E	SP	SANDBAG HEADWALL	300 SF		
0039	2220000000-E	838	REINFORCED ENDWALLS	9.8 CY		
0040	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5 EA		
0041	2355000000-N	840	FRAME WITH GRATE, STD 840.29	1 EA		
0042	2363000000-N	840	FRAME WITH TWO GRATES, STD 840.***** (840.29)	4 EA		
0043	2535000000-E	846	***X *** CONCRETE CURB (6" x 8")	25 LF		
0044	2556000000-E	846	SHOULDER BERM GUTTER	111 LF		
0045	3030000000-E	862	STEEL BM GUARDRAIL	712.5 LF		
0046	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	150 LF		
0047	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0048	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	3 EA		
0049	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	5 EA		
0050	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	8 EA		
0051	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	325 LF		
0052	3382000000-E	862	TEMPORARY STEEL BM GUARDRAIL (SHOP CURVED)	100 LF		
0053	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (AT-1)	2 EA		

County : Bladen, Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	2 EA		
0055	3649000000-E	876	RIP RAP, CLASS B	35 TON		
0056	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	755 SY		
0057	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0058	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	16 LF		
0059	4102000000-N	904	SIGN ERECTION, TYPE E	2 EA		
0060	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	13 EA		
0061	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	495 SF		
0062	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0063	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	205 SF		
0064	4430000000-N	1130	DRUMS	35 EA		
0065	4435000000-N	1135	CONES	10 EA		
0066	4445000000-E	1145	BARRICADES (TYPE III)	272 LF		
0067	4450000000-N	1150	FLAGGER	530 HR		
0068	4480000000-N	1165	TMIA	1 EA		
0069	4507000000-E	SP	WATER FILLED BARRIER	48 LF		
0070	4516000000-N	1180	SKINNY DRUM	20 EA		
0071	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	40 EA		
0072	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	3,220 LF		

County : Bladen, Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	3,220 LF		
0074	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	400 LF		
0075	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	35,720 LF		
0076	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	3,300 LF		
0077	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	32 EA		
0078	6000000000-E	1605	TEMPORARY SILT FENCE	5,100 LF		
0079	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	100 TON		
0080	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	445 TON		
0081	6012000000-E	1610	SEDIMENT CONTROL STONE	260 TON		
0082	6015000000-E	1615	TEMPORARY MULCHING	4 ACR		
0083	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0084	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.75 TON		
0085	6024000000-E	1622	TEMPORARY SLOPE DRAINS	100 LF		
0086	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0087	6029000000-E	SP	SAFETY FENCE	1,500 LF		
0088	6030000000-E	1630	SILT EXCAVATION	780 CY		
0089	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,460 SY		
0090	6042000000-E	1632	1/4" HARDWARE CLOTH	450 LF		

County : Bladen, Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	50 SY		
0092	6071030000-E	SP	COIR FIBER BAFFLES	320 LF		
0093	6084000000-E	1660	SEEDING & MULCHING	4 ACR		
0094	6087000000-E	1660	MOWING	3 ACR		
0095	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		
0096	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5 TON		
0097	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	125 LB		
0098	6108000000-E	1665	FERTILIZER TOPDRESSING	3 TON		
0099	6114000000-N	SP	SPECIALIZED HAND MOWING	4.5 HR		
0100	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	39 EA		
0101	6123000000-E	1670	REFORESTATION	1 ACR		

STRUCTURE ITEMS

0102	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+95.00-L-)	Lump Sum	L.S.	
0103	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+40.50-L-)	Lump Sum	L.S.	
0104	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+56.00-L-)	Lump Sum	L.S.	
0105	8112740000-N	SP	PDA ASSISTANCE	3 EA		
0106	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (14+95.00-L-)	Lump Sum	L.S.	

County : Bladen, Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (15+40.50-L-)	Lump Sum	L.S.	
0108	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (16+56.00-L-)	Lump Sum	L.S.	
0109	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	75.9 CY		
0110	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	111.7 CY		
0111	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14+95.00-L-)	Lump Sum	L.S.	
0112	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15+40.50-L-)	Lump Sum	L.S.	
0113	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+56.00-L-)	Lump Sum	L.S.	
0114	8217000000-E	425	REINFORCING STEEL (BRIDGE)	28,550 LB		
0115	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	1,088 LB		
0116	8364000000-E	450	HP12X53 STEEL PILES	1,855 LF		
0117	8365000000-E	450	HP12X53 GALVANIZED STEEL PILES	875 LF		
0118	8393000000-N	450	PILE REDRIVES	42 EA		
0119	8433000000-E	SP	*** STEEL SHEET PILES (19.69)	450 SF		
0120	8433000000-E	SP	*** STEEL SHEET PILES (22)	1,525 SF		
0121	8503000000-E	460	CONCRETE BARRIER RAIL	522.63 LF		
0122	8590000000-E	876	RIP RAP, CLASS ** (I)	92 TON		
0123	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	232 TON		

County : Bladen, Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0124	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	404 SY		
0125	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0126	8748000000-E	300	SELECT MATERIAL, CLASS ** (VI)	4 TON		
0127	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	2,940 LF		
0801/Aug19/Q108898.28/D545161330000/E127			Total Amount Of Bid For Entire Project :			

Contract No **C202120**

County (ies): **Bladen, Columbus**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General