

PROJECT: R-2206BA
COUNTIES: LINCOLN & CATAWBA

PROJECT SPECIAL PROVISIONS
Utility

UTILITY CONFLICTS:

General:

The following utility companies have facilities that will be in conflict with the construction of this project:

- A.. Rutherford Electric Membership Corporation
- B. Charter Communications
- C. AT & T of NC

The conflicting facilities will be adjusted prior to the date of availability except where noted and are therefore listed in these special provisions for the benefit of the Contractor. All utility work listed herein will be done by the utility owners. All utilities are shown on the plans from the best available information.

The Contractor's attention is directed to Article 105.8 of the Standard Specifications.

Utilities Requiring Adjustment:

After Rough Grading is Completed in the Affected Areas

- A. Rutherford Electric Membership Corporation
 1. See "Utility By Others Plans" for utility conflicts.
 2. Contact Person is Thomas Conner (828)245-1621
 3. All Power facilities will be relocated within One Month.
- B. Charter Communications
 1. See "Utility By Others Plans" for utility conflicts.
 2. All Cable facilities will be relocated within Two Weeks after the Rutherford Electric Membership Corporation complete there work.
- C. AT & T of NC
 1. See "Utility By Others Plans" for utility conflicts.
 2. Contact Person is Steve Mode (704)276-3197
 3. All Telephone facilities will be relocated within One Month after Charter Communications complete there work.

The contractor shall be advised that utilities along existing SR 1895 (Tower Road), proposed -Y20-, and proposed -LDET- shall be relocated in conjunction with the contractor's operation in these locations on the project.

STAGE 1: Prior to Construction

The utility owners will complete the following utility work:

The proposed overhead lines from approximately -Y17- Sta. 17+60 to Sta. 10+00 and from approximately -Y16- Sta. 14+07.66 to Sta. 10+00 will be constructed as shown on R-2206BA sheets UO-2, UO-3, and UO-4.

The proposed overhead lines from approximately -Y20- Sta. 10+00 to Sta. 11+60 will be constructed as shown on R-2206BA sheets UO-3 and UO-4.

STAGE 2: Removal of SR 1895 (TOWER Rd.) and Construction -LDET-

Once the contractor has completed the earthwork necessary to remove the section of SR 1895 (Tower Rd) near SBL Sta. 269+00 and rough graded -LDET-, the utility owners will perform the following:

Construction of proposed overhead lines from approximately SBL Sta. 267+36 to SBL Sta. 271+20.

Construction of temporary overhead lines from approximately -LDET- Sta. 12+20 to -LDET- Sta. 15+87 as shown on R-2206BA sheets UO-5 & UO-6.

STAGE 3: Traffic on -LDET-

After NC 16 traffic is switched onto -LDET- and the contractor has cleared and rough graded from SBL Sta. 271+00 to SBL Sta. 274+60, the utility owner will perform the following:

Construction of overhead lines from SBL Sta. 271+20 to SBL Sta. 274+60 as shown on R-2206BA sheets UO-5 and UO-6.

STAGE 4: Prior to removal of -LDET-

After traffic has been removed from -LDET-, the utility owner will perform the following:

1. The utility owner will remove the temporary overhead lines from -LDET-.