

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (15+53.00)	Lump Sum	L.S.	
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (31+65.00)	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0007	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0008	0106000000-E	230	BORROW EXCAVATION	46,900 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	4,800 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	10,900 SY		
0011	0241000000-E	SP	GENERIC GRADING ITEM ROCK PLATING	50 SY		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	18 TON		
0013	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	32 LF		
0014	0588000000-E	310	18" CS PIPE CULVERTS, 0.064" THICK	72 LF		
0015	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	24 LF		
0016	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0017	0995000000-E	340	PIPE REMOVAL	72 LF		
0018	1121000000-E	520	AGGREGATE BASE COURSE	3,918 TON		

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1275000000-E	600	PRIME COAT	633	GAL	
0020	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	620	TON	
0021	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	365	TON	
0022	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,940	TON	
0023	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	225	TON	
0024	2022000000-E	815	SUBDRAIN EXCAVATION	45	CY	
0025	2033000000-E	815	SUBDRAIN FINE AGGREGATE	34	CY	
0026	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200	LF	
0027	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6	EA	
0028	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2	EA	
0029	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12	LF	
0030	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3	EA	
0031	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3	EA	
0032	2556000000-E	846	SHOULDER BERM GUTTER	88.5	LF	
0033	3030000000-E	862	STEEL BM GUARDRAIL	1,200	LF	
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10	EA	
0035	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	8	EA	
0036	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	8	EA	
0037	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	881.25	LF	

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)	9 EA		
0039	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	10 EA		
0040	3649000000-E	876	RIP RAP, CLASS B	3 TON		
0041	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	525 SY		
0042	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	152 SF		
0043	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	192 SF		
0044	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	72 SF		
0045	4430000000-N	1130	DRUMS	188 EA		
0046	4435000000-N	1135	CONES	77 EA		
0047	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
0048	4455000000-N	1150	FLAGGER	80 MD		
0049	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1 EA		
0050	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	343 EA		
0051	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	7,808 LF		
0052	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	7,808 LF		
0053	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	53,316 LF		
0054	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	53 EA		
0055	6000000000-E	1605	TEMPORARY SILT FENCE	7,970 LF		

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	120	TON	
0057	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	395	TON	
0058	6012000000-E	1610	SEDIMENT CONTROL STONE	220	TON	
0059	6015000000-E	1615	TEMPORARY MULCHING	8	ACR	
0060	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	350	LB	
0061	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.5	TON	
0062	6024000000-E	1622	TEMPORARY SLOPE DRAINS	160	LF	
0063	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	6	EA	
0064	6029000000-E	SP	SAFETY FENCE	3,670	LF	
0065	6030000000-E	1630	SILT EXCAVATION	600	CY	
0066	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,800	SY	
0067	6042000000-E	1632	1/4" HARDWARE CLOTH	305	LF	
0068	6070000000-N	SP	SPECIAL STILLING BASINS	2	EA	
0069	6071010000-E	SP	WATTLE	145	LF	
0070	6071020000-E	SP	POLYACRYLAMIDE (PAM)	36	LB	
0071	6071030000-E	SP	COIR FIBER BAFFLES	160	LF	
0072	6084000000-E	1660	SEEDING & MULCHING	15.1	ACR	
0073	6087000000-E	1660	MOWING	7	ACR	
0074	6090000000-E	1661	SEED FOR REPAIR SEEDING	100	LB	
0075	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5	TON	

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	275 LB		
0077	6108000000-E	1665	FERTILIZER TOPDRESSING	8.25 TON		
0078	6114000000-N	SP	SPECIALIZED HAND MOWING	7.5 HR		
0079	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	39 EA		
0080	6123000000-E	1670	REFORESTATION	1 ACR		
STRUCTURE ITEMS						
0081	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (15+53.00-L-)	Lump Sum	L.S.	
0082	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (31+65.00 -L-)	Lump Sum	L.S.	
0083	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+53.00-L-)	Lump Sum	L.S.	
0084	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (31+65.00 -L-)	Lump Sum	L.S.	
0085	8112740000-N	SP	PDA ASSISTANCE	1 EA		
0086	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	568 CY		
0087	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (31+65.00 -L-)	Lump Sum	L.S.	
0088	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	3,826 SF		
0089	8156000000-E	SP	CONCRETE WEARING SURFACE	5,022 SF		
0090	8161000000-E	420	GROOVING BRIDGE FLOORS	10,421 SF		

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	115.1 CY		
0092	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15+53.00-L-)	Lump Sum	L.S.	
0093	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (31+65.00 -L-)	Lump Sum	L.S.	
0094	8217000000-E	425	REINFORCING STEEL (BRIDGE)	18,828 LB		
0095	8265000000-E	430	54" PRESTRESSED CONCRETE GIR- DERS	440.78 LF		
0096	8364000000-E	450	HP12X53 STEEL PILES	1,715 LF		
0097	8365000000-E	450	HP12X53 GALVANIZED STEEL PILES	810 LF		
0098	8393000000-N	450	PILE REDRIVES	8 EA		
0099	8433000000-E	SP	*** STEEL SHEET PILES (22")	1,473 SF		
0100	8503000000-E	460	CONCRETE BARRIER RAIL	440.75 LF		
0101	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	675 TON		
0102	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	747 SY		
0103	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0104	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0105	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,820 LF		
1437/Aug04/Q209600.23/D486967400000/E105			Total Amount Of Bid For Entire Project :			

Contract No **C201962**

County (ies): **Columbus**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General