

County : Franklin

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|--|-------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0000400000-N | 801 | CONSTRUCTION SURVEYING | Lump Sum | L.S. | |
| 0003 | 0043000000-N | 226 | GRADING | Lump Sum | L.S. | |
| 0004 | 0050000000-E | 226 | SUPPLEMENTARY CLEARING & GRUB-BING | 1 ACR | | |
| 0005 | 0057000000-E | 226 | UNDERCUT EXCAVATION | 500 CY | | |
| 0006 | 0134000000-E | 240 | DRAINAGE DITCH EXCAVATION | 20 CY | | |
| 0007 | 0196000000-E | 270 | FABRIC FOR SOIL STABILIZATION | 500 SY | | |
| 0008 | 0234000000-E | SP | GENERIC GRADING ITEM SELECT GRANULAR MATERIAL | 1,300 CY | | |
| 0009 | 0318000000-E | 300 | FOUNDATION CONDITIONING MATERIAL, MINOR STRS | 30 TON | | |
| 0010 | 0343000000-E | 310 | 15" SIDE DRAIN PIPE | 36 LF | | |
| 0011 | 0414000000-E | 310 | 60" RC PIPE CULVERTS, CLASS III | 56 LF | | |
| 0012 | 0708000000-E | 310 | 15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK | 100 LF | | |
| 0013 | 0995000000-E | 340 | PIPE REMOVAL | 22 LF | | |
| 0014 | 1220000000-E | 545 | INCIDENTAL STONE BASE | 100 TON | | |
| 0015 | 1489000000-E | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0B | 590 TON | | |
| 0016 | 1498000000-E | 610 | ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B | 320 TON | | |
| 0017 | 1525000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE SF9.5A | 380 TON | | |
| 0018 | 1560000000-E | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 | 70 TON | | |
| 0019 | 2000000000-N | 806 | RIGHT OF WAY MARKERS | 12 EA | | |

County : Franklin

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|-------------|-----------|--------|
| 0020 | 2022000000-E | 815 | SUBDRAIN EXCAVATION | 22.4 CY | | |
| 0021 | 2033000000-E | 815 | SUBDRAIN FINE AGGREGATE | 16.8 CY | | |
| 0022 | 2044000000-E | 815 | 6" PERFORATED SUBDRAIN PIPE | 100 LF | | |
| 0023 | 2055000000-E | 815 | 6" SUBDRAIN PIPE WYES, TEES, & ELBOWS | 3 EA | | |
| 0024 | 2066000000-N | 815 | CONCRETE PAD FOR SUBDRAIN PIPE OUTLET | 1 EA | | |
| 0025 | 2077000000-E | 815 | 6" OUTLET PIPE (SUBDRAINS) | 6 LF | | |
| 0026 | 2220000000-E | 838 | REINFORCED ENDWALLS | 5.7 CY | | |
| 0027 | 2286000000-N | 840 | MASONRY DRAINAGE STRUCTURES | 2 EA | | |
| 0028 | 2308000000-E | 840 | MASONRY DRAINAGE STRUCTURES | 2.5 LF | | |
| 0029 | 2367000000-N | 840 | FRAME WITH TWO GRATES, STD 840.29 | 2 EA | | |
| 0030 | 2556000000-E | 846 | SHOULDER BERM GUTTER | 875 LF | | |
| 0031 | 3030000000-E | 862 | STEEL BM GUARDRAIL | 1,000 LF | | |
| 0032 | 3150000000-N | 862 | ADDITIONAL GUARDRAIL POSTS | 5 EA | | |
| 0033 | 3270000000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE 350 | 4 EA | | |
| 0034 | 3360000000-E | 863 | REMOVE EXISTING GUARDRAIL | 820 LF | | |
| 0035 | 3628000000-E | 876 | RIP RAP, CLASS I | 115 TON | | |
| 0036 | 3649000000-E | 876 | RIP RAP, CLASS B | 125 TON | | |
| 0037 | 3656000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 505 SY | | |
| 0038 | 3659000000-N | SP | PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON | 1 EA | | |
| 0039 | 4400000000-E | 1110 | WORK ZONE SIGNS (STATIONARY) | 437 SF | | |

County : Franklin

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|---------------|-----------|--------|
| 0040 | 4410000000-E | 1110 | WORK ZONE SIGNS (BARRICADE MOUNTED) | 94 SF | | |
| 0041 | 4445000000-E | 1145 | BARRICADES (TYPE III) | 64 LF | | |
| 0042 | 4810000000-E | 1205 | PAINT PAVEMENT MARKING LINES (4") | 166,400 LF | | |
| 0043 | 4850000000-E | 1205 | REMOVAL OF PAVEMENT MARKING LINES (4") | 79,400 LF | | |
| 0044 | 4900000000-N | 1251 | PERMANENT RAISED PAVEMENT MARKERS | 24 EA | | |
| 0045 | 6000000000-E | 1605 | TEMPORARY SILT FENCE | 900 LF | | |
| 0046 | 6006000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS A | 150 TON | | |
| 0047 | 6009000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS B | 150 TON | | |
| 0048 | 6012000000-E | 1610 | SEDIMENT CONTROL STONE | 230 TON | | |
| 0049 | 6015000000-E | 1615 | TEMPORARY MULCHING | 2 ACR | | |
| 0050 | 6018000000-E | 1620 | SEED FOR TEMPORARY SEEDING | 100 LB | | |
| 0051 | 6021000000-E | 1620 | FERTILIZER FOR TEMPORARY SEEDING | 0.25 TON | | |
| 0052 | 6024000000-E | 1622 | TEMPORARY SLOPE DRAINS | 125 LF | | |
| 0053 | 6027000000-N | 1622 | INLET PROTECTION AT TEMPORARY SLOPE DRAINS | 4 EA | | |
| 0054 | 6029000000-E | SP | SAFETY FENCE | 925 LF | | |
| 0055 | 6030000000-E | 1630 | SILT EXCAVATION | 290 CY | | |
| 0056 | 6036000000-E | 1631 | MATTING FOR EROSION CONTROL | 1,400 SY | | |
| 0057 | 6042000000-E | 1632 | 1/4" HARDWARE CLOTH | 300 LF | | |
| 0058 | 6070000000-N | SP | SPECIAL STILLING BASINS | 4 EA | | |

County : Franklin

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|-------------------------------|-------------|-----------|--------|
| 0059 | 6071030000-E | SP | COIR FIBER BAFFLES | 170 LF | | |
| 0060 | 6084000000-E | 1660 | SEEDING & MULCHING | 2 ACR | | |
| 0061 | 6087000000-E | 1660 | MOWING | 1.5 ACR | | |
| 0062 | 6090000000-E | 1661 | SEED FOR REPAIR SEEDING | 50 LB | | |
| 0063 | 6093000000-E | 1661 | FERTILIZER FOR REPAIR SEEDING | 0.25 TON | | |
| 0064 | 6096000000-E | 1662 | SEED FOR SUPPLEMENTAL SEEDING | 50 LB | | |
| 0065 | 6108000000-E | 1665 | FERTILIZER TOPDRESSING | 1.5 TON | | |
| 0066 | 6111000000-E | SP | IMPERVIOUS DIKE | 275 LF | | |
| 0067 | 6114000000-N | SP | SPECIALIZED HAND MOWING | 2.5 HR | | |
| 0068 | 6117000000-N | SP | RESPONSE FOR EROSION CONTROL | 12 EA | | |
| 0069 | 6123000000-E | 1670 | REFORESTATION | 0.1 ACR | | |

CULVERT ITEMS

| | | | | | | |
|------|--------------|-----|---|--------------|------|--|
| 0070 | 8056000000-N | 402 | REMOVAL OF EXISTING STRUCTURE AT STATION ***** (22+03.00-L-) | Lump Sum | L.S. | |
| 0071 | 8126000000-N | 414 | CULVERT EXCAVATION, STA ***** (22+03.00-L-) | Lump Sum | L.S. | |
| 0072 | 8133000000-E | 414 | FOUNDATION CONDITIONING MATERIAL, BOX CULVERT | 146 TON | | |
| 0073 | 8196000000-E | 420 | CLASS A CONCRETE (CULVERT) | 281.7 CY | | |
| 0074 | 8245000000-E | 425 | REINFORCING STEEL (CULVERT) | 44,050 LB | | |

Contract No **C201925**

County (ies): **Franklin**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General