

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+89.500)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	60 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0009	0199000000-E	SP	TEMPORARY SHORING	360 SF		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	40 TON		
0011	0343000000-E	310	15" SIDE DRAIN PIPE	28 LF		
0012	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	36 LF		
0013	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	100 LF		
0014	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	84 LF		
0015	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	72 LF		
0016	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0017	0995000000-E	340	PIPE REMOVAL	231 LF		
0018	1121000000-E	520	AGGREGATE BASE COURSE	82 TON		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0020	1330000000-E	607	INCIDENTAL MILLING	100 SY		
0021	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,200 TON		
0022	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	700 TON		
0023	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	900 TON		
0024	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	30 TON		
0025	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	141 TON		
0026	2000000000-N	806	RIGHT OF WAY MARKERS	27 EA		
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0028	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0029	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0030	2556000000-E	846	SHOULDER BERM GUTTER	86 LF		
0031	3420000000-E	SP	GENERIC GUARDRAIL ITEM PAINTED STEEL BM GUARDRAIL	237.5 LF		
0032	3420000000-E	SP	GENERIC GUARDRAIL ITEM PAINTED STEEL BM GUARDRAIL, SHOP CURVED	100 LF		
0033	3435000000-N	SP	GENERIC GUARDRAIL ITEM PAINTED ADDITIONAL GUARDRAIL POSTS	5 EA		
0034	3435000000-N	SP	GENERIC GUARDRAIL ITEM PAINTED GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0035	3435000000-N	SP	GENERIC GUARDRAIL ITEM PAINTED GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	3435000000-N	SP	GENERIC GUARDRAIL ITEM PAINTED GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0037	3628000000-E	876	RIP RAP, CLASS I	40 TON		
0038	3649000000-E	876	RIP RAP, CLASS B	100 TON		
0039	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,145 SY		
0040	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	181 SF		
0041	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	144 SF		
0042	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	97 SF		
0043	4430000000-N	1130	DRUMS	56 EA		
0044	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0045	4450000000-N	1150	FLAGGER	640 HR		
0046	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1 EA		
0047	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	1 EA		
0048	4485000000-E	1170	PORTABLE CONCRETE BARRIER	200 LF		
0049	4500000000-E	1170	RESET PORTABLE CONCRETE BAR- RIER	100 LF		
0050	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	85 EA		
0051	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	32,844 LF		
0052	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	86 LF		
0053	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	248 LF		
0054	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	2 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	45 EA		
0056	6000000000-E	1605	TEMPORARY SILT FENCE	730 LF		
0057	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	190 TON		
0058	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	255 TON		
0059	6012000000-E	1610	SEDIMENT CONTROL STONE	400 TON		
0060	6015000000-E	1615	TEMPORARY MULCHING	4.5 ACR		
0061	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0062	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.75 TON		
0063	6029000000-E	SP	SAFETY FENCE	410 LF		
0064	6030000000-E	1630	SILT EXCAVATION	1,440 CY		
0065	6036000000-E	1631	MATTING FOR EROSION CONTROL	950 SY		
0066	6037000000-E	SP	COIR FIBER MAT	15 SY		
0067	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	775 SY		
0068	6042000000-E	1632	1/4" HARDWARE CLOTH	50 LF		
0069	6070000000-N	SP	SPECIAL STILLING BASINS	12 EA		
0070	6071030000-E	SP	COIR FIBER BAFFLES	485 LF		
0071	6071050000-E	SP	*** SKIMMER (1-1/2")	2 EA		
0072	6084000000-E	1660	SEEDING & MULCHING	4.5 ACR		
0073	6087000000-E	1660	MOWING	2.5 ACR		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0075	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0076	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0077	6108000000-E	1665	FERTILIZER TOPDRESSING	3.5 TON		
0078	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0079	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0080	6123000000-E	1670	REFORESTATION	0.8 ACR		
STRUCTURE ITEMS						
0081	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+89.50-L-)	Lump Sum	L.S.	
0082	8105520000-E	SP	3'-0" DIA DRILLED PIERS IN SO IL	88.2 LF		
0083	8105620000-E	SP	3'-0" DIA DRILLED PIERS NOT IN SOIL	43 LF		
0084	8111200000-E	SP	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	79.2 LF		
0085	8113000000-N	SP	SID INSPECTION	1 EA		
0086	8114000000-N	SP	SPT TESTING	3 EA		
0087	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0088	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (16+89.50-L-)	Lump Sum	L.S.	
0089	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	8,519 SF		
0090	8161000000-E	420	GROOVING BRIDGE FLOORS	8,790 SF		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	136.3 CY		
0092	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+89.50-L-)	Lump Sum	L.S.	
0093	8217000000-E	425	REINFORCING STEEL (BRIDGE)	27,787 LB		
0094	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,284 LB		
0095	8262000000-E	430	45" PRESTRESSED CONCRETE GIR- DERS	847.96 LF		
0096	8364000000-E	450	HP12X53 STEEL PILES	290 LF		
0097	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	460 TON		
0098	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	515 SY		
0099	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0100	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0101	8867000000-E	SP	GENERIC STRUCTURE ITEM CONCRETE POST & BEAM RAIL	345.67 LF		

0926/Aug13/Q98676.63/D458329520000/E101

Total Amount Of Bid For Entire Project :

Contract No: C201768

County: Guilford

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General