

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0134000000-E	240	DRAINAGE DITCH EXCAVATION	87 CY		
0005	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	460 TON		
0006	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	696 LF		
0007	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	303 LF		
0008	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	2,684 LF		
0009	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	573 LF		
0010	0995000000-E	340	PIPE REMOVAL	361 LF		
0011	1220000000-E	545	INCIDENTAL STONE BASE	250 TON		
0012	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 3")	2,000 SY		
0013	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	4,600 TON		
0014	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	2,150 TON		
0015	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	4,100 TON		
0016	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	545 TON		
0017	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	900 TON		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	2264000000-E	840	PIPE PLUGS	1 CY		
0019	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	53 EA		
0020	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	4 LF		
0021	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	11 EA		
0022	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	6 EA		
0023	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	17 EA		
0024	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	11 EA		
0025	2396000000-N	840	FRAME WITH COVER, STD 840.54	4 EA		
0026	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	9,380 LF		
0027	2591000000-E	848	4" CONCRETE SIDEWALK	4,200 SY		
0028	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	60 EA		
0029	2612000000-E	848	6" CONCRETE DRIVEWAY	650 SY		
0030	2830000000-N	858	ADJUSTMENT OF MANHOLES	12 EA		
0031	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	63 EA		
0032	2860000000-N	859	CONVERT EXISTING CATCH BASIN TO JUNCTION BOX	1 EA		
0033	2905000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX	1 EA		
0034	3030000000-E	862	STEEL BM GUARDRAIL	275 LF		
0035	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	10 EA		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0037	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	250 SY		
0038	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	168 LF		
0039	4078000000-E	903	SUPPORTS, 2-LB STEEL U-CHANNEL	20 EA		
0040	4102000000-N	904	SIGN ERECTION, TYPE E	10 EA		
0041	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	30 EA		
0042	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	960 SF		
0043	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	560 SF		
0044	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	122 SF		
0045	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0046	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	4 EA		
0047	4430000000-N	1130	DRUMS	250 EA		
0048	4435000000-N	1135	CONES	30 EA		
0049	4445000000-E	1145	BARRICADES (TYPE III)	360 LF		
0050	4455000000-N	1150	FLAGGER	2,000 MD		
0051	4480000000-N	1165	TMIA	2 EA		
0052	4510000000-N	SP	POLICE	100 HR		
0053	4516000000-N	1180	SKINNY DRUM	25 EA		
0054	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	34,900 LF		
0055	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,240 LF		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	41 EA		
0057	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (HIGHLY REFLECTIVE ELEMENTS)	11,566 LF		
0058	4847110000-E	1205	POLYUREA PAVEMENT MARKING LINES (8", *****) (HIGHLY REFLECTIVE ELEMENTS)	2,995 LF		
0059	4847140000-E	1205	POLYUREA PAVEMENT MARKING LINES (24", *****) (HIGHLY REFLECTIVE ELEMENTS)	620 LF		
0060	4847200000-N	1205	POLYUREA PAVEMENT MARKING CHARACTER (*****) (HIGHLY REFLECTIVE ELEMENTS)	24 EA		
0061	4847220000-N	1205	POLYUREA PAVEMENT MARKING SYMBOL (*****) (HIGHLY REFLECTIVE ELEMENTS)	77 EA		
0062	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	500 LF		
0063	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0064	5325800000-E	1510	8" WATER LINE	695 LF		
0065	5326200000-E	1510	12" WATER LINE	5,119 LF		
0066	5536000000-E	1515	2" VALVE	1 EA		
0067	5546000000-E	1515	8" VALVE	16 EA		
0068	5558000000-E	1515	12" VALVE	14 EA		
0069	5571000000-E	1515	*** TAPPING VALVE (2")	1 EA		
0070	5572200000-E	1515	12" TAPPING VALVE	1 EA		
0071	5589100000-E	1515	1" AIR RELEASE VALVE	1 EA		
0072	5643000000-E	1515	*** WATER METER (1")	1 EA		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	5643100000-E	1515	3/4" WATER METER	17 EA		
0074	5643200000-E	1515	2" WATER METER	3 EA		
0075	5648000000-N	1515	RELOCATE WATER METER	1 EA		
0076	5649000000-N	1515	RECONNECT WATER METER	5 EA		
0077	5666000000-E	1515	FIRE HYDRANT	9 EA		
0078	5691200000-E	1520	6" SANITARY GRAVITY SEWER	151 LF		
0079	5691300000-E	1520	8" SANITARY GRAVITY SEWER	702 LF		
0080	5691500000-E	1520	12" SANITARY GRAVITY SEWER	160 LF		
0081	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	6 EA		
0082	5775000000-E	1525	4' DIA UTILITY MANHOLE	11 EA		
0083	5776000000-E	1525	5' DIA UTILITY MANHOLE	1 EA		
0084	5781000000-E	1525	UTILITY MANHOLE WALL, 4' DIA	33.5 LF		
0085	5782000000-E	1525	UTILITY MANHOLE WALL, 5' DIA	1.5 LF		
0086	5801000000-E	1530	ABANDON 8" UTILITY PIPE	2,182 LF		
0087	5804000000-E	1530	ABANDON 12" UTILITY PIPE	160 LF		
0088	5815000000-N	1530	REMOVE WATER METER	33 EA		
0089	5815500000-N	1530	REMOVE FIRE HYDRANT	9 EA		
0090	5828000000-N	1530	REMOVE UTILITY MANHOLE	12 EA		
0091	6000000000-E	1605	TEMPORARY SILT FENCE	5,900 LF		
0092	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	100 TON		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0093	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	120 TON		
0094	6012000000-E	1610	SEDIMENT CONTROL STONE	110 TON		
0095	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0096	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0097	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1 TON		
0098	6030000000-E	1630	SILT EXCAVATION	500 CY		
0099	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,300 SY		
0100	6042000000-E	1632	1/4" HARDWARE CLOTH	1,800 LF		
0101	6071030000-E	SP	COIR FIBER BAFFLES	150 LF		
0102	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
0103	6087000000-E	1660	MOWING	10 ACR		
0104	6090000000-E	1661	SEED FOR REPAIR SEEDING	30 LB		
0105	6114000000-N	SP	SPECIALIZED HAND MOWING	20 HR		
0106	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	10 EA		
0107	6890000000-E	SP	CONCRETE STEPS	5 CY		
0108	7000000000-E	1705	PEDESTRIAN SIGNAL HEAD (***, ** SECTION) (16", 1 SECTION WITH COUNTDOWN)	26 EA		
0109	7060000000-E	1705	SIGNAL CABLE	6,700 LF		
0110	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	46 EA		
0111	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	2 EA		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0112	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	4 EA		
0113	7264000000-E	1710	MESSENGER CABLE (3/8")	770 LF		
0114	7288000000-E	1715	PAVED TRENCHING (*****) (1, 2")	120 LF		
0115	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	760 LF		
0116	7301000000-E	1715	DIRECTIONAL DRILL (*****) (3, 2")	130 LF		
0117	7301000000-E	1715	DIRECTIONAL DRILL (*****) (4, 2")	460 LF		
0118	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	10 EA		
0119	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEAVY DUTY)	16 EA		
0120	7360000000-N	1720	WOOD POLE	14 EA		
0121	7372000000-N	1721	GUY ASSEMBLY	28 EA		
0122	7396000000-E	1722	1/2" RISER WITH WEATHERHEAD	2 EA		
0123	7408000000-E	1722	1" RISER WITH WEATHERHEAD	4 EA		
0124	7420000000-E	1722	2" RISER WITH WEATHERHEAD	12 EA		
0125	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	4,250 LF		
0126	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	5,295 LF		
0127	7575142000-N	SP	900MHZ WIRELESS RADIO SYSTEM	4 EA		
0128	7588000000-N	SP	METAL POLE WITH SINGLE MAST ARM	9 EA		
0129	7613000000-N	SP	SOIL TEST	9 EA		
0130	7614100000-E	SP	DRILLED PIER FOUNDATION	54 CY		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0131	7624000000-N	1743	SIGNAL PEDESTAL WITH FOUNDATION	3 EA		
0132	7631000000-N	SP	MAST ARM WITH METAL POLE DESIGN	9 EA		
0133	7636000000-N	1745	SIGN FOR SIGNALS	6 EA		
0134	7648000000-N	SP	RELOCATE EXISTING SIGN	6 EA		
0135	7684000000-N	1750	SIGNAL CABINET FOUNDATION	4 EA		
0136	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	4 EA		
0137	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	23 EA		
0138	7901000000-N	1753	CABINET BASE EXTENDER	4 EA		
0139	7980000000-N	SP	GENERIC SIGNAL ITEM FURNISH WIRELESS RADIO LIGHTNING ARRESTOR	2 EA		
0140	7980000000-N	SP	GENERIC SIGNAL ITEM FURNISH WIRELESS RADIO MODEM	1 EA		
0141	7980000000-N	SP	GENERIC SIGNAL ITEM POWDER COAT FOR PEDESTRIAN PEDESTAL	3 EA		
0142	7980000000-N	SP	GENERIC SIGNAL ITEM POWDER COAT FOR SINGLE MAST ARM WITH METAL POLE	9 EA		
0143	8203000000-E	420	CLASS A CONCRETE (RETAINING WALL)	310 CY		
0144	8832000000-N	SP	GENERIC RETAINING WALL ITEM ARCHITECTURAL CONCRETE SURFACE TREATMENT	Lump Sum	L.S.	
0145	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	

Contract No **C201858**

County (ies): **Henderson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General