

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0015000000-N	205	SEALING ABANDONED WELLS	5 EA		
0006	0022000000-E	225	UNCLASSIFIED EXCAVATION	22,700 CY		
0007	0036000000-E	225	UNDERCUT EXCAVATION	11,450 CY		
000E	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	10,500 TON		
0009	0106000000-E	230	BORROW EXCAVATION	200,000 CY		
001C	0134000000-E	240	DRAINAGE DITCH EXCAVATION	750 CY		
0011	0141000000-E	240	BERM DITCH CONSTRUCTION	1,000 LF		
0012	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	16,340 SY		
0013	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	6,990 SY		
0014	0192000000-N	260	PROOF ROLLING	40 HR		
001E	0195000000-E	265	SELECT GRANULAR MATERIAL	2,000 CY		
0016	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	16,650 SY		
0017	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	3,182 TON		
001E	0343000000-E	310	15" SIDE DRAIN PIPE	644 LF		
0019	0344000000-E	310	18" SIDE DRAIN PIPE	160 LF		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
002C	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	24 LF		
0021	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	100 LF		
0022	0995000000-E	340	PIPE REMOVAL	7,207 LF		
0023	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0024	1044000000-E	501	LIME TREATED SOIL (SLURRY METHOD)	56,810 SY		
002E	1066000000-E	501	LIME FOR LIME TREATED SOIL	570 TON		
002E	1110000000-E	510	STABILIZER AGGREGATE	1,500 TON		
0027	1121000000-E	520	AGGREGATE BASE COURSE	57,500 TON		
002E	1176000000-E	542	SOIL CEMENT BASE	37,870 SY		
002E	1187000000-E	542	PORTLAND CEMENT FOR SOIL CE- MENT BASE	1,042 TON		
003C	1209000000-E	543	ASPHALT CURING SEAL	14,210 GAL		
0031	1220000000-E	545	INCIDENTAL STONE BASE	2,000 TON		
0032	1275000000-E	600	PRIME COAT	260 GAL		
0033	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	610 SY		
0034	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	44,560 SY		
003E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	7,120 TON		
003E	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	24,540 TON		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	8,475	TON	
003E	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	35,390	TON	
003E	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	7,630	TON	
004C	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	27,515	TON	
0041	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	2,975	TON	
0042	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	4,085	TON	
004E	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	1,655	TON	
0044	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	380	TON	
004E	2022000000-E	815	SUBDRAIN EXCAVATION	336	CY	
004E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	168	CY	
0047	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,000	LF	
004E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	30	EA	
004E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2	EA	
005C	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12	LF	
0051	2143000000-E	818	BLOTTING SAND	20	TON	
0052	2209000000-E	838	ENDWALLS	3.4	CY	
005E	2253000000-E	840	PIPE COLLARS	1	CY	
0054	2264000000-E	840	PIPE PLUGS	1	CY	

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	2275000000-E	SP	FLOWABLE FILL	25 CY		
005E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	338 EA		
0057	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	131 LF		
005E	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	68 EA		
005E	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	28 EA		
006C	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	7 EA		
0061	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	42 EA		
0062	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	72 EA		
006E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	120 EA		
0064	2396000000-N	840	FRAME WITH COVER, STD 840.54	3 EA		
006E	2535000000-E	846	***X*** CONCRETE CURB (8" x 18")	1,240 LF		
006E	2538000000-E	846	***.*** CONCRETE CURB & GUTTER (2'-0")	370 LF		
0067	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	31,320 LF		
006E	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	60,700 LF		
006E	2570000000-N	SP	MODIFIED CONCRETE FLUME	4 EA		
007C	2591000000-E	848	4" CONCRETE SIDEWALK	22,210 SY		
0071	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	150 EA		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	2612000000-E	848	6" CONCRETE DRIVEWAY	3,290 SY		
0073	2619000000-E	850	4" CONCRETE PAVED DITCH	60 SY		
0074	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	4,550 SY		
007E	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	1 EA		
0076	2830000000-N	858	ADJUSTMENT OF MANHOLES	13 EA		
0077	2860000000-N	859	CONVERT EXISTING CATCH BASIN TO JUNCTION BOX	3 EA		
007E	2905000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX	3 EA		
007E	3030000000-E	862	STEEL BM GUARDRAIL	1,100 LF		
008C	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	2 EA		
0081	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0082	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	7 EA		
008E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	7 EA		
0084	3628000000-E	876	RIP RAP, CLASS I	650 TON		
008E	3649000000-E	876	RIP RAP, CLASS B	165 TON		
008E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	3,490 SY		
0087	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	4,086 LF		
008E	4102000000-N	904	SIGN ERECTION, TYPE E	271 EA		
008E	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	5 EA		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
009C	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	80	EA	
0091	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	799	SF	
0092	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	192	SF	
0093	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	45	SF	
0094	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	1	EA	
009E	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	3	EA	
009E	4422000000-N	1120	CHANGEABLE MESSAGE SIGN (SHORT TERM)	40	DAY	
0097	4430000000-N	1130	DRUMS	400	EA	
009E	4445000000-E	1145	BARRICADES (TYPE III)	1,325	LF	
009E	4455000000-N	1150	FLAGGER	600	MD	
010C	4480000000-N	1165	TMIA	1	EA	
0101	4507000000-E	SP	WATER FILLED BARRIER	548	LF	
0102	4510000000-N	SP	POLICE	300	HR	
0103	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	2,800	EA	
0104	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	29	EA	
010E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	306	EA	
010E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	556,950	LF	
0107	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	14,930	LF	

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
010E	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	4,600 LF		
010E	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	58 EA		
011C	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	612 EA		
0111	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (STANDARD GLASS BEADS)	128,350 LF		
0112	4847110000-E	1205	POLYUREA PAVEMENT MARKING LINES (8", *****) (STANDARD GLASS BEADS)	7,265 LF		
0113	4847140000-E	1205	POLYUREA PAVEMENT MARKING LINES (24", *****) (STANDARD GLASS BEADS)	1,600 LF		
0114	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	703 EA		
011E	4915000000-E	1264	7' U-CHANNEL POSTS	6 EA		
011E	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	6 EA		
0117	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
011E	5325200000-E	1510	2" WATER LINE	250 LF		
011E	5326200000-E	1510	12" WATER LINE	203 LF		
012C	5327000000-E	1510	20" WATER LINE	35 LF		
0121	5536000000-E	1515	2" VALVE	1 EA		
0122	5648000000-N	1515	RELOCATE WATER METER	12 EA		
0123	5649000000-N	1515	RECONNECT WATER METER	5 EA		
0124	5672000000-N	1515	RELOCATE FIRE HYDRANT	1 EA		
012E	5691300000-E	1520	8" SANITARY GRAVITY SEWER	16 LF		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0126	5775000000-E	1525	4' DIA UTILITY MANHOLE	1	EA	
0127	5781000000-E	1525	UTILITY MANHOLE WALL, 4' DIA	7	LF	
0128	5804000000-E	1530	ABANDON 12" UTILITY PIPE	190	LF	
0129	5812000000-E	1530	ABANDON 20" UTILITY PIPE	20	LF	
0130	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE 1" RPZ BACKFLOW PREVENTION ASSEMBLY WITH NEW VAULT	1	EA	
0131	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE 1-1/2" WATER METER WITH NEW VAULT	4	EA	
0132	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE 2" RPZ BACKFLOW PREVENTION ASSEMBLY	3	EA	
0133	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE 2" RPZ BACKFLOW PREVENTION ASSEMBLY WITH NEW VAULT	1	EA	
0134	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE 2" WATER METER WITH NEW VAULT	9	EA	
0135	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE FIRE HYDRANT AND ADJU ST VALVE BOX TO PROPOSED FINISHED GRADE	3	EA	
0136	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE FIRE HYDRANT WITH NEW 6" GATE VALVE	10	EA	
0137	5882000000-N	SP	GENERIC UTILITY ITEM REMOVE EXISTING SANITARY SEWER PUMP STATION	1	EA	
0138	6000000000-E	1605	TEMPORARY SILT FENCE	12,290	LF	
0139	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	2,525	TON	

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
014C	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	5,680	TON	
0141	6012000000-E	1610	SEDIMENT CONTROL STONE	6,640	TON	
0142	6015000000-E	1615	TEMPORARY MULCHING	87.5	ACR	
0143	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	3,650	LB	
0144	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	15.5	TON	
014E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	290	LF	
014E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1	EA	
0147	6029000000-E	SP	SAFETY FENCE	875	LF	
014E	6030000000-E	1630	SILT EXCAVATION	27,570	CY	
014E	6036000000-E	1631	MATTING FOR EROSION CONTROL	31,000	SY	
015C	6037000000-E	SP	COIR FIBER MAT	160	SY	
0151	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	2,765	SY	
0152	6042000000-E	1632	1/4" HARDWARE CLOTH	6,390	LF	
0153	6071010000-E	SP	WATTLE	1,740	LF	
0154	6071020000-E	SP	POLYACRYLAMIDE (PAM)	1,088	LB	
015E	6071030000-E	SP	COIR FIBER BAFFLES	2,325	LF	
015E	6071050000-E	SP	*** SKIMMER (1-1/2")	12	EA	
0157	6071050000-E	SP	*** SKIMMER (2")	10	EA	

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
015E	6071050000-E	SP	*** SKIMMER (2-1/2")	1 EA		
0159	6071050000-E	SP	*** SKIMMER (3")	1 EA		
016C	6071050000-E	SP	*** SKIMMER (4")	2 EA		
0161	6084000000-E	1660	SEEDING & MULCHING	109.5 ACR		
0162	6087000000-E	1660	MOWING	60 ACR		
0163	6090000000-E	1661	SEED FOR REPAIR SEEDING	750 LB		
0164	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	2 TON		
0165	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	2,400 LB		
0166	6108000000-E	1665	FERTILIZER TOPDRESSING	71.75 TON		
0167	6114000000-N	SP	SPECIALIZED HAND MOWING	3.5 HR		
016E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	54 EA		
0169	6123000000-E	1670	REFORESTATION	0.75 ACR		
017C	7000000000-E	1705	PEDESTRIAN SIGNAL HEAD (***, ** SECTION) (16", 1 SECTION W/COUNTDOWN)	30 EA		
0171	7060000000-E	1705	SIGNAL CABLE	21,460 LF		
0172	7108000000-E	1705	VEHICLE SIGNAL HEAD (12", 1 SECTION)	4 EA		
0173	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	96 EA		
0174	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	7 EA		
017E	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	25 EA		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0176	7252000000-E	1710	MESSENGER CABLE (1/4")	20,100	LF	
0177	7264000000-E	1710	MESSENGER CABLE (3/8")	6,680	LF	
0178	7279000000-E	1715	TRACER WIRE	150	LF	
0179	7288000000-E	1715	PAVED TRENCHING (*****) (1, 2")	500	LF	
0180	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	4,560	LF	
0181	7301000000-E	1715	DIRECTIONAL DRILL (*****) (1, 2")	40	LF	
0182	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	43	EA	
0183	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEAVY DUTY)	6	EA	
0184	7360000000-N	1720	WOOD POLE	23	EA	
0185	7372000000-N	1721	GUY ASSEMBLY	94	EA	
0186	7408000000-E	1722	1" RISER WITH WEATHERHEAD	6	EA	
0187	7420000000-E	1722	2" RISER WITH WEATHERHEAD	22	EA	
0188	7432000000-E	1722	2" RISER WITH HEAT SHRINK TUBING	6	EA	
0189	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	9,120	LF	
0190	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	28,560	LF	
0191	7481000000-N	SP	SITE SURVEY	6	EA	
0192	7481200000-N	SP	LUMINAIRE ARM FOR VIDEO SYSTEM	21	EA	
0193	7481240000-N	SP	CAMERA WITHOUT INTERNAL LOOP EMULATOR PROCESSING UNIT	21	EA	

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0194	7481260000-N	SP	EXTERNAL LOOP EMULATOR PROCESSING UNIT	6 EA		
0195	7481280000-N	SP	RELOCATE CAMERA SENSOR UNIT	7 EA		
0196	7516000000-E	1730	COMMUNICATIONS CABLE (**FIBER) (12)	22,820 LF		
0197	7540000000-N	1731	SPLICE ENCLOSURE	1 EA		
0198	7552000000-N	1731	INTERCONNECT CENTER	6 EA		
0199	7564000000-N	1732	FIBER-OPTIC TRANSCEIVER, DROP & REPEAT	6 EA		
0200	7566000000-N	1733	DELINEATOR MARKER	6 EA		
0201	7568000000-N	SP	FURNISH FIBER-OPTIC RESTORATION KIT	1 EA		
0202	7570000000-N	SP	FURNISH FIBER-OPTIC POWER METER	1 EA		
0203	7572000000-N	SP	FURNISH OPTICAL LIGHT GENERATOR	1 EA		
0204	7574000000-N	SP	FURNISH FIBER-OPTIC TRANSCEIVER	1 EA		
0205	7576000000-N	SP	METAL STRAIN SIGNAL POLE	24 EA		
0206	7613000000-N	SP	SOIL TEST	24 EA		
0207	7614100000-E	SP	DRILLED PIER FOUNDATION	144 CY		
0208	7624000000-N	1743	SIGNAL PEDESTAL WITH FOUNDATION	15 EA		
0209	7636000000-N	1745	SIGN FOR SIGNALS	31 EA		
0210	7684000000-N	1750	SIGNAL CABINET FOUNDATION	5 EA		
0211	7688000000-N	1753	CABINET BASE ADAPTER	5 EA		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0212	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	5 EA		
0213	7768000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)	1 EA		
0214	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	82 EA		
0215	7912000000-N	1755	BEACON CONTROLLER ASSEMBLY & CABINET (*****) (TYPE F1)	1 EA		
0216	7948000000-N	SP	TRAFFIC SIGNAL REMOVAL	1 EA		
0217	7980000000-N	SP	GENERIC SIGNAL ITEM GPS UNIT	6 EA		
0218	7980000000-N	SP	GENERIC SIGNAL ITEM WOOD POLE (50')	1 EA		
0219	8438000000-E	453	GENERIC RETAINING WALL ITEM GRAVITY RETAINING WALL (LOCATION #6)	293 SF		
0220	8839000000-E	SP	GENERIC RETAINING WALL ITEM STEEL PIPE HANDRAIL FOR RETAINING WALLS	550 LF		
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0221 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	16,002 LF		
0222 AA1	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	5,050 LF		
0223 AA1	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	6,058 LF		
0224 AA1	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	712 LF		
0225 AA1	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	696 LF		

*** OR ***

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0226 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	13,990	LF	
0227 AA2	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	4,190	LF	
022E AA2	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	4,326	LF	
022E AA2	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	568	LF	
023C AA2	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	408	LF	
0231 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	2,012	LF	
0232 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	860	LF	
0233 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	1,732	LF	
0234 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (30")	144	LF	
023E AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (36")	288	LF	
*** OR ***						
0236 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	13,990	LF	
0237 AA3	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	4,190	LF	
023E AA3	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	4,326	LF	
023E AA3	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	568	LF	
024C AA3	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	408	LF	

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0241 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (15", 0.064")	2,012 LF		
0242 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (18", 0.064")	860 LF		
0243 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (24", 0.064")	1,732 LF		
0244 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (30", 0.079")	144 LF		
0245 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (36", 0.079")	288 LF		
***** END SCHEDULE AA *****						
***** BEGIN SCHEDULE AB ***** (2 ALTERNATES) *****						
0246 AB1	8438000000-E	453	GENERIC RETAINING WALL ITEM GRAVITY RETAINING WALL (LOCATION #1)	267 SF		
*** OR ***						
0247 AB2	8847000000-E	SP	GENERIC RETAINING WALL ITEM SEGMENTAL GRAVITY RETAINING WALL (LOCATION #1)	267 SF		
***** END SCHEDULE AB *****						
***** BEGIN SCHEDULE AC ***** (2 ALTERNATES) *****						
0248 AC1	8438000000-E	453	GENERIC RETAINING WALL ITEM GRAVITY RETAINING WALL (LOCATION #2)	216 SF		
*** OR ***						
0249 AC2	8847000000-E	SP	GENERIC RETAINING WALL ITEM SEGMENTAL GRAVITY RETAINING WALL (LOCATION #2)	216 SF		
***** END SCHEDULE AC *****						

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
***** BEGIN SCHEDULE AD ***** ***** (2 ALTERNATES) *****						
025C AD1	8438000000-E	453	GENERIC RETAINING WALL ITEM GRAVITY RETAINING WALL (LOCATION #3)	359	SF	
*** OR ***						
0251 AD2	8847000000-E	SP	GENERIC RETAINING WALL ITEM SEGMENTAL GRAVITY RETAINING WALL (LOCATION #3)	359	SF	
***** END SCHEDULE AD *****						
***** BEGIN SCHEDULE AE ***** ***** (2 ALTERNATES) *****						
0252 AE1	8438000000-E	453	GENERIC RETAINING WALL ITEM GRAVITY RETAINING WALL (LOCATION #4)	333	SF	
*** OR ***						
0253 AE2	8847000000-E	SP	GENERIC RETAINING WALL ITEM SEGMENTAL GRAVITY RETAINING WALL (LOCATION #4)	333	SF	
***** END SCHEDULE AE *****						
***** BEGIN SCHEDULE AF ***** ***** (2 ALTERNATES) *****						
0254 AF1	8438000000-E	453	GENERIC RETAINING WALL ITEM GRAVITY RETAINING WALL (LOCATION #5)	270	SF	
*** OR ***						
025E AF2	8847000000-E	SP	GENERIC RETAINING WALL ITEM SEGMENTAL GRAVITY RETAINING WALL (LOCATION #5)	270	SF	
***** END SCHEDULE AF *****						
1044/Aug13/Q1808524.9/D1075164940000/E255			Total Amount Of Bid For Entire Project :			

Contract No **C201902**

County (ies): **Iredell**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General