

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1245000000-E	SP	SHOULDER RECONSTRUCTION	3.19	SMI	
0003	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	6,252	TON	
0004	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	5,750	TON	
0005	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	294	TON	
0006	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	345	TON	
0007	1704000000-E	SP	PATCHING EXISTING PAVEMENT	11,215	TON	
0008	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	28,724	LF	
0009	1891000000-E	SP	GENERIC PAVING ITEM MILLING ASPHALT PAVEMENT, 2-1/2"	64,640	SY	
0010	2099000000-E	816	SHOULDER DRAIN	14,362	LF	
0011	2110000000-E	816	4" SHOULDER DRAIN PIPE	14,362	LF	
0012	2121000000-E	816	4" OUTLET PIPE FOR SHOULDER DRAINS	480	LF	
0013	2132000000-N	816	CONCRETE PAD FOR SHOULDER DRAIN PIPE OUTLET	48	EA	
0014	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2	EA	
0015	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2	EA	
0016	4430000000-N	1130	DRUMS	200	EA	
0017	4480000000-N	1165	TMIA	1	EA	
0018	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	28,724	LF	

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	3,590	LF	
0020	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	64,628	LF	
0021	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	186	EA	

1100/Aug12/Q243809.19/D58136100000/E21

Total Amount Of Bid For Entire Project :

Contract No **C201856**

County (ies): **McDowell**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General