

County : Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (26+37.50)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	43 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	5 TON		
0010	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	36 LF		
0011	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0012	0995000000-E	340	PIPE REMOVAL	20 LF		
0013	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	430 TON		
0015	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	355 TON		
0016	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	45 TON		
0017	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0018	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		

County : Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2556000000-E	846	SHOULDER BERM GUTTER	160 LF		
0020	3030000000-E	862	STEEL BM GUARDRAIL	600 LF		
0021	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0022	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0023	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0024	3649000000-E	876	RIP RAP, CLASS B	30 TON		
0025	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	255 SY		
0026	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	303 SF		
0027	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	57 SF		
0028	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
0029	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	7,000 LF		
0030	6000000000-E	1605	TEMPORARY SILT FENCE	520 LF		
0031	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0032	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	100 TON		
0033	6012000000-E	1610	SEDIMENT CONTROL STONE	30 TON		
0034	6015000000-E	1615	TEMPORARY MULCHING	3 ACR		
0035	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0036	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.5 TON		
0037	6029000000-E	SP	SAFETY FENCE	330 LF		

County : Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	6030000000-E	1630	SILT EXCAVATION	670 CY		
0039	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,300 SY		
0040	6037000000-E	SP	COIR FIBER MAT	25 SY		
0041	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	150 SY		
0042	6042000000-E	1632	1/4" HARDWARE CLOTH	40 LF		
0043	6071030000-E	SP	COIR FIBER BAFFLES	265 LF		
0044	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		
0045	6084000000-E	1660	SEEDING & MULCHING	3.5 ACR		
0046	6087000000-E	1660	MOWING	2 ACR		
0047	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0048	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0049	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0050	6108000000-E	1665	FERTILIZER TOPDRESSING	2.25 TON		
0051	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0052	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
STRUCTURE ITEMS						
0053	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (26+37.50-L-)	Lump Sum	L.S.	
0054	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (26+37.50-L-)	Lump Sum	L.S.	

County : Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	40.5 CY		
0056	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (26+37.50-L-)	Lump Sum	L.S.	
0057	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,170 LB		
0058	8364000000-E	450	HP12X53 STEEL PILES	500 LF		
0059	8433000000-E	SP	*** STEEL SHEET PILES (18")	980 SF		
0060	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	185.5 LF		
0061	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	440 TON		
0062	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	490 SY		
0063	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0064	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	1,020.25 LF		
0857/Aug01/Q23519.75/D294290680000/E64			Total Amount Of Bid For Entire Project :			

Contract No **C201930**

County (ies): **Union**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General