

County : Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (15 + 81.00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	35 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	5 TON		
0011	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	40 LF		
0012	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0013	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	418 TON		
0015	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	280 TON		
0016	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	37 TON		
0017	2000000000-N	806	RIGHT OF WAY MARKERS	20 EA		
0018	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		

County : Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		
002C	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0021	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0022	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0023	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0024	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
002E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0026	2556000000-E	846	SHOULDER BERM GUTTER	55 LF		
0027	3030000000-E	862	STEEL BM GUARDRAIL	100 LF		
002E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
002E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
003C	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0031	3649000000-E	876	RIP RAP, CLASS B	295 TON		
0032	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,965 SY		
0033	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	16 LF		
0034	4102000000-N	904	SIGN ERECTION, TYPE E	2 EA		
003E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	9 EA		
0036	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	377 SF		

County : Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94	SF	
003E	4445000000-E	1145	BARRICADES (TYPE III)	64	LF	
003E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,630	LF	
004C	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,630	LF	
0041	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	340	LF	
0042	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	20	EA	
004E	6000000000-E	1605	TEMPORARY SILT FENCE	3,300	LF	
0044	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	230	TON	
004E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	240	TON	
004E	6012000000-E	1610	SEDIMENT CONTROL STONE	70	TON	
0047	6015000000-E	1615	TEMPORARY MULCHING	4.5	ACR	
004E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
004E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5	TON	
005C	6024000000-E	1622	TEMPORARY SLOPE DRAINS	480	LF	
0051	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4	EA	
0052	6029000000-E	SP	SAFETY FENCE	250	LF	
005E	6030000000-E	1630	SILT EXCAVATION	400	CY	
0054	6036000000-E	1631	MATTING FOR EROSION CONTROL	7,700	SY	

County : Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	130 SY		
005E	6042000000-E	1632	1/4" HARDWARE CLOTH	40 LF		
0057	6071030000-E	SP	COIR FIBER BAFFLES	200 LF		
005E	6084000000-E	1660	SEEDING & MULCHING	8 ACR		
005E	6087000000-E	1660	MOWING	2 ACR		
006C	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0061	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0062	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0063	6108000000-E	1665	FERTILIZER TOPDRESSING	2.5 TON		
0064	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
006E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		

STRUCTURE ITEMS

006E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+81.00 -L-)	Lump Sum	L.S.	
0067	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (15+81.00 -L-)	Lump Sum	L.S.	
006E	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	2,508 SF		
006E	8161000000-E	420	GROOVING BRIDGE FLOORS	2,621 SF		
007C	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	39.5 CY		

County : Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15 + 81.00 -L-)	Lump Sum	L.S.	
0072	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,859 LB		
0073	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	83,900 LS		
0074	8364000000-E	450	HP12X53 STEEL PILES	280 LF		
007E	8503000000-E	460	CONCRETE BARRIER RAIL	165.82 LF		
007E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	293 TON		
0077	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	425 SY		
007E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
007E	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1316/Aug04/Q117733.07/D350499530000/E79

Total Amount Of Bid For Entire Project :

Contract No **C201931**

County (ies): **Warren**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General