

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	4,100 CY		
0005	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	3,000 TON		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	90 CY		
0007	0141000000-E	240	BERM DITCH CONSTRUCTION	5,400 LF		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	3,000 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	4,500 SY		
001C	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	170 TON		
0011	0343000000-E	310	15" SIDE DRAIN PIPE	140 LF		
0012	0344000000-E	310	18" SIDE DRAIN PIPE	275 LF		
0013	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	810 LF		
0014	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	75 LF		
0015	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	100 LF		
0016	0908000000-E	310	**** X **** BIT COAT CS PIPE ARCH CULVERTS, TYPE B ***** THICK (142" X 91", 0.138")	92 LF		
0017	0908000000-E	310	**** X **** BIT COAT CS PIPE ARCH CULVERTS, TYPE B ***** THICK (64" X 43", 0.109")	100 LF		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0908000000-E	310	**** X **** BIT COAT CS PIPE ARCH CULVERTS, TYPE B ***** THICK (73" X 55", 0.109")	126 LF		
001E	0995000000-E	340	PIPE REMOVAL	545 LF		
002C	1220000000-E	545	INCIDENTAL STONE BASE	493 TON		
0021	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	6,950 SY		
0022	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	3,710 TON		
0023	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	3,530 TON		
0024	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,980 TON		
002E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	505 TON		
002E	2022000000-E	815	SUBDRAIN EXCAVATION	224 CY		
0027	2033000000-E	815	SUBDRAIN FINE AGGREGATE	168 CY		
002E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,000 LF		
002E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	30 EA		
003C	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0031	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0032	2209000000-E	838	ENDWALLS	4.2 CY		
0033	2220000000-E	838	REINFORCED ENDWALLS	18.3 CY		
0034	2275000000-E	SP	FLOWABLE FILL	10 CY		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	10 EA		
0036	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	5 CY		
0037	2354000000-N	840	FRAME WITH GRATE, STD 840.22	1 EA		
003E	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	3 EA		
003E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	9 EA		
004C	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	310 LF		
0041	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	2,730 LF		
0042	2612000000-E	848	6" CONCRETE DRIVEWAY	10 SY		
004E	3030000000-E	862	STEEL BM GUARDRAIL	3,162.5 LF		
0044	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	87.5 LF		
004E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	18 EA		
004E	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
0047	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	16 EA		
004E	3628000000-E	876	RIP RAP, CLASS I	50 TON		
004E	3635000000-E	876	RIP RAP, CLASS II	40 TON		
005C	3649000000-E	876	RIP RAP, CLASS B	40 TON		
0051	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	210 SY		
0052	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	1,536 SF		
005E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	144 SF		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	314	SF	
005E	4430000000-N	1130	DRUMS	225	EA	
005E	4435000000-N	1135	CONES	125	EA	
0057	4445000000-E	1145	BARRICADES (TYPE III)	208	LF	
005E	4455000000-N	1150	FLAGGER	480	MD	
005E	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	96	EA	
006C	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	9,947	LF	
0061	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	12,638	LF	
0062	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	547	LF	
0063	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	91	LF	
0064	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	18	EA	
006E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	32,800	LF	
006E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	208	EA	
0067	5325600000-E	1510	6" WATER LINE	1,826	LF	
006E	5540000000-E	1515	6" VALVE	5	EA	
006E	5648000000-N	1515	RELOCATE WATER METER	3	EA	
007C	5666000000-E	1515	FIRE HYDRANT	1	EA	
0071	5672000000-N	1515	RELOCATE FIRE HYDRANT	1	EA	

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	5691300000-E	1520	8" SANITARY GRAVITY SEWER	768.8	LF	
0073	5775000000-E	1525	4' DIA UTILITY MANHOLE	7	EA	
0074	5781000000-E	1525	UTILITY MANHOLE WALL, 4' DIA	27	LF	
007E	5801000000-E	1530	ABANDON 8" UTILITY PIPE	619	LF	
007E	5816000000-N	1530	ABANDON UTILITY MANHOLE	2	EA	
0077	6000000000-E	1605	TEMPORARY SILT FENCE	670	LF	
007E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	160	TON	
007E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	430	TON	
008C	6012000000-E	1610	SEDIMENT CONTROL STONE	495	TON	
0081	6015000000-E	1615	TEMPORARY MULCHING	15.5	ACR	
0082	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	550	LB	
0083	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2.25	TON	
0084	6024000000-E	1622	TEMPORARY SLOPE DRAINS	470	LF	
008E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	13	EA	
008E	6029000000-E	SP	SAFETY FENCE	1,800	LF	
0087	6030000000-E	1630	SILT EXCAVATION	2,520	CY	
008E	6036000000-E	1631	MATTING FOR EROSION CONTROL	5,290	SY	
008E	6037000000-E	SP	COIR FIBER MAT	100	SY	
009C	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,395	SY	

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	6042000000-E	1632	1/4" HARDWARE CLOTH	820	LF	
0092	6045000000-E	SP	*** TEMPORARY PIPE (18")	45	LF	
0093	6071030000-E	SP	COIR FIBER BAFFLES	405	LF	
0094	6071050000-E	SP	*** SKIMMER (3")	16	EA	
0095	6084000000-E	1660	SEEDING & MULCHING	15.5	ACR	
0096	6087000000-E	1660	MOWING	9.5	ACR	
0097	6090000000-E	1661	SEED FOR REPAIR SEEDING	150	LB	
0098	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5	TON	
0099	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	375	LB	
0100	6108000000-E	1665	FERTILIZER TOPDRESSING	11.5	TON	
0101	6114000000-N	SP	SPECIALIZED HAND MOWING	7.5	HR	
0102	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	36	EA	
0103	7060000000-E	1705	SIGNAL CABLE	810	LF	
0104	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	8	EA	
0105	7288000000-E	1715	PAVED TRENCHING (***** (1, 2")	30	LF	
0106	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2")	660	LF	
0107	7301000000-E	1715	DIRECTIONAL DRILL (***** (2, 2")	200	LF	
0108	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	8	EA	
0109	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	625	LF	

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
011C	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	1,150	LF	
0111	7588000000-N	SP	METAL POLE WITH SINGLE MAST ARM	2	EA	
0112	7590000000-N	SP	METAL POLE WITH DUAL MAST ARM	1	EA	
0113	7613000000-N	SP	SOIL TEST	3	EA	
0114	7614100000-E	SP	DRILLED PIER FOUNDATION	18	CY	
0115	7631000000-N	SP	MAST ARM WITH METAL POLE DE- SIGN	3	EA	
0116	7636000000-N	1745	SIGN FOR SIGNALS	1	EA	
0117	7684000000-N	1750	SIGNAL CABINET FOUNDATION	1	EA	
0118	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	1	EA	
0119	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	3	EA	
012C	7901000000-N	1753	CABINET BASE EXTENDER	1	EA	

1101/Sep11/Q130830.55/D501983180000/E120

Total Amount Of Bid For Entire Project :

**Contract No**     **C201777**

**County (ies):**    **Macon**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General