

County : Richmond, Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	4 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	188,000 CY		
0006	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (434+27.00 -L- LT)	Lump Sum	L.S.	
0007	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (434+27.00 -L- RT)	Lump Sum	L.S.	
0008	0036000000-E	225	UNDERCUT EXCAVATION	23,850 CY		
0009	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	1,000 TON		
0010	0106000000-E	230	BORROW EXCAVATION	68,000 CY		
0011	0134000000-E	240	DRAINAGE DITCH EXCAVATION	5,275 CY		
0012	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	15,350 SY		
0013	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	16,790 SY		
0014	0192000000-N	260	PROOF ROLLING	48 HR		
0015	0195000000-E	265	SELECT GRANULAR MATERIAL	29,000 CY		
0016	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	17,200 SY		
0017	0199000000-E	SP	TEMPORARY SHORING	32,400 SF		
0018	0245000000-E	SP	GENERIC GRADING ITEM CONTAMINATED WATER DISPOSAL	2,000 GAL		

County : Richmond, Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0248000000-N	SP	GENERIC GRADING ITEM HAZARDOUS WASTE RETENTION BASIN	Lump Sum	L.S.	
0020	0255000000-E	SP	GENERIC GRADING ITEM EXCAVATION, HAULING, AND DISPOSAL OF CONTAMINATED SOIL	200 TON		
0021	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	4,472 TON		
0022	0343000000-E	310	15" SIDE DRAIN PIPE	880 LF		
0023	0344000000-E	310	18" SIDE DRAIN PIPE	300 LF		
0024	0345000000-E	310	24" SIDE DRAIN PIPE	200 LF		
0025	0588000000-E	310	18" CS PIPE CULVERTS, 0.064" THICK	324 LF		
0026	0630000000-E	310	***X ***X *** CS PIPE TEES, ***** THICK (18" X 18" X 18", 0.064")	2 EA		
0027	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	60 LF		
0028	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	20 LF		
0029	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	40 LF		
0030	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0031	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	2 EA		
0032	0808000000-E	310	24" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	4 EA		
0033	0974000000-E	SP	*** WELDED STEEL PIPE, ***** THICK, GRADE B, (UNDER RR) (30", 0.079")	120 LF		
0034	0995000000-E	340	PIPE REMOVAL	4,624 LF		
0035	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	

County : Richmond, Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	1110000000-E	510	STABILIZER AGGREGATE	2,500 TON		
0037	1121000000-E	520	AGGREGATE BASE COURSE	112,200 TON		
0038	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
0039	1275000000-E	600	PRIME COAT	1,356 GAL		
0040	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	200 SY		
0041	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	7,610 SY		
0042	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	690 TON		
0043	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	26,695 TON		
0044	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	59,580 TON		
0045	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	60,625 TON		
0046	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	720 TON		
0047	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	4,026 TON		
0048	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	3,638 TON		
0049	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	350 TON		
0050	2000000000-N	806	RIGHT OF WAY MARKERS	171 EA		
0051	2022000000-E	815	SUBDRAIN EXCAVATION	672 CY		
0052	2033000000-E	815	SUBDRAIN FINE AGGREGATE	336 CY		
0053	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	2,000 LF		

County : Richmond, Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	60 EA		
0055	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	4 EA		
0056	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	24 LF		
0057	2209000000-E	838	ENDWALLS	6 CY		
0058	2220000000-E	838	REINFORCED ENDWALLS	8 CY		
0059	2253000000-E	840	PIPE COLLARS	5 CY		
0060	2264000000-E	840	PIPE PLUGS	1 CY		
0061	2275000000-E	SP	FLOWABLE FILL	31 CY		
0062	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	135 EA		
0063	2354200000-N	840	FRAME WITH GRATE, STD 840.24	8 EA		
0064	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	5 EA		
0065	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	33 EA		
0066	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	59 EA		
0067	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	3 EA		
0068	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	6 EA		
0069	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	10 EA		
0070	2396000000-N	840	FRAME WITH COVER, STD 840.54	5 EA		
0071	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	18 EA		

County : Richmond, Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	2462000000-E	SP	*** SLUICE GATE (25")	1 EA		
0073	2462000000-E	SP	*** SLUICE GATE (32")	2 EA		
0074	2462000000-E	SP	*** SLUICE GATE (38-3/4")	1 EA		
0075	2535000000-E	846	***X *** CONCRETE CURB (8" X 6")	730 LF		
0076	2538000000-E	846	***.*** CONCRETE CURB & GUTTER (2'-9")	21,300 LF		
0077	2556000000-E	846	SHOULDER BERM GUTTER	4,565 LF		
0078	2619000000-E	850	4" CONCRETE PAVED DITCH	80 SY		
0079	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	2,200 SY		
0080	3000000000-N	SP	IMPACT ATTENUATOR UNIT, TYPE 350	2 EA		
0081	3030000000-E	862	STEEL BM GUARDRAIL	5,137.5 LF		
0082	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	20 EA		
0083	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	5 EA		
0084	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	5 EA		
0085	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	8 EA		
0086	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	7,300 LF		
0087	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	400 EA		
0088	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	210 EA		

County : Richmond, Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	3533000000-E	866	CHAIN LINK FENCE, *** FABRIC (72")	650	LF	
0090	3539000000-E	866	METAL LINE POSTS FOR *** CHAIN LINK FENCE (72")	54	EA	
0091	3545000000-E	866	METAL TERMINAL POSTS FOR *** CHAIN LINK FENCE (72")	6	EA	
0092	3551000000-E	866	METAL GATE POSTS FOR *** CHAIN LINK FENCE, SINGLE GATE (72")	2	EA	
0093	3565000000-E	866	DOUBLE GATES, *** HIGH, *** WIDE, *** OPENING (72", 15', 30')	1	EA	
0094	3579000000-N	866	GENERIC FENCING ITEM TEMPORARY DOUBLE GATES, 72" HIGH, 15' WIDE, 30' OPENING	1	EA	
0095	3579000000-N	866	GENERIC FENCING ITEM TEMPORARY METAL GATE POST FOR 72" CHAIN LINK FENCE	2	EA	
0096	3579000000-N	866	GENERIC FENCING ITEM TEMPORARY METAL LINE POSTS FOR 72" CHAIN LINK FENCE	55	EA	
0097	3579000000-N	866	GENERIC FENCING ITEM TEMPORARY METAL TERMINAL POST FOR 72" CHAIN LINK FENCE	8	EA	
0098	3580000000-E	866	GENERIC FENCING ITEM TEMPORARY CHAIN LINK FENCE 72" FABRIC	660	LF	
0099	3628000000-E	876	RIP RAP, CLASS I	60	TON	
0100	3649000000-E	876	RIP RAP, CLASS B	910	TON	
0101	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	6,850	SY	
0102	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	3,595	LF	
0103	4096000000-N	904	SIGN ERECTION, TYPE D	16	EA	
0104	4102000000-N	904	SIGN ERECTION, TYPE E	176	EA	

County : Richmond, Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0105	4108000000-N	904	SIGN ERECTION, TYPE F	21 EA		
0106	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	6 EA		
0107	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	1 EA		
0108	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	146 EA		
0109	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	6 EA		
0110	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	1,876 SF		
0111	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	1,002 SF		
0112	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	982 SF		
0113	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0114	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	4 EA		
0115	4422000000-N	1120	CHANGEABLE MESSAGE SIGN (SHORT TERM)	80 DAY		
0116	4430000000-N	1130	DRUMS	1,627 EA		
0117	4445000000-E	1145	BARRICADES (TYPE III)	656 LF		
0118	4455000000-N	1150	FLAGGER	1,155 MD		
0119	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	5 EA		
0120	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	5 EA		
0121	4480000000-N	1165	TMIA	3 EA		
0122	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	100 LF		

County : Richmond, Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0123	4505000000-E	1170	RESET PORTABLE CONCRETE BARRIER (ANCHORED)	100 LF		
0124	4516000000-N	1180	SKINNY DRUM	20 EA		
0125	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	2,981 EA		
0126	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	4,320 LF		
0127	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	715,005 LF		
0128	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	46 EA		
0129	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (HIGHLY REFLECTIVE ELEMENTS)	225,656 LF		
0130	4847110000-E	1205	POLYUREA PAVEMENT MARKING LINES (8", *****) (HIGHLY REFLECTIVE ELEMENTS)	1,682 LF		
0131	4847130000-E	1205	POLYUREA PAVEMENT MARKING LINES (16", *****) (HIGHLY REFLECTIVE ELEMENTS)	130 LF		
0132	4847140000-E	1205	POLYUREA PAVEMENT MARKING LINES (24", *****) (HIGHLY REFLECTIVE ELEMENTS)	793 LF		
0133	4847200000-N	1205	POLYUREA PAVEMENT MARKING CHARACTER (*****) (HIGHLY REFLECTIVE ELEMENTS)	6 EA		
0134	4847220000-N	1205	POLYUREA PAVEMENT MARKING SYMBOL (*****) (HIGHLY REFLECTIVE ELEMENTS)	394 EA		
0135	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	150,499 LF		
0136	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	1,427 LF		
0137	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	102 EA		
0138	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,789 EA		

County : Richmond, Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0139	5325200000-E	1510	2" WATER LINE	227 LF		
0140	5325600000-E	1510	6" WATER LINE	1,277 LF		
0141	5325800000-E	1510	8" WATER LINE	130 LF		
0142	5326000000-E	1510	10" WATER LINE	35,707 LF		
0143	5326200000-E	1510	12" WATER LINE	87 LF		
0144	5536000000-E	1515	2" VALVE	2 EA		
0145	5540000000-E	1515	6" VALVE	15 EA		
0146	5546000000-E	1515	8" VALVE	1 EA		
0147	5552000000-E	1515	10" VALVE	37 EA		
0148	5558000000-E	1515	12" VALVE	1 EA		
0149	5648000000-N	1515	RELOCATE WATER METER	44 EA		
0150	5649000000-N	1515	RECONNECT WATER METER	11 EA		
0151	5666000000-E	1515	FIRE HYDRANT	7 EA		
0152	5672000000-N	1515	RELOCATE FIRE HYDRANT	20 EA		
0153	5804000000-E	1530	ABANDON 12" UTILITY PIPE	250 LF		
0154	5912000000-N	SP	GENERIC UTILITY ITEM UTILITY COORDINATOR	Lump Sum	L.S.	
0155	6000000000-E	1605	TEMPORARY SILT FENCE	15,000 LF		
0156	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	4,325 TON		
0157	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	7,000 TON		
0158	6012000000-E	1610	SEDIMENT CONTROL STONE	5,550 TON		

County : Richmond, Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0159	6015000000-E	1615	TEMPORARY MULCHING	125.5	ACR	
0160	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	4,850	LB	
0161	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	20	TON	
0162	6024000000-E	1622	TEMPORARY SLOPE DRAINS	700	LF	
0163	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	19	EA	
0164	6029000000-E	SP	SAFETY FENCE	7,350	LF	
0165	6030000000-E	1630	SILT EXCAVATION	101,675	CY	
0166	6036000000-E	1631	MATTING FOR EROSION CONTROL	105,800	SY	
0167	6037000000-E	SP	COIR FIBER MAT	250	SY	
0168	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,250	SY	
0169	6042000000-E	1632	1/4" HARDWARE CLOTH	1,370	LF	
0170	6069000000-E	1638	STILLING BASINS	3,750	CY	
0171	6070000000-N	SP	SPECIAL STILLING BASINS	24	EA	
0172	6071030000-E	SP	COIR FIBER BAFFLES	12,450	LF	
0173	6071050000-E	SP	*** SKIMMER (1-1/2")	5	EA	
0174	6071050000-E	SP	*** SKIMMER (2")	9	EA	
0175	6071050000-E	SP	*** SKIMMER (2-1/2")	12	EA	
0176	6071050000-E	SP	*** SKIMMER (3")	3	EA	
0177	6071050000-E	SP	*** SKIMMER (4")	5	EA	

County : Richmond, Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0178	6071050000-E	SP	*** SKIMMER (5")	4 EA		
0179	6084000000-E	1660	SEEDING & MULCHING	136 ACR		
0180	6087000000-E	1660	MOWING	78 ACR		
0181	6090000000-E	1661	SEED FOR REPAIR SEEDING	1,100 LB		
0182	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	2.75 TON		
0183	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	3,125 LB		
0184	6108000000-E	1665	FERTILIZER TOPDRESSING	94.5 TON		
0185	6114000000-N	SP	SPECIALIZED HAND MOWING	4 HR		
0186	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	72 EA		
0187	6123000000-E	1670	REFORESTATION	1 ACR		
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0188	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	10,500 LF		
AA1						
0189	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	4,400 LF		
AA1						
0190	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	3,900 LF		
AA1						
0191	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	1,720 LF		
AA1						
0192	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	940 LF		
AA1						
0193	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	320 LF		
AA1						
*** OR ***						
0194	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	4,900 LF		
AA2						

County : Richmond, Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0195 AA2	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	3,260	LF	
0196 AA2	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	3,060	LF	
0197 AA2	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	740	LF	
0198 AA2	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	180	LF	
0199 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	5,600	LF	
0200 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	1,140	LF	
0201 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	840	LF	
0202 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (30")	980	LF	
0203 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (36")	760	LF	
0204 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (42")	320	LF	
*** OR ***						
0205 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	4,900	LF	
0206 AA3	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	3,260	LF	
0207 AA3	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	3,060	LF	
0208 AA3	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	740	LF	
0209 AA3	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	180	LF	
0210 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	5,600	LF	

County : Richmond, Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0211 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (18", 0.064")	1,140 LF		
0212 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (24", 0.064")	840 LF		
0213 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (30", 0.079")	980 LF		
0214 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (36", 0.079")	760 LF		
0215 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (42", 0.109")	320 LF		
***** END SCHEDULE AA *****						
0242	4485000000-E	1170	PORTABLE CONCRETE BARRIER	12,610 LF		
0243	4500000000-E	1170	RESET PORTABLE CONCRETE BAR- RIER	710 LF		
STRUCTURE ITEMS						
0216	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (434+27.00 -L-NBL)	Lump Sum	L.S.	
0217	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (434+27.00 -L-SBL)	Lump Sum	L.S.	
0218	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (437+27.00 -L-NBL)	Lump Sum	L.S.	

County : Richmond, Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0219	8105500000-E	SP	***-*** DIA DRILLED PIERS IN SOIL (4'-6")	290.4 LF		
0220	8105600000-E	SP	***-*** DIA DRILLED PIERS NOT IN SOIL (4'-6")	63.6 LF		
0221	8111000000-E	SP	PERMANENT STEEL CASING FOR ***-*** DIA DRILLED PIER (4'-6")	300 LF		
0222	8113000000-N	SP	SID INSPECTION	6 EA		
0223	8114000000-N	SP	SPT TESTING	6 EA		
0224	8115000000-N	SP	CROSSHOLE SONIC LOGGING	6 EA		
0225	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVATION	1,460 CY		
0226	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	34,540 SF		
0227	8161000000-E	420	GROOVING BRIDGE FLOORS	31,868 SF		
0228	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	310.2 CY		
0229	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (434+27.00 -L-NBL)	Lump Sum	L.S.	
0230	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (434+27.00 -L-SBL)	Lump Sum	L.S.	
0231	8217000000-E	425	REINFORCING STEEL (BRIDGE)	80,960 LB		
0232	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	10,907 LB		
0233	8274000000-E	430	MODIFIED 63" PRESTRESSED CONC GIRDERS	4,353.34 LF		
0234	8384000000-E	450	HP14X73 STEEL PILES	1,100 LF		
0235	8503000000-E	460	CONCRETE BARRIER RAIL	1,753.34 LF		

County : Richmond, Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0236	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	708 TON		
0237	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	788 SY		
0238	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0239	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0240	8741000000-N	SP	STRUCTURE DRAINAGE SYSTEM AT STA***** (434+27.00 -L-NBL)	Lump Sum	L.S.	
0241	8741000000-N	SP	STRUCTURE DRAINAGE SYSTEM AT STA***** (434+27.00 -L-SBL)	Lump Sum	L.S.	
1312/Oct16/Q2424206.43/D870421130000/E243			Total Amount Of Bid For Entire Project :			

Contract No **C201371**

County (ies): **Richmond/Moore**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General