

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	300 CY		
0005	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	350 TON		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	280 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	10 TON		
001C	0995000000-E	340	PIPE REMOVAL	26 LF		
0011	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0012	1330000000-E	607	INCIDENTAL MILLING	230 SY		
0013	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	240 TON		
0014	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	150 TON		
0015	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	250 TON		
0016	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	33 TON		
0017	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50 TON		
0018	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0020	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	1 EA		
0021	3030000000-E	862	STEEL BM GUARDRAIL	675 LF		
0022	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0023	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0024	3628000000-E	876	RIP RAP, CLASS I	95 TON		
0025	3649000000-E	876	RIP RAP, CLASS B	135 TON		
0026	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,930 SY		
0027	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	347 SF		
0028	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	107 SF		
0029	4430000000-N	1130	DRUMS	14 EA		
0030	4435000000-N	1135	CONES	14 EA		
0031	4445000000-E	1145	BARRICADES (TYPE III)	136 LF		
0032	5326200000-E	1510	12" WATER LINE	311 LF		
0033	5558000000-E	1515	12" VALVE	2 EA		
0034	5648000000-N	1515	RELOCATE WATER METER	1 EA		
0035	5804000000-E	1530	ABANDON 12" UTILITY PIPE	245 LF		
0036	5871700000-E	1550	TRENCHLESS INSTALLATION OF 12" IN SOIL	95 LF		
0037	5871710000-E	1550	TRENCHLESS INSTALLATION OF 12" NOT IN SOIL	95 LF		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	6000000000-E	1605	TEMPORARY SILT FENCE	1,755	LF	
003E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225	TON	
004C	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	70	TON	
0041	6012000000-E	1610	SEDIMENT CONTROL STONE	20	TON	
0042	6015000000-E	1615	TEMPORARY MULCHING	2	ACR	
004E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0044	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25	TON	
004E	6029000000-E	SP	SAFETY FENCE	400	LF	
004E	6030000000-E	1630	SILT EXCAVATION	490	CY	
0047	6036000000-E	1631	MATTING FOR EROSION CONTROL	6,390	SY	
004E	6037000000-E	SP	COIR FIBER MAT	25	SY	
004E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	75	SY	
005C	6042000000-E	1632	1/4" HARDWARE CLOTH	20	LF	
0051	6069000000-E	1638	STILLING BASINS	300	CY	
0052	6071030000-E	SP	COIR FIBER BAFFLES	195	LF	
0053	6071050000-E	SP	*** SKIMMER (1-1/2")	4	EA	
0054	6084000000-E	1660	SEEDING & MULCHING	4.5	ACR	
005E	6087000000-E	1660	MOWING	1	ACR	
005E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
005E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
005E	6108000000-E	1665	FERTILIZER TOPDRESSING	1	TON	
006C	6111000000-E	SP	IMPERVIOUS DIKE	280	LF	
0061	6114000000-N	SP	SPECIALIZED HAND MOWING	5	HR	
0062	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	

***** BEGIN SCHEDULE AA *****
***** (3 ALTERNATES) *****

0063 AA1	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	52	LF	
-------------	--------------	-----	---------------------------------	----	----	--

*** OR ***

0064 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	52	LF	
-------------	--------------	----	-------------------------------	----	----	--

*** OR ***

0065 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (18", 0.064")	52	LF	
-------------	--------------	----	--	----	----	--

***** END SCHEDULE AA *****

CULVERT ITEMS

006E	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+48.00-L-)	Lump Sum	L.S.	
0067	8126000000-N	414	CULVERT EXCAVATION, STA ***** (15+48.00-L-)	Lump Sum	L.S.	
006E	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	146	TON	
006E	8196000000-E	420	CLASS A CONCRETE (CULVERT)	203.9	CY	

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007C	8245000000-E	425	REINFORCING STEEL (CULVERT)	36,132		
				LB		

1105/Sep04/Q53701.9/D290064790000/E70

Total Amount Of Bid For Entire Project :

Contract No **C201964**

County (ies): **Stanly**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General