

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (13+83.00)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	12 TON		
0009	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	24 LF		
0010	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	24 LF		
0011	0995000000-E	340	PIPE REMOVAL	20 LF		
0012	1121000000-E	520	AGGREGATE BASE COURSE	35 TON		
0013	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	180 TON		
0015	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	350 TON		
0016	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	31 TON		
0017	2000000000-N	806	RIGHT OF WAY MARKERS	4 EA		
0018	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	7 LF		
002C	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0021	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0022	2556000000-E	846	SHOULDER BERM GUTTER	65 LF		
0023	3030000000-E	862	STEEL BM GUARDRAIL	325 LF		
0024	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
002E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
002E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0027	3649000000-E	876	RIP RAP, CLASS B	5 TON		
002E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,110 SY		
002E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	312 SF		
003C	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0031	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
0032	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	4,680 LF		
003E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	67 EA		
0034	6000000000-E	1605	TEMPORARY SILT FENCE	2,900 LF		
003E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225 TON		
003E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	215 TON		

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	6012000000-E	1610	SEDIMENT CONTROL STONE	75 TON		
003E	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
003E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
004C	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0041	6029000000-E	SP	SAFETY FENCE	500 LF		
0042	6030000000-E	1630	SILT EXCAVATION	350 CY		
0043	6036000000-E	1631	MATTING FOR EROSION CONTROL	5,100 SY		
0044	6042000000-E	1632	1/4" HARDWARE CLOTH	50 LF		
004E	6071030000-E	SP	COIR FIBER BAFFLES	100 LF		
004E	6084000000-E	1660	SEEDING & MULCHING	3.5 ACR		
0047	6087000000-E	1660	MOWING	1 ACR		
004E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
004E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
005C	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0051	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
0052	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0053	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		

***** BEGIN SCHEDULE AA *****
 ***** (3 ALTERNATES) *****

0054	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	48 LF		
------	--------------	-----	------------------------------------	----------	--	--

*** OR ***

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E AA2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (24", 0.064")	48 LF		
*** OR ***						
005E AA3	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	48 LF		
***** END SCHEDULE AA *****						
STRUCTURE ITEMS						
0057	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (13+83.00-L-)	Lump Sum	L.S.	
005E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (13+83.00-L-)	Lump Sum	L.S.	
005E	8096000000-E	SP	PILE EXCAVATION IN SOIL	48 LF		
006C	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	32 LF		
0061	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (13+83.00-L-)	Lump Sum	L.S.	
0062	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	33.5 CY		
0063	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (13+83.00-L-)	Lump Sum	L.S.	
0064	8217000000-E	425	REINFORCING STEEL (BRIDGE)	4,931 LB		
006E	8364000000-E	450	HP12X53 STEEL PILES	160 LF		
006E	8391000000-N	450	STEEL PILE POINTS	8 EA		
0067	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	174.8 LF		
006E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	350 TON		

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0069	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	380 SY		
007C	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0071	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	786.61 LF		
1032/Oct03/Q24875.66/D314128230000/E71			Total Amount Of Bid For Entire Project :			

Contract No C201975

County (ies): Granville

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General