

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	600 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	55 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	8 TON		
0011	0344000000-E	310	18" SIDE DRAIN PIPE	72 LF		
0012	0995000000-E	340	PIPE REMOVAL	80 LF		
0013	1121000000-E	520	AGGREGATE BASE COURSE	170 TON		
0014	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	150 TON		
0016	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	115 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	14 TON		
0018	2000000000-N	806	RIGHT OF WAY MARKERS	15 EA		
0019	2022000000-E	815	SUBDRAIN EXCAVATION	67.2 CY		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	2033000000-E	815	SUBDRAIN FINE AGGREGATE	50.4 CY		
0021	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	300 LF		
0022	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	9 EA		
0023	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0024	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0025	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0026	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (350, TL-2)	4 EA		
0027	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (W-BEAM BRIDGE RAIL TRANSITION)	4 EA		
0028	3420000000-E	SP	GENERIC GUARDRAIL ITEM W-BEAM BRIDGE RAIL	200 LF		
0029	3628000000-E	876	RIP RAP, CLASS I	40 TON		
0030	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	300 SY		
0031	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	186 SF		
0032	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	128 SF		
0033	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	36 SF		
0034	4435000000-N	1135	CONES	30 EA		
0035	4445000000-E	1145	BARRICADES (TYPE III)	30 LF		
0036	4450000000-N	1150	FLAGGER	640 HR		
0037	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1 EA		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	4480000000-N	1165	TMIA	1	EA	
003E	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	225	LF	
004C	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	1,908	LF	
0041	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	570	LF	
0042	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	2,930	LF	
0043	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	240	LF	
0044	6000000000-E	1605	TEMPORARY SILT FENCE	1,000	LF	
004E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	115	TON	
004E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	120	TON	
0047	6012000000-E	1610	SEDIMENT CONTROL STONE	30	TON	
004E	6015000000-E	1615	TEMPORARY MULCHING	2	ACR	
004E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
005C	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25	TON	
0051	6029000000-E	SP	SAFETY FENCE	470	LF	
0052	6030000000-E	1630	SILT EXCAVATION	380	CY	
0053	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,200	SY	
0054	6037000000-E	SP	COIR FIBER MAT	30	SY	

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	190	SY	
005E	6071030000-E	SP	COIR FIBER BAFFLES	200	LF	
0057	6071050000-E	SP	*** SKIMMER (1-1/2")	5	EA	
005E	6084000000-E	1660	SEEDING & MULCHING	2.5	ACR	
005E	6087000000-E	1660	MOWING	1	ACR	
006C	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0061	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0062	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
006E	6108000000-E	1665	FERTILIZER TOPDRESSING	1	TON	
0064	6114000000-N	SP	SPECIALIZED HAND MOWING	5	HR	
006E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	
006E	6123000000-E	1670	REFORESTATION	0.25	ACR	

STRUCTURE ITEMS

0067	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16 + 48.00-L-)	Lump Sum	L.S.	
006E	8096000000-E	SP	PILE EXCAVATION IN SOIL	75	LF	
006E	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	275	LF	
007C	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (16 + 48.00-L-)	Lump Sum	L.S.	
0071	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	31.3	CY	

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	8217000000-E	425	REINFORCING STEEL (BRIDGE)	4,538 LB		
0073	8364000000-E	450	HP12X53 STEEL PILES	350 LF		
0074	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	550 TON		
007E	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	610 SY		
007E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0077	8753200000-E	430	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	684.25 LF		
007E	8867000000-E	SP	GENERIC STRUCTURE ITEM TYPE T101 RAIL	189.17 LF		

1032/Oct03/Q22015.57/D342927780000/E78

Total Amount Of Bid For Entire Project :

Contract No **C201972**

County (ies): **Watauga**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General