

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17 + 30.00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	600 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	83 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	20 TON		
0012	0343000000-E	310	15" SIDE DRAIN PIPE	44 LF		
0013	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	116 LF		
0014	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	16 LF		
0015	0995000000-E	340	PIPE REMOVAL	55 LF		
0016	1121000000-E	520	AGGREGATE BASE COURSE	260 TON		
0017	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0018	1275000000-E	600	PRIME COAT	270 GAL		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	140 TON		
002C	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	350 TON		
0021	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	29 TON		
0022	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	8 TON		
0023	2022000000-E	815	SUBDRAIN EXCAVATION	67 CY		
0024	2033000000-E	815	SUBDRAIN FINE AGGREGATE	50 CY		
002E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	300 LF		
002E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	9 EA		
0027	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
002E	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
003C	2355000000-N	840	FRAME WITH GRATE, STD 840.29	3 EA		
0031	3030000000-E	862	STEEL BM GUARDRAIL	275 LF		
0032	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
003E	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	1 EA		
0034	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
003E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
003E	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	150 LF		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (B-77)	4	EA	
003E	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	4	EA	
003E	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	440	LF	
004C	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	20	EA	
0041	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	30	EA	
0042	3564000000-E	866	SINGLE GATES, *** HIGH, *** WIDE, *** OPENING (47" HIGH, 19' WIDE, 19' OPEN- ING)	1	EA	
0043	3574000000-E	867	GENERIC FENCING ITEM WOVEN WIRE FENCE RESET (INCLUDE GATE RESET)	355	LF	
0044	3649000000-E	876	RIP RAP, CLASS B	11	TON	
0045	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	540	SY	
0046	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	196	SF	
0047	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96	SF	
004E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	32	SF	
004E	4430000000-N	1130	DRUMS	23	EA	
005C	4435000000-N	1135	CONES	23	EA	
0051	4445000000-E	1145	BARRICADES (TYPE III)	32	LF	
0052	4450000000-N	1150	FLAGGER	960	HR	
0053	4480000000-N	1165	TMIA	1	EA	

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	15,134	LF	
005E	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	18	LF	
005E	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	646	LF	
0057	6000000000-E	1605	TEMPORARY SILT FENCE	650	LF	
005E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	90	TON	
005E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	140	TON	
006C	6012000000-E	1610	SEDIMENT CONTROL STONE	235	TON	
0061	6015000000-E	1615	TEMPORARY MULCHING	1.5	ACR	
0062	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
006E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25	TON	
0064	6029000000-E	SP	SAFETY FENCE	350	LF	
006E	6030000000-E	1630	SILT EXCAVATION	430	CY	
006E	6036000000-E	1631	MATTING FOR EROSION CONTROL	550	SY	
0067	6037000000-E	SP	COIR FIBER MAT	25	SY	
006E	6042000000-E	1632	1/4" HARDWARE CLOTH	60	LF	
006E	6070000000-N	SP	SPECIAL STILLING BASINS	8	EA	
007C	6071030000-E	SP	COIR FIBER BAFFLES	95	LF	
0071	6071050000-E	SP	*** SKIMMER (1-1/2")	4	EA	

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	6084000000-E	1660	SEEDING & MULCHING	2	ACR	
0073	6087000000-E	1660	MOWING	1	ACR	
0074	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
007E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0076	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0077	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25	TON	
007E	6114000000-N	SP	SPECIALIZED HAND MOWING	2	HR	
007E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	
008C	6123000000-E	1670	REFORESTATION	0.3	ACR	
0081	7060000000-E	1705	SIGNAL CABLE	1,260	LF	
0082	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	8	EA	
0083	7264000000-E	1710	MESSENGER CABLE (3/8")	610	LF	
0084	7360000000-N	1720	WOOD POLE	6	EA	
008E	7372000000-N	1721	GUY ASSEMBLY	6	EA	
008E	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1	EA	
0087	7420000000-E	1722	2" RISER WITH WEATHERHEAD	3	EA	
008E	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	375	LF	
008E	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	1,610	LF	
009C	7636000000-N	1745	SIGN FOR SIGNALS	6	EA	
0091	7768000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)	1	EA	

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	2 EA		
STRUCTURE ITEMS						
0093	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (17+30.00-L-)	Lump Sum	L.S.	
0094	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+30.00-L-)	Lump Sum	L.S.	
0095	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (17+30.00-L-)	Lump Sum	L.S.	
0096	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	66.6 CY		
0097	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+30.00-L-)	Lump Sum	L.S.	
0098	8217000000-E	425	REINFORCING STEEL (BRIDGE)	12,402 LB		
0099	8475000000-E	460	TWO BAR METAL RAIL	206.31 LF		
0100	8517000000-E	460	1'***X ***** CONCRETE PARA- PET (1'-2" X 2'-10")	223.64 LF		
0101	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	300 TON		
0102	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	335 SY		
0103	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0104	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,226.18 LF		
0105	8860000000-N	SP	GENERIC STRUCTURE ITEM LATERAL LOAD TESTING ASSIST- ANCE	Lump Sum	L.S.	

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0106	8860000000-N	SP	GENERIC STRUCTURE ITEM TEMPORARY CAP	Lump Sum	L.S.	
0107	8897000000-N	SP	GENERIC STRUCTURE ITEM 10 3/4" DIA MICROPILES	20 EA		
0108	8897000000-N	SP	GENERIC STRUCTURE ITEM 10-3/4" DIA NON-PRODUCTION MICROPILES	16 EA		
0109	8897000000-N	SP	GENERIC STRUCTURE ITEM MICROPILE PROOF TESTS	2 EA		
1111/Nov10/Q44489.28/D510577680000/E109			Total Amount Of Bid For Entire Project :			

Contract No C201767

County (ies): Ashe

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General