

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (14 + 22.50 -L-)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	50 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	10 TON		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	10 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	10 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	33 TON		
0010	0343000000-E	310	15" SIDE DRAIN PIPE	52 LF		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	60 LF		
0012	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	52 LF		
0013	1121000000-E	520	AGGREGATE BASE COURSE	110 TON		
0014	1220000000-E	545	INCIDENTAL STONE BASE	30 TON		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	190 TON		
0016	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	260 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	30 TON		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	20 TON		
001E	2000000000-N	806	RIGHT OF WAY MARKERS	15 EA		
002C	2022000000-E	815	SUBDRAIN EXCAVATION	6 CY		
0021	2033000000-E	815	SUBDRAIN FINE AGGREGATE	5 CY		
0022	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	25 LF		
0023	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	1 EA		
0024	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
002E	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0027	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
002E	2556000000-E	846	SHOULDER BERM GUTTER	160 LF		
002E	3030000000-E	862	STEEL BM GUARDRAIL	125 LF		
003C	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	37.5 LF		
0031	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0032	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
0033	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0034	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
003E	3649000000-E	876	RIP RAP, CLASS B	70 TON		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	370	SY	
0037	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1	EA	
003E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	44	LF	
003E	4102000000-N	904	SIGN ERECTION, TYPE E	3	EA	
004C	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	9	EA	
0041	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	471	SF	
0042	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	177	SF	
0043	4430000000-N	1130	DRUMS	15	EA	
0044	4445000000-E	1145	BARRICADES (TYPE III)	156	LF	
004E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	3,376	LF	
004E	5326200000-E	1510	12" WATER LINE	255	LF	
0047	5558000000-E	1515	12" VALVE	2	EA	
004E	5648000000-N	1515	RELOCATE WATER METER	3	EA	
004E	5672000000-N	1515	RELOCATE FIRE HYDRANT	1	EA	
005C	5800000000-E	1530	ABANDON 6" UTILITY PIPE	165	LF	
0051	5804000000-E	1530	ABANDON 12" UTILITY PIPE	72	LF	
0052	6000000000-E	1605	TEMPORARY SILT FENCE	440	LF	
0053	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75	TON	
0054	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	175	TON	

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6012000000-E	1610	SEDIMENT CONTROL STONE	65 TON		
005E	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0057	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
005E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25 TON		
005E	6029000000-E	SP	SAFETY FENCE	250 LF		
006C	6030000000-E	1630	SILT EXCAVATION	430 CY		
0061	6036000000-E	1631	MATTING FOR EROSION CONTROL	420 SY		
0062	6037000000-E	SP	COIR FIBER MAT	10 SY		
006E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	50 SY		
0064	6042000000-E	1632	1/4" HARDWARE CLOTH	60 LF		
006E	6071030000-E	SP	COIR FIBER BAFFLES	110 LF		
006E	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
0067	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
006E	6087000000-E	1660	MOWING	0.5 ACR		
006E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
007C	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0071	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0072	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
007E	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		

STRUCTURE ITEMS

0075	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14 + 22.50-L-)	Lump Sum	L.S.	
0076	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (14 + 22.50-L-)	Lump Sum	L.S.	
0077	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	47.5 CY		
0078	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14 + 22.50-L-)	Lump Sum	L.S.	
0079	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,953 LB		
0080	8384000000-E	450	HP14X73 STEEL PILES	240 LF		
0081	8503000000-E	460	CONCRETE BARRIER RAIL	204.83 LF		
0082	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	330 TON		
0083	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	367 SY		
0084	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0085	8753200000-E	430	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	1,126.58 LF		

Contract No **C201850**

County (ies): **Buncombe**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General