

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	600 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	40 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0010	0255000000-E	SP	GENERIC GRADING ITEM #57 LIMESTONE	4.5 TON		
0011	0255000000-E	SP	GENERIC GRADING ITEM AGRICULTURAL GRADE GROUND LIMESTONE	2 TON		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	30 TON		
0013	0344000000-E	310	18" SIDE DRAIN PIPE	44 LF		
0014	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	184 LF		
0015	0995000000-E	340	PIPE REMOVAL	34 LF		
0016	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
0017	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/4")	270 SY		
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	450 TON		

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	240 TON		
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	35 TON		
0021	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50 TON		
0022	2022000000-E	815	SUBDRAIN EXCAVATION	120 CY		
0023	2033000000-E	815	SUBDRAIN FINE AGGREGATE	90 CY		
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0025	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
0026	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0027	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0028	2190000000-N	828	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE	1 EA		
0029	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0030	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	1 LF		
0031	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0032	2556000000-E	846	SHOULDER BERM GUTTER	120 LF		
0033	2570000000-N	SP	MODIFIED CONCRETE FLUME	1 EA		
0034	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	70 LF		
0035	3030000000-E	862	STEEL BM GUARDRAIL	125 LF		
0036	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	75 LF		
0037	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	15 EA		

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (TL-2)	1 EA		
0039	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0040	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0041	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	25 LF		
0042	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)	2 EA		
0043	3389000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (TL-2)	2 EA		
0044	3566000000-E	867	WOVEN WIRE FENCE RESET	200 LF		
0045	3635000000-E	876	RIP RAP, CLASS II	6 TON		
0046	3649000000-E	876	RIP RAP, CLASS B	8 TON		
0047	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	295 SY		
0048	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	177 SF		
0049	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0050	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	72 SF		
0051	4430000000-N	1130	DRUMS	60 EA		
0052	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0053	4450000000-N	1150	FLAGGER	2,500 HR		
0054	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0055	4480000000-N	1165	TMIA	2 EA		

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4485000000-E	1170	PORTABLE CONCRETE BARRIER	80 LF		
0057	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	45 LF		
0058	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	40 EA		
0059	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	6,670 LF		
0060	6000000000-E	1605	TEMPORARY SILT FENCE	300 LF		
0061	6060000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	115 TON		
0062	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	125 TON		
0063	6012000000-E	1610	SEDIMENT CONTROL STONE	50 TON		
0064	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
0065	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0066	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25 TON		
0067	6029000000-E	SP	SAFETY FENCE	250 LF		
0068	6030000000-E	1630	SILT EXCAVATION	385 CY		
0069	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,200 SY		
0070	6037000000-E	SP	COIR FIBER MAT	10 SY		
0071	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	160 SY		
0072	6042000000-E	1632	1/4" HARDWARE CLOTH	60 LF		
0073	6071010000-E	SP	WATTLE	25 LF		
0074	6071020000-E	SP	POLYACRYLAMIDE (PAM)	9 LB		

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	6071030000-E	SP	COIR FIBER BAFFLES	155 LF		
0076	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
0077	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0078	6087000000-E	1660	MOWING	1 ACR		
0079	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0080	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0081	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0082	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
0083	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0084	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
STRUCTURE ITEMS						
0085	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+32.50-L-)	Lump Sum	L.S.	
0086	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	26.1 CY		
0087	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+32.50-L-)	Lump Sum	L.S.	
0088	8217000000-E	425	REINFORCING STEEL (BRIDGE)	4,159 LB		
0089	8364000000-E	450	HP12X53 STEEL PILES	70 LF		
0090	8391000000-N	450	STEEL PILE POINTS	14 EA		
0091	8475000000-E	460	TWO BAR METAL RAIL	69.35 LF		

County : Cherokee

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	8517000000-E	460	1'-**X ***** CONCRETE PARA- PET (1'-2" X 2'-8")	85.2 LF		
0093	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0094	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	468.65 LF		
1502/Nov03/Q23468.05/D373871610000/E94			Total Amount Of Bid For Entire Project :			

Contract No **C202038**

County (ies): **B-3635**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General