

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0022000000-E	225	UNCLASSIFIED EXCAVATION	4,600 CY		
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	600 CY		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	600 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	20 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	45 TON		
0011	0344000000-E	310	18" SIDE DRAIN PIPE	40 LF		
0012	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	96 LF		
0013	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	268 LF		
0014	0995000000-E	340	PIPE REMOVAL	114 LF		
0015	1220000000-E	545	INCIDENTAL STONE BASE	250 TON		
0016	1330000000-E	607	INCIDENTAL MILLING	70 SY		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	461 TON		
0018	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	292 TON		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	39 TON		
0020	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	30 TON		
0021	2022000000-E	815	SUBDRAIN EXCAVATION	115 CY		
0022	2033000000-E	815	SUBDRAIN FINE AGGREGATE	85 CY		
0023	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0024	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
0025	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0026	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0028	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0029	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0030	2556000000-E	846	SHOULDER BERM GUTTER	100 LF		
0031	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	195 LF		
0032	2724000000-E	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	50 LF		
0033	3030000000-E	862	STEEL BM GUARDRAIL	137.5 LF		
0034	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	62.5 LF		
0035	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0036	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	6 EA		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	2	EA	
003E	3628000000-E	876	RIP RAP, CLASS I	90	TON	
003E	3649000000-E	876	RIP RAP, CLASS B	25	TON	
004C	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	725	SY	
0041	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	460	SF	
0042	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	114	SF	
0043	4430000000-N	1130	DRUMS	40	EA	
0044	4445000000-E	1145	BARRICADES (TYPE III)	50	LF	
0045	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	5,800	LF	
0046	6000000000-E	1605	TEMPORARY SILT FENCE	1,900	LF	
0047	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	160	TON	
004E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	125	TON	
0049	6012000000-E	1610	SEDIMENT CONTROL STONE	165	TON	
005C	6015000000-E	1615	TEMPORARY MULCHING	3	ACR	
0051	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0052	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.5	TON	
0053	6024000000-E	1622	TEMPORARY SLOPE DRAINS	40	LF	
0054	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1	EA	

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6029000000-E	SP	SAFETY FENCE	750	LF	
005E	6030000000-E	1630	SILT EXCAVATION	410	CY	
0057	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,750	SY	
005E	6037000000-E	SP	COIR FIBER MAT	15	SY	
005E	6042000000-E	1632	1/4" HARDWARE CLOTH	60	LF	
006C	6070000000-N	SP	SPECIAL STILLING BASINS	4	EA	
0061	6071010000-E	SP	WATTLE	25	LF	
0062	6071020000-E	SP	POLYACRYLAMIDE (PAM)	9	LB	
0063	6071030000-E	SP	COIR FIBER BAFFLES	120	LF	
0064	6071050000-E	SP	*** SKIMMER (1-1/2")	2	EA	
006E	6084000000-E	1660	SEEDING & MULCHING	4	ACR	
006E	6087000000-E	1660	MOWING	1.5	ACR	
0067	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
006E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
006E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75	LB	
007C	6108000000-E	1665	FERTILIZER TOPDRESSING	1.75	TON	
0071	6111000000-E	SP	IMPERVIOUS DIKE	530	LF	
0072	6114000000-N	SP	SPECIALIZED HAND MOWING	5	HR	
0073	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	
0074	6123000000-E	1670	REFORESTATION	0.1	ACR	

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
CULVERT ITEMS						
007E	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+77.28-L-)	Lump Sum	L.S.	
007E	8196000000-E	420	CLASS A CONCRETE (CULVERT)	161.1 CY		
0077	8804000000-N	SP	GENERIC CULVERT ITEM PRECAST REINFORCED CONCRETE 3-SIDED CULVERT AT STA 16+77. 28 -L-	Lump Sum	L.S.	

WALL ITEMS

007E	8802014000-E	SP	SOLDIER PILE RETAINING WALLS	610 SF		
------	--------------	----	------------------------------	-----------	--	--

0959/Nov07/Q24213.2/D297940224000/E78

Total Amount Of Bid For Entire Project :

Contract No **C202035**

County (ies): **Macon**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General