

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (14+68.00 -L-)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	20 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	100 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	30 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	30 TON		
0011	0343000000-E	310	15" SIDE DRAIN PIPE	44 LF		
0012	0345000000-E	310	24" SIDE DRAIN PIPE	24 LF		
0013	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	124 LF		
0014	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	68 LF		
0015	0995000000-E	340	PIPE REMOVAL	178 LF		
0016	1121000000-E	520	AGGREGATE BASE COURSE	1,662 TON		
0017	1220000000-E	545	INCIDENTAL STONE BASE	20 TON		
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	700 TON		

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	480 TON		
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	65 TON		
0021	1748000000-E	660	ASPHALT SURFACE TREATMENT, MAT & SEAL	2,100 SY		
0022	2000000000-N	806	RIGHT OF WAY MARKERS	31 EA		
0023	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		
0024	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		
0025	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0026	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0027	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0028	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0029	3030000000-E	862	STEEL BM GUARDRAIL	300 LF		
0030	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	137.5 LF		
0031	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	8 EA		
0032	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0033	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (III, SHOP CURVE)	2 EA		
0034	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	3 EA		
0035	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	2 EA		
0036	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	1 EA		

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3628000000-E	876	RIP RAP, CLASS I	80 TON		
0038	3635000000-E	876	RIP RAP, CLASS II	400 TON		
0039	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	2,170 SY		
0040	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	140 LF		
0041	4102000000-N	904	SIGN ERECTION, TYPE E	11 EA		
0042	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	1 EA		
0043	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	11 EA		
0044	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	1 EA		
0045	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	202 SF		
0046	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	384 SF		
0047	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	122 SF		
0048	4430000000-N	1130	DRUMS	61 EA		
0049	4435000000-N	1135	CONES	30 EA		
0050	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
0051	4450000000-N	1150	FLAGGER	600 HR		
0052	4516000000-N	1180	SKINNY DRUM	30 EA		
0053	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	18,894 LF		
0054	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	508 LF		
0055	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	197 LF		

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	21 LF		
0057	4915000000-E	1264	7' U-CHANNEL POSTS	6 EA		
0058	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	6 EA		
0059	6000000000-E	1605	TEMPORARY SILT FENCE	2,300 LF		
0060	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	400 TON		
0061	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	260 TON		
0062	6012000000-E	1610	SEDIMENT CONTROL STONE	360 TON		
0063	6015000000-E	1615	TEMPORARY MULCHING	4.5 ACR		
0064	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0065	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.5 TON		
0066	6029000000-E	SP	SAFETY FENCE	650 LF		
0067	6030000000-E	1630	SILT EXCAVATION	1,000 CY		
0068	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,250 SY		
0069	6037000000-E	SP	COIR FIBER MAT	20 SY		
0070	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	300 SY		
0071	6070000000-N	SP	SPECIAL STILLING BASINS	12 EA		
0072	6071030000-E	SP	COIR FIBER BAFFLES	450 LF		
0073	6071050000-E	SP	*** SKIMMER (1-1/2")	2 EA		
0074	6084000000-E	1660	SEEDING & MULCHING	8 ACR		

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	6087000000-E	1660	MOWING	2 ACR		
0076	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0077	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0078	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0079	6108000000-E	1665	FERTILIZER TOPDRESSING	2.25 TON		
0080	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0081	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0082	6123000000-E	1670	REFORESTATION	0.1 ACR		
STRUCTURE ITEMS						
0083	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (14+68.00-L-)	Lump Sum	L.S.	
0084	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+68.00-L-)	Lump Sum	L.S.	
0085	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	34.17 LF		
0086	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	42 LF		
0087	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	34.05 LF		
0088	8113000000-N	SP	SID INSPECTION	2 EA		
0089	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0090	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	71.6 CY		

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14+68.00-L-)	Lump Sum	L.S.	
0092	8217000000-E	425	REINFORCING STEEL (BRIDGE)	18,902 LB		
0093	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,705 LB		
0094	8364000000-E	450	HP12X53 STEEL PILES	350 LF		
0095	8468000000-E	460	ONE BAR METAL RAIL	302.35 LF		
0096	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-0" x 2'-0 1/2")	317.65 LF		
0097	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	815 TON		
0098	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	904 SY		
0099	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0100	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,585.52 LF		
0847/Nov10/Q63812.44/D442791860000/E100			Total Amount Of Bid For Entire Project :			

Contract No **C202034**

County (ies): **Madison**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General