

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (16 + 22.00)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	625 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	600 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	105 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	10 TON		
0011	0343000000-E	310	15" SIDE DRAIN PIPE	56 LF		
0012	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	24 LF		
0013	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0014	1220000000-E	545	INCIDENTAL STONE BASE	25 TON		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	250 TON		
0016	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	170 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	25 TON		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2000000000-N	806	RIGHT OF WAY MARKERS	11 EA		
001S	2022000000-E	815	SUBDRAIN EXCAVATION	117.6 CY		
002C	2033000000-E	815	SUBDRAIN FINE AGGREGATE	88.2 CY		
0021	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	525 LF		
0022	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	16 EA		
0023	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0024	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
002E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0027	3030000000-E	862	STEEL BM GUARDRAIL	312.5 LF		
002E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
002S	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
003C	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0031	3628000000-E	876	RIP RAP, CLASS I	145 TON		
0032	3635000000-E	876	RIP RAP, CLASS II	200 TON		
0033	3649000000-E	876	RIP RAP, CLASS B	1 TON		
0034	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	606 SY		
003E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	388 SF		
003E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	132 SF		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4430000000-N	1130	DRUMS	8 EA		
003E	4445000000-E	1145	BARRICADES (TYPE III)	102 LF		
0039	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	5,512 LF		
004C	6000000000-E	1605	TEMPORARY SILT FENCE	1,500 LF		
0041	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	120 TON		
0042	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	180 TON		
0043	6012000000-E	1610	SEDIMENT CONTROL STONE	140 TON		
0044	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0045	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0046	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25 TON		
0047	6029000000-E	SP	SAFETY FENCE	350 LF		
004E	6030000000-E	1630	SILT EXCAVATION	450 CY		
0049	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,500 SY		
005C	6037000000-E	SP	COIR FIBER MAT	30 SY		
0051	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	200 SY		
0052	6042000000-E	1632	1/4" HARDWARE CLOTH	20 LF		
0053	6070000000-N	SP	SPECIAL STILLING BASINS	4 EA		
0054	6071030000-E	SP	COIR FIBER BAFFLES	200 LF		
005E	6071050000-E	SP	*** SKIMMER (1-1/2")	5 EA		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6084000000-E	1660	SEEDING & MULCHING	8 ACR		
0057	6087000000-E	1660	MOWING	0.5 ACR		
005E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0059	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
006C	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0061	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0062	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0063	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0064	6123000000-E	1670	REFORESTATION	0.25 ACR		
STRUCTURE ITEMS						
006E	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (16 + 22.00-L-)	Lump Sum	L.S.	
006E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16 + 22.00-L-)	Lump Sum	L.S.	
0067	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	32.6 LF		
006E	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	12 LF		
0069	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	32.6 LF		
007C	8113000000-N	SP	SID INSPECTION	1 EA		
0071	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		

County : Rutherford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (16+22.00-L-)	Lump Sum	L.S.	
0073	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	5,280 SF		
0074	8161000000-E	420	GROOVING BRIDGE FLOORS	4,902 SF		
0075	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	55.4 CY		
0076	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+22.00-L-)	Lump Sum	L.S.	
0077	8217000000-E	425	REINFORCING STEEL (BRIDGE)	13,205 LB		
007E	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,225 LB		
0079	8265000000-E	430	54" PRESTRESSED CONCRETE GIRDERS	629.333 LF		
008C	8364000000-E	450	HP12X53 STEEL PILES	335 LF		
0081	8391000000-N	450	STEEL PILE POINTS	9 EA		
0082	8503000000-E	460	CONCRETE BARRIER RAIL	316.67 LF		
0083	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	165 TON		
0084	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	185 SY		
008E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0086	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0806/Oct31/Q42361.403/D410931760000/E86			Total Amount Of Bid For Entire Project :			

Contract No **C202033**

County (ies): **Rutherford**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General