

County : Surry

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17 + 40.00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	350 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	20 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	250 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	250 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	10 TON		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	32 LF		
0012	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	48 LF		
0013	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0014	1121000000-E	520	AGGREGATE BASE COURSE	200 TON		
0015	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	290 TON		
0017	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	430 TON		

County : Surry

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	41 TON		
001E	2000000000-N	806	RIGHT OF WAY MARKERS	8 EA		
002C	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
0021	2033000000-E	815	SUBDRAIN FINE AGGREGATE	35 CY		
0022	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0023	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0024	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
002E	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0027	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
002E	2556000000-E	846	SHOULDER BERM GUTTER	240 LF		
002E	3030000000-E	862	STEEL BM GUARDRAIL	250 LF		
003C	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0031	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0032	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
003E	3649000000-E	876	RIP RAP, CLASS B	15 TON		
0034	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	375 SY		
003E	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		

County : Surry

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	452 SF		
0037	4430000000-N	1130	DRUMS	10 EA		
003E	4435000000-N	1135	CONES	10 EA		
003E	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
004C	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	7,000 LF		
0041	6000000000-E	1605	TEMPORARY SILT FENCE	260 LF		
0042	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0043	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	115 TON		
0044	6012000000-E	1610	SEDIMENT CONTROL STONE	145 TON		
004E	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
004E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0047	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
004E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	230 LF		
004E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
005C	6029000000-E	SP	SAFETY FENCE	240 LF		
0051	6030000000-E	1630	SILT EXCAVATION	520 CY		
0052	6036000000-E	1631	MATTING FOR EROSION CONTROL	740 SY		
0053	6037000000-E	SP	COIR FIBER MAT	25 SY		
0054	6042000000-E	1632	1/4" HARDWARE CLOTH	100 LF		

County : Surry

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6070000000-N	SP	SPECIAL STILLING BASINS	4 EA		
005E	6071030000-E	SP	COIR FIBER BAFFLES	165 LF		
0057	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		
005E	6084000000-E	1660	SEEDING & MULCHING	2 ACR		
005E	6087000000-E	1660	MOWING	1 ACR		
006C	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0061	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0062	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0063	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5 TON		
0064	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
006E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
006E	6123000000-E	1670	REFORESTATION	0.1 ACR		

STRUCTURE ITEMS

0067	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17 + 40.00-L-)	Lump Sum	L.S.	
006E	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	41 LF		
006E	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	8 LF		
007C	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	35 LF		
0071	8113000000-N	SP	SID INSPECTION	1 EA		

County : Surry

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	8114000000-N	SP	SPT TESTING	1 EA		
0073	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0074	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (17 + 40.00-L-)	Lump Sum	L.S.	
0075	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	53.1 CY		
0076	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17 + 40.00-L-)	Lump Sum	L.S.	
0077	8217000000-E	425	REINFORCING STEEL (BRIDGE)	11,507 LB		
0078	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,288 LB		
0079	8364000000-E	450	HP12X53 STEEL PILES	330 LF		
008C	8391000000-N	450	STEEL PILE POINTS	14 EA		
0081	8503000000-E	460	CONCRETE BARRIER RAIL	225.5 LF		
0082	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	425 TON		
0083	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	475 SY		
0084	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
008E	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	1,238.88 LF		

1349/Oct29/Q29179.08/D392556260000/E85

Total Amount Of Bid For Entire Project :

Contract No **C201816**

County (ies): **Surry**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General