

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+71.00)	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	400 CY		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0106000000-E	230	BORROW EXCAVATION	1,500 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	280 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	400 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	400 SY		
0010	0241000000-E	SP	GENERIC GRADING ITEM ROCK PLATING	100 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	6 TON		
0012	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	48 LF		
0013	0995000000-E	340	PIPE REMOVAL	20 LF		
0014	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	230 TON		
0016	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	125 TON		
0017	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	580 TON		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	51 TON		
001E	2000000000-N	806	RIGHT OF WAY MARKERS	18 EA		
002C	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0021	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0022	2556000000-E	846	SHOULDER BERM GUTTER	35 LF		
0023	3030000000-E	862	STEEL BM GUARDRAIL	625 LF		
0024	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0025	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (BIC)	1 EA		
0026	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0027	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	7 EA		
002E	3628000000-E	876	RIP RAP, CLASS I	200 TON		
002E	3649000000-E	876	RIP RAP, CLASS B	69 TON		
003C	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	808 SY		
0031	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0032	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	40 LF		
0033	4102000000-N	904	SIGN ERECTION, TYPE E	3 EA		
0034	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	9 EA		
003E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	355 SF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94	SF	
0037	4445000000-E	1145	BARRICADES (TYPE III)	64	LF	
003E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,120	LF	
003E	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,120	LF	
004C	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	460	LF	
0041	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	30	EA	
0042	6000000000-E	1605	TEMPORARY SILT FENCE	200	LF	
0043	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	80	TON	
0044	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	260	TON	
004E	6012000000-E	1610	SEDIMENT CONTROL STONE	130	TON	
004E	6015000000-E	1615	TEMPORARY MULCHING	2	ACR	
0047	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
004E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.25	TON	
004E	6029000000-E	SP	SAFETY FENCE	700	LF	
005C	6030000000-E	1630	SILT EXCAVATION	700	CY	
0051	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,550	SY	
0052	6037000000-E	SP	COIR FIBER MAT	20	SY	
0053	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	270	SY	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6042000000-E	1632	1/4" HARDWARE CLOTH	50 LF		
005E	6045000000-E	SP	*** TEMPORARY PIPE (15")	100 LF		
005E	6070000000-N	SP	SPECIAL STILLING BASINS	3 EA		
0057	6071030000-E	SP	COIR FIBER BAFFLES	120 LF		
005E	6071050000-E	SP	*** SKIMMER (1-1/2")	2 EA		
005E	6084000000-E	1660	SEEDING & MULCHING	10 ACR		
006C	6087000000-E	1660	MOWING	1.5 ACR		
0061	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0062	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0063	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0064	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
006E	6111000000-E	SP	IMPERVIOUS DIKE	100 LF		
006E	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0067	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	27 EA		
006E	6123000000-E	1670	REFORESTATION	0.25 ACR		
CULVERT ITEMS						
006E	8126000000-N	414	CULVERT EXCAVATION, STA ***** (24 + 40.00-L-)	Lump Sum	L.S.	
007C	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	87 TON		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	8196000000-E	420	CLASS A CONCRETE (CULVERT)	138.6 CY		
0072	8245000000-E	425	REINFORCING STEEL (CULVERT)	21,668 LB		
STRUCTURE ITEMS						
0073	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+71.00-L)	Lump Sum	L.S.	
0074	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (17+71.00-L)	Lump Sum	L.S.	
0075	8156000000-E	SP	CONCRETE WEARING SURFACE	4,082 SF		
0076	8161000000-E	420	GROOVING BRIDGE FLOORS	5,335 SF		
0077	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	53.4 CY		
0078	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+71.00-L)	Lump Sum	L.S.	
0079	8217000000-E	425	REINFORCING STEEL (BRIDGE)	8,790 LB		
0080	8364000000-E	450	HP12X53 STEEL PILES	385 LF		
0081	8365000000-E	450	HP12X53 GALVANIZED STEEL PILES	400 LF		
0082	8475000000-E	460	TWO BAR METAL RAIL	210 LF		
0083	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 2'-10 5/8")	225.5 LF		
0084	8590000000-E	876	RIP RAP, CLASS ** (I)	105 TON		
0085	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	380 TON		
0086	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	570 SY		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0087	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
008E	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
008E	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,462.5 LF		
0914/Nov07/Q59747.5/D433314180000/E89			Total Amount Of Bid For Entire Project :			

Contract No **C202031**

County (ies): **Wake**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General