

County : Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	375 CY		
0006	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (15+31.00)	Lump Sum	L.S.	
0007	0036000000-E	225	UNDERCUT EXCAVATION	200 CY		
0008	0106000000-E	230	BORROW EXCAVATION	625 CY		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	50 CY		
0010	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	1,500 SY		
0011	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0012	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0013	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	7 TON		
0014	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	20 LF		
0015	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	28 LF		
0016	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0017	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0018	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		

County : Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	385	TON	
0020	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	340	TON	
0021	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	39	TON	
0022	2000000000-N	806	RIGHT OF WAY MARKERS	15	EA	
0023	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1	EA	
0024	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1	EA	
0025	2556000000-E	846	SHOULDER BERM GUTTER	110	LF	
0026	2570000000-N	SP	MODIFIED CONCRETE FLUME	1	EA	
0027	3030000000-E	862	STEEL BM GUARDRAIL	250	LF	
0028	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0029	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4	EA	
0030	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4	EA	
0031	3649000000-E	876	RIP RAP, CLASS B	170	TON	
0032	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	385	SY	
0033	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	46	LF	
0034	4096000000-N	904	SIGN ERECTION, TYPE D	1	EA	
0035	4102000000-N	904	SIGN ERECTION, TYPE E	2	EA	
0036	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	10	EA	

County : Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	259	SF	
003E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94	SF	
003E	4445000000-E	1145	BARRICADES (TYPE III)	80	LF	
004C	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	7,480	LF	
0041	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	10	EA	
0042	6000000000-E	1605	TEMPORARY SILT FENCE	1,550	LF	
004E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	120	TON	
0044	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	120	TON	
004E	6012000000-E	1610	SEDIMENT CONTROL STONE	35	TON	
004E	6015000000-E	1615	TEMPORARY MULCHING	3.5	ACR	
0047	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
004E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.5	TON	
004E	6029000000-E	SP	SAFETY FENCE	350	LF	
005C	6030000000-E	1630	SILT EXCAVATION	450	CY	
0051	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,610	SY	
0052	6037000000-E	SP	COIR FIBER MAT	25	SY	
005E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	70	SY	
0054	6042000000-E	1632	1/4" HARDWARE CLOTH	50	LF	

County : Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6071030000-E	SP	COIR FIBER BAFFLES	200 LF		
005E	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		
0057	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
005E	6087000000-E	1660	MOWING	1.5 ACR		
005E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
006C	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0061	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0062	6108000000-E	1665	FERTILIZER TOPDRESSING	1.75 TON		
006E	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0064	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
006E	6123000000-E	1670	REFORESTATION	0.1 ACR		
STRUCTURE ITEMS						
006E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** 15+31.00 -L-	Lump Sum	L.S.	
0067	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	750 CY		
006E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	53.9 CY		
006E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** 15+31.00 -L-	Lump Sum	L.S.	
007C	8217000000-E	425	REINFORCING STEEL (BRIDGE)	8,303 LB		
0071	8364000000-E	450	HP12X53 STEEL PILES	630 LF		

County : Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	675 LF		
0073	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	264.8 LF		
0074	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	260 TON		
0075	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	290 SY		
0076	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0077	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,453.31 LF		
0850/Nov06/Q30527.11/D327038780000/E77				Total Amount Of Bid For Entire Project :		

Contract No **C202030**

County (ies): **Warren**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General