

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	100 TON		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0009	0199000000-E	SP	TEMPORARY SHORING	3,230 SF		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	30 TON		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	116 LF		
0012	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	80 LF		
0013	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	84 LF		
0014	0995000000-E	340	PIPE REMOVAL	221 LF		
0015	1121000000-E	520	AGGREGATE BASE COURSE	300 TON		
0016	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0017	1275000000-E	600	PRIME COAT	263 GAL		
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	160 TON		
0019	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	100 TON		
0020	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	610 TON		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0021	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	52 TON		
0022	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
0023	2000000000-N	806	RIGHT OF WAY MARKERS	11 EA		
0024	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		
0025	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		
0026	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0027	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0028	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0029	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0030	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0031	2354000000-N	840	FRAME WITH GRATE, STD 840.22	1 EA		
0032	3000000000-N	SP	IMPACT ATTENUATOR UNIT, TYPE 350	1 EA		
0033	3030000000-E	862	STEEL BM GUARDRAIL	312.5 LF		
0034	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	112.5 LF		
0035	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0036	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0037	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	6 EA		
0038	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	87.5 LF		
0039	3382000000-E	862	TEMPORARY STEEL BM GUARDRAIL (SHOP CURVED)	100 LF		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0040	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)	4 EA		
0041	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	4 EA		
0042	3628000000-E	876	RIP RAP, CLASS I	70 TON		
0043	3635000000-E	876	RIP RAP, CLASS II	96 TON		
0044	3649000000-E	876	RIP RAP, CLASS B	3 TON		
0045	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	903 SY		
0046	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	543 SF		
0047	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	414 SF		
0048	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	28 SF		
0049	4430000000-N	1130	DRUMS	41 EA		
0050	4435000000-N	1135	CONES	20 EA		
0051	4445000000-E	1145	BARRICADES (TYPE III)	58 LF		
0052	4450000000-N	1150	FLAGGER	900 HR		
0053	4480000000-N	1165	TMIA	1 EA		
0054	4507000000-E	SP	WATER FILLED BARRIER	156 LF		
0055	4516000000-N	1180	SKINNY DRUM	40 EA		
0056	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	118 EA		
0057	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	22,018 LF		
0058	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	314 LF		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0059	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	1,036	LF	
0060	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	44	LF	
0061	6000000000-E	1605	TEMPORARY SILT FENCE	2,400	LF	
0062	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	205	TON	
0063	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	200	TON	
0064	6012000000-E	1610	SEDIMENT CONTROL STONE	355	TON	
0065	6015000000-E	1615	TEMPORARY MULCHING	2	ACR	
0066	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0067	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.25	TON	
0068	6024000000-E	1622	TEMPORARY SLOPE DRAINS	400	LF	
0069	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	3	EA	
0070	6029000000-E	SP	SAFETY FENCE	580	LF	
0071	6030000000-E	1630	SILT EXCAVATION	395	CY	
0072	6036000000-E	1631	MATTING FOR EROSION CONTROL	4,750	SY	
0073	6037000000-E	SP	COIR FIBER MAT	10	SY	
0074	6042000000-E	1632	1/4" HARDWARE CLOTH	250	LF	
0075	6070000000-N	SP	SPECIAL STILLING BASINS	8	EA	
0076	6071010000-E	SP	WATTLE	100	LF	
0077	6071020000-E	SP	POLYACRYLAMIDE (PAM)	36	LB	

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0078	6071030000-E	SP	COIR FIBER BAFFLES	40 LF		
0079	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
0080	6084000000-E	1660	SEEDING & MULCHING	4 ACR		
0081	6087000000-E	1660	MOWING	1.5 ACR		
0082	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0083	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0084	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0085	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5 TON		
0086	6111000000-E	SP	IMPERVIOUS DIKE	340 LF		
0087	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0088	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0089	6123000000-E	1670	REFORESTATION	0.15 ACR		

CULVERT ITEMS

0090	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (15+83.00-L-)	Lump Sum	L.S.	
0091	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+83.00-L-)	Lump Sum	L.S.	
0092	8196000000-E	420	CLASS A CONCRETE (CULVERT)	112 CY		
0093	8590000000-E	876	RIP RAP, CLASS ** (II)	22 TON		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0094	8804000000-N	SP	GENERIC CULVERT ITEM PRECAST REINFORCED CONCRETE 3- SIDED CULVERT @ STA. 15+83.00-L-	Lump Sum	L.S.	

1415/Feb04/Q43761.15/D366534310000/E93

Total Amount Of Bid For Entire Project :

Contract No **C202111**

County (ies): **Ashe**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General