

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0000930000-E	SP	GENERIC MISCELLANEOUS ITEM STEEL PIPE HANDRAIL FOR RETAINING WALL	131 LF		
0004	0036000000-E	225	UNDERCUT EXCAVATION	6,350 CY		
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	200 TON		
0008	0106000000-E	230	BORROW EXCAVATION	24,500 CY		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	875 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0011	0199000000-E	SP	TEMPORARY SHORING	725 SF		
0012	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL	200 CY		
0013	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	942 TON		
0014	0343000000-E	310	15" SIDE DRAIN PIPE	308 LF		
0015	0345000000-E	310	24" SIDE DRAIN PIPE	212 LF		
0016	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	24 LF		
0017	0426000000-E	310	72" RC PIPE CULVERTS, CLASS III	140 LF		
0018	0453000000-E	310	*** PIPE END SECTION (15")	2 EA		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0453000000-E	310	*** PIPE END SECTION (18")	2	EA	
0020	0453000000-E	310	*** PIPE END SECTION (24")	1	EA	
0021	0995000000-E	340	PIPE REMOVAL	2,674	LF	
0022	1077000000-E	SP	#57 STONE	10	TON	
0023	1110000000-E	510	STABILIZER AGGREGATE	2,500	TON	
0024	1121000000-E	520	AGGREGATE BASE COURSE	15,000	TON	
0025	1220000000-E	545	INCIDENTAL STONE BASE	1,000	TON	
0026	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	2,900	TON	
0027	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	11,000	TON	
0028	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	11,400	TON	
0029	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,326	TON	
0030	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	314	TON	
0031	2022000000-E	815	SUBDRAIN EXCAVATION	1,549	CY	
0032	2033000000-E	815	SUBDRAIN FINE AGGREGATE	774	CY	
0033	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	4,600	LF	
0034	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	138	EA	
0035	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	10	EA	
0036	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	60	LF	

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2190000000-N	828	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE	10 EA		
003E	2209000000-E	838	ENDWALLS	19 CY		
003E	2220000000-E	838	REINFORCED ENDWALLS	15 CY		
004C	2253000000-E	840	PIPE COLLARS	2 CY		
0041	2264000000-E	840	PIPE PLUGS	1 CY		
004Z	2275000000-E	SP	FLOWABLE FILL	45 CY		
004Z	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	88 EA		
0044	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	5 LF		
004E	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	22 EA		
004E	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	4 EA		
0047	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	29 EA		
004E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	13 EA		
004E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	17 EA		
005C	2396000000-N	840	FRAME WITH COVER, STD 840.54	5 EA		
0051	2440000000-N	852	CONCRETE TRANSITIONAL SECTION FOR CATCH BASIN	8 EA		
005Z	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLETS	10 EA		
005Z	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	4,140 LF		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	8,600 LF		
005E	2570000000-N	SP	MODIFIED CONCRETE FLUME	2 EA		
005E	2591000000-E	848	4" CONCRETE SIDEWALK	3,625 SY		
0057	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	39 EA		
005E	2612000000-E	848	6" CONCRETE DRIVEWAY	600 SY		
005E	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	1,650 SY		
006C	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	2 EA		
0061	2830000000-N	858	ADJUSTMENT OF MANHOLES	5 EA		
0062	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	23 EA		
0063	2905000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX	2 EA		
0064	2920000000-N	SP	CONVERT EXISTING DROP INLET TO CATCH BASIN	1 EA		
006E	3030000000-E	862	STEEL BM GUARDRAIL	100 LF		
006E	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	25 LF		
0067	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	1 EA		
006E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
006E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	1 EA		
007C	3360000000-E	863	REMOVE EXISTING GUARDRAIL	172 LF		
0071	3536000000-E	866	CHAIN LINK FENCE, 48" FABRIC	8,580 LF		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	718 EA		
0073	3548000000-E	866	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	55 EA		
0074	3557000000-E	866	ADDITIONAL BARBED WIRE	100 LF		
0075	3628000000-E	876	RIP RAP, CLASS I	83 TON		
0076	3649000000-E	876	RIP RAP, CLASS B	238 TON		
0077	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	4,488 SY		
0078	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	4 EA		
0079	4057000000-E	SP	OVERHEAD FOOTING	24 CY		
0080	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	984 LF		
0081	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (33+00.00-L-)	Lump Sum	L.S.	
0082	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (36+75.00-L-)	Lump Sum	L.S.	
0083	4096000000-N	904	SIGN ERECTION, TYPE D	3 EA		
0084	4102000000-N	904	SIGN ERECTION, TYPE E	56 EA		
0085	4108000000-N	904	SIGN ERECTION, TYPE F	13 EA		
0086	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	15 EA		
0087	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	324 SF		
0088	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	928 SF		
0089	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	197 SF		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
009C	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2	EA	
0091	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	4	EA	
0092	4430000000-N	1130	DRUMS	290	EA	
0093	4435000000-N	1135	CONES	100	EA	
0094	4445000000-E	1145	BARRICADES (TYPE III)	808	LF	
009E	4450000000-N	1150	FLAGGER	4,590	HR	
009E	4480000000-N	1165	TMIA	2	EA	
0097	4507000000-E	SP	WATER FILLED BARRIER	337	LF	
009E	4508000000-E	SP	RESET WATER FILLED BARRIER	152	LF	
009E	4510000000-N	SP	POLICE	300	HR	
010C	4516000000-N	1180	SKINNY DRUM	150	EA	
0101	4520000000-N	1266	TUBULAR MARKERS (FIXED)	200	EA	
0102	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	683	EA	
0103	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	17,618	LF	
0104	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	18,519	LF	
010E	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,066	LF	
010E	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	742	LF	
0107	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	655	LF	

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
010E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	89	EA	
010E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	124,365	LF	
011C	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	3,998	LF	
0111	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,416	LF	
0112	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	208	EA	
0113	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	12,209	LF	
0114	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	300	LF	
011E	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	366	LF	
011E	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	15	EA	
0117	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	195	EA	
011E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	444	EA	
011E	4915000000-E	1264	7' U-CHANNEL POSTS	5	EA	
012C	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	5	EA	
0121	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0122	5325300000-E	1510	3" WATER LINE	310	LF	
0123	5325600000-E	1510	6" WATER LINE	988	LF	
0124	5325800000-E	1510	8" WATER LINE	692	LF	
012E	5326200000-E	1510	12" WATER LINE	3,669	LF	

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0126	5534000000-E	1515	*** VALVE (1-1/2")	1 EA		
0127	5534000000-E	1515	*** VALVE (3")	4 EA		
0128	5540000000-E	1515	6" VALVE	5 EA		
0129	5546000000-E	1515	8" VALVE	1 EA		
0130	5558000000-E	1515	12" VALVE	6 EA		
0131	5606000000-E	1515	2" BLOW OFF	1 EA		
0132	5648000000-N	1515	RELOCATE WATER METER	16 EA		
0133	5649000000-N	1515	RECONNECT WATER METER	12 EA		
0134	5672000000-N	1515	RELOCATE FIRE HYDRANT	4 EA		
0135	5709000000-E	1520	*** FORCE MAIN SEWER (1-1/2")	284 LF		
0136	5709000000-E	1520	*** FORCE MAIN SEWER (3")	1,963 LF		
0137	5709100000-E	1520	2" FORCE MAIN SEWER	1,354 LF		
0138	5798000000-E	1530	ABANDON *** UTILITY PIPE (3")	262 LF		
0139	5800000000-E	1530	ABANDON 6" UTILITY PIPE	1,500 LF		
0140	5801000000-E	1530	ABANDON 8" UTILITY PIPE	880 LF		
0141	5804000000-E	1530	ABANDON 12" UTILITY PIPE	3,325 LF		
0142	5816000000-N	1530	ABANDON UTILITY MANHOLE	2 EA		
0143	5871200000-E	1550	TRENCHLESS INSTALLATION OF 3" IN SOIL	100 LF		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0144	5871210000-E	1550	TRENCHLESS INSTALLATION OF 3" NOT IN SOIL	100 LF		
014E	5871500000-E	1550	TRENCHLESS INSTALLATION OF 8" IN SOIL	70 LF		
014E	5871510000-E	1550	TRENCHLESS INSTALLATION OF 8" NOT IN SOIL	70 LF		
0147	5871700000-E	1550	TRENCHLESS INSTALLATION OF 12" IN SOIL	77 LF		
014E	5871710000-E	1550	TRENCHLESS INSTALLATION OF 12" NOT IN SOIL	77 LF		
014E	5882000000-N	SP	GENERIC UTILITY ITEM RECONNECT SEWER FORCE MAIN SERVICE	16 EA		
015C	6000000000-E	1605	TEMPORARY SILT FENCE	6,100 LF		
0151	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	1,200 TON		
0152	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,400 TON		
015E	6012000000-E	1610	SEDIMENT CONTROL STONE	1,275 TON		
0154	6015000000-E	1615	TEMPORARY MULCHING	23.5 ACR		
015E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	600 LB		
015E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	3.25 TON		
0157	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50 LF		
015E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
015E	6029000000-E	SP	SAFETY FENCE	3,500 LF		
016C	6030000000-E	1630	SILT EXCAVATION	2,450 CY		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0161	6036000000-E	1631	MATTING FOR EROSION CONTROL	10,500	SY	
0162	6037000000-E	SP	COIR FIBER MAT	75	SY	
0163	6042000000-E	1632	1/4" HARDWARE CLOTH	2,450	LF	
0164	6046000000-E	SP	TEMPORARY PIPE FOR STREAM CROSSING	20	LF	
0165	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	75	SY	
0166	6070000000-N	SP	SPECIAL STILLING BASINS	6	EA	
0167	6071030000-E	SP	COIR FIBER BAFFLES	875	LF	
0168	6071050000-E	SP	*** SKIMMER (1-1/2")	7	EA	
0169	6084000000-E	1660	SEEDING & MULCHING	27.5	ACR	
0170	6087000000-E	1660	MOWING	16.5	ACR	
0171	6090000000-E	1661	SEED FOR REPAIR SEEDING	200	LB	
0172	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.75	TON	
0173	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	450	LB	
0174	6108000000-E	1665	FERTILIZER TOPDRESSING	13	TON	
0175	6111000000-E	SP	IMPERVIOUS DIKE	650	LF	
0176	6114000000-N	SP	SPECIALIZED HAND MOWING	5	HR	
0177	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	36	EA	
0178	6120000000-E	SP	CULVERT DIVERSION CHANNEL	275	CY	
0179	6123000000-E	1670	REFORESTATION	0.5	ACR	
0180	6126000000-E	SP	STREAMBANK REFORESTATION	0.1	ACR	

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0181	6135000000-E	SP	GENERIC EROSION CONTROL ITEM WETLAND GRASS PLANTING	0.9 ACR		
0182	7000000000-E	1705	PEDESTRIAN SIGNAL HEAD (**", ** SECTION) (16", 1)	8 EA		
0183	7060000000-E	1705	SIGNAL CABLE	5,490 LF		
0184	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	19 EA		
0185	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	3 EA		
0186	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	7 EA		
0187	7264000000-E	1710	MESSENGER CABLE (3/8")	615 LF		
0188	7279000000-E	1715	TRACER WIRE	2,005 LF		
0189	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2")	1,330 LF		
0190	7301000000-E	1715	DIRECTIONAL DRILL (***** (1, 2")	1,355 LF		
0191	7301000000-E	1715	DIRECTIONAL DRILL (***** (3, 2")	620 LF		
0192	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	20 EA		
0193	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEA- VY DUTY)	3 EA		
0194	7360000000-N	1720	WOOD POLE	4 EA		
0195	7372000000-N	1721	GUY ASSEMBLY	8 EA		
0196	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0197	7420000000-E	1722	2" RISER WITH WEATHERHEAD	5 EA		
0198	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	4,515 LF		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
019	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	9,180	LF	
020	7516000000-E	1730	COMMUNICATIONS CABLE (**FIBER) (12)	2,435	LF	
0201	7540000000-N	1731	SPLICE ENCLOSURE	1	EA	
0202	7552000000-N	1731	INTERCONNECT CENTER	1	EA	
0203	7564000000-N	1732	FIBER-OPTIC TRANSCEIVER, DROP & REPEAT	1	EA	
0204	7566000000-N	1733	DELINEATOR MARKER	1	EA	
0205	7574000000-N	SP	FURNISH FIBER-OPTIC TRANSCEIV- ER	1	EA	
0206	7575142000-N	SP	900MHZ WIRELESS RADIO SYSTEM	3	EA	
0207	7588000000-N	SP	METAL POLE WITH SINGLE MAST ARM	8	EA	
0208	7613000000-N	SP	SOIL TEST	8	EA	
0209	7614100000-E	SP	DRILLED PIER FOUNDATION	56	CY	
0210	7631000000-N	SP	MAST ARM WITH METAL POLE DE- SIGN	8	EA	
0211	7684000000-N	1750	SIGNAL CABINET FOUNDATION	2	EA	
0212	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	2	EA	
0213	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	12	EA	
0214	7901000000-N	1753	CABINET BASE EXTENDER	2	EA	
0215	7980000000-N	SP	GENERIC SIGNAL ITEM FURNISH WIRELESS RADIO LIGHTN- ING ARRESTOR	2	EA	

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0216	7980000000-N	SP	GENERIC SIGNAL ITEM FURNISH WIRELESS RADIO MODEM	1 EA		
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0217 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	2,700 LF		
0218 AA1	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	2,072 LF		
0219 AA1	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	596 LF		
0220 AA1	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	200 LF		
*** OR ***						
0221 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	2,384 LF		
0222 AA2	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,392 LF		
0223 AA2	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	444 LF		
0224 AA2	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	168 LF		
0225 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	316 LF		
0226 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	680 LF		
0227 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	152 LF		
0228 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (48")	32 LF		
*** OR ***						
0229 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	2,384 LF		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0230 AA3	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,392 LF		
0231 AA3	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	444 LF		
0232 AA3	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	168 LF		
0233 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	316 LF		
0234 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (18", 0.064")	680 LF		
0235 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (24", 0.064")	152 LF		
0236 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (48", 0.109")	32 LF		
***** END SCHEDULE AA *****						
CULVERT ITEMS						
0237	8126000000-N	414	CULVERT EXCAVATION, STA ***** (15 + 59.77-Y-)	Lump Sum	L.S.	
0238	8126000000-N	414	CULVERT EXCAVATION, STA ***** (33 + 75.00-L-)	Lump Sum	L.S.	
0239	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	195 TON		
0240	8196000000-E	420	CLASS A CONCRETE (CULVERT)	284.5 CY		
0241	8248000000-E	425	EPOXY COATED REINFORCING STEEL (CULVERT)	51,887 LB		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
--------	-------------	-------	-------------	----------	-----------	--------

WALL ITEMS

0242	8802030000-E	SP	SEGMENTAL GRAVITY RETAINING WALLS	300	SF	
------	--------------	----	-----------------------------------	-----	----	--

0959/Feb05/Q461183.5/D1016095812000/E242 Total Amount Of Bid For Entire Project :

Contract No **C202027**

County (ies): **Brunswick**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General