

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	5,500 CY		
000E	0063000000-N	SP	GRADING	Lump Sum	L.S.	
000E	0106000000-E	230	BORROW EXCAVATION	5,100 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	130 CY		
000E	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	700 SY		
000E	0199000000-E	SP	TEMPORARY SHORING	7,000 SF		
001C	0255000000-E	SP	GENERIC GRADING ITEM SELECT MATERIAL, CLASS VI	300 TON		
0011	0255000000-E	SP	GENERIC GRADING ITEM SELECT MATERIAL, CLASS VII	1,800 TON		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	21 TON		
0013	0343000000-E	310	15" SIDE DRAIN PIPE	112 LF		
0014	0344000000-E	310	18" SIDE DRAIN PIPE	40 LF		
001E	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	16 LF		
001E	0660000000-E	310	****BIT COAT CS PIPE CULVERTS, TYPE A ***** THICK (15", 0.064")	28 LF		
0017	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
001E	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/4")	1,500 SY		

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	640	TON	
002C	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	870	TON	
0021	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	85	TON	
0022	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	400	TON	
0023	2022000000-E	815	SUBDRAIN EXCAVATION	33.6	CY	
0024	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8	CY	
002E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100	LF	
002E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3	EA	
0027	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1	EA	
002E	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6	LF	
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2	EA	
003C	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	2	EA	
0031	2556000000-E	846	SHOULDER BERM GUTTER	220	LF	
0032	3030000000-E	862	STEEL BM GUARDRAIL	2,050	LF	
0033	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	25	LF	
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10	EA	
003E	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1	EA	
003E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	7	EA	

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	8	EA	
003E	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	250	LF	
003E	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	1	EA	
004C	3628000000-E	876	RIP RAP, CLASS I	2	TON	
0041	3649000000-E	876	RIP RAP, CLASS B	2	TON	
0042	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	620	SY	
0043	3677000000-E	SP	GENERIC EROSION CONTROL ITEM ROCK PLATING	520	SY	
0044	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	220	SF	
004E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96	SF	
004E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	52	SF	
0047	4430000000-N	1130	DRUMS	80	EA	
004E	4435000000-N	1135	CONES	60	EA	
004E	4445000000-E	1145	BARRICADES (TYPE III)	48	LF	
005C	4450000000-N	1150	FLAGGER	480	HR	
0051	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4	EA	
0052	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	4	EA	
0053	4480000000-N	1165	TMIA	2	EA	
0054	4485000000-E	1170	PORTABLE CONCRETE BARRIER	1,500	LF	
005E	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	555	LF	

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	51,100 LF		
0057	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	600 LF		
005E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	40 EA		
005E	6000000000-E	1605	TEMPORARY SILT FENCE	3,000 LF		
006C	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	110 TON		
0061	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	290 TON		
0062	6012000000-E	1610	SEDIMENT CONTROL STONE	100 TON		
0063	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0064	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
006E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
006E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50 LF		
0067	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
006E	6029000000-E	SP	SAFETY FENCE	3,000 LF		
006E	6030000000-E	1630	SILT EXCAVATION	490 CY		
007C	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,200 SY		
0071	6042000000-E	1632	1/4" HARDWARE CLOTH	60 LF		
0072	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	250 SY		
0073	6071030000-E	SP	COIR FIBER BAFFLES	80 LF		

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6084000000-E	1660	SEEDING & MULCHING	2.3	ACR	
007E	6087000000-E	1660	MOWING	1	ACR	
007E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0077	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
007E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
007E	6108000000-E	1665	FERTILIZER TOPDRESSING	1	TON	
008C	6114000000-N	SP	SPECIALIZED HAND MOWING	5	HR	
0081	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	27	EA	
008Z	7060000000-E	1705	SIGNAL CABLE	2,300	LF	
008Z	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	8	EA	
0084	7252000000-E	1710	MESSENGER CABLE (1/4")	2,060	LF	
008E	7264000000-E	1710	MESSENGER CABLE (3/8")	170	LF	
008E	7360000000-N	1720	WOOD POLE	13	EA	
0087	7372000000-N	1721	GUY ASSEMBLY	8	EA	
008E	7408000000-E	1722	1" RISER WITH WEATHERHEAD	2	EA	
008E	7420000000-E	1722	2" RISER WITH WEATHERHEAD	4	EA	
009C	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	560	LF	
0091	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	2,490	LF	
009Z	7768000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)	2	EA	

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0093	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	4	EA	
<b>WALL ITEMS</b>						
0094	8430000000-E	452	SHEET PILE RETAINING WALLS	2,792	SF	
009E	8847000000-E	SP	GENERIC RETAINING WALL ITEM TIEBACK STEEL SHEET PILE RETAINING WALLS	16,888	SF	
<b>STRUCTURE ITEMS</b>						
009E	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (20 + 66.00 -L-)	Lump Sum	L.S.	
0097	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (39 + 17.00 -L-)	Lump Sum	L.S.	
009E	8112730000-N	SP	PDA TESTING	2	EA	
009E	8112740000-N	SP	PDA ASSISTANCE	2	EA	
010C	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	670	CY	
0101	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (39 + 17.00 -L-)	Lump Sum	L.S.	
0102	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	116.9	CY	
0103	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (20 + 66.00 -L-)	Lump Sum	L.S.	
0104	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (39 + 17.00 -L-)	Lump Sum	L.S.	
010E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	19,515	LB	

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
010E	8364000000-E	450	HP12X53 STEEL PILES	2,280 LF		
0107	8365000000-E	450	HP12X53 GALVANIZED STEEL PILES	1,200 LF		
010E	8387000000-E	450	PP 18 X 0.50 GALVANIZED STEEL PILES	1,610 LF		
010E	8393000000-N	450	PILE REDRIVES	37 EA		
011C	8503000000-E	460	CONCRETE BARRIER RAIL	619.66 LF		
0111	8590000000-E	876	RIP RAP, CLASS ** (I)	367 TON		
0112	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	407 SY		
0113	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0114	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	4,027.84 LF		

1316/Jan30/Q151448.6/D543115100000/E114

Total Amount Of Bid For Entire Project :

**Contract No**     **C201923**

**County (ies):**   **Columbus**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General