

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (15+13.00)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
000E	0057000000-E	226	UNDERCUT EXCAVATION	425 CY		
000E	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	350 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	209 CY		
000E	0195000000-E	265	SELECT GRANULAR MATERIAL	3,600 CY		
000E	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	4,100 SY		
001C	0199000000-E	SP	TEMPORARY SHORING	140 SF		
0011	0314000000-E	300	SELECT MATERIAL, CLASS ***** (VI)	80 TON		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	10 TON		
0013	0343000000-E	310	15" SIDE DRAIN PIPE	32 LF		
0014	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	44 LF		
001E	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	16 LF		
001E	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	2 EA		
0017	0995000000-E	340	PIPE REMOVAL	55 LF		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1121000000-E	520	AGGREGATE BASE COURSE	592 TON		
001E	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
002C	1275000000-E	600	PRIME COAT	560 GAL		
0021	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	350 TON		
0022	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	415 TON		
002E	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	800 TON		
0024	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	83 TON		
002E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	10 TON		
002E	2000000000-N	806	RIGHT OF WAY MARKERS	10 EA		
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
002E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
002E	2556000000-E	846	SHOULDER BERM GUTTER	40 LF		
003C	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	2 EA		
0031	3030000000-E	862	STEEL BM GUARDRAIL	850 LF		
0032	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
003E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0034	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
003E	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	650 LF		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)	4 EA		
0037	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	4 EA		
003E	3649000000-E	876	RIP RAP, CLASS B	98 TON		
003E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	492 SY		
004C	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	128 SF		
0041	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0042	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	56 SF		
004E	4430000000-N	1130	DRUMS	50 EA		
0044	4435000000-N	1135	CONES	40 EA		
004E	4445000000-E	1145	BARRICADES (TYPE III)	32 LF		
004E	4450000000-N	1150	FLAGGER	400 HR		
0047	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	50 EA		
004E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,620 LF		
004E	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,620 LF		
005C	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	760 LF		
0051	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	8,064 LF		
0052	5325600000-E	1510	6" WATER LINE	514 LF		
005E	5326200000-E	1510	12" WATER LINE	460 LF		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	5648000000-N	1515	RELOCATE WATER METER	1		
					EA	
005E	5800000000-E	1530	ABANDON 6" UTILITY PIPE	896		
					LF	
005E	5804000000-E	1530	ABANDON 12" UTILITY PIPE	456		
					LF	
0057	5871400000-E	1550	TRENCHLESS INSTALLATION OF 6" IN SOIL	400		
					LF	
005E	6000000000-E	1605	TEMPORARY SILT FENCE	2,750		
					LF	
005E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	100		
					TON	
006C	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	200		
					TON	
0061	6012000000-E	1610	SEDIMENT CONTROL STONE	120		
					TON	
0062	6015000000-E	1615	TEMPORARY MULCHING	2.5		
					ACR	
006E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100		
					LB	
0064	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25		
					TON	
006E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	65		
					LF	
006E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2		
					EA	
0067	6029000000-E	SP	SAFETY FENCE	450		
					LF	
006E	6030000000-E	1630	SILT EXCAVATION	765		
					CY	
006E	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,700		
					SY	
007C	6037000000-E	SP	COIR FIBER MAT	100		
					SY	
0071	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	205		
					SY	
0072	6042000000-E	1632	1/4" HARDWARE CLOTH	230		
					LF	

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6071010000-E	SP	WATTLE	50 LF		
0074	6071020000-E	SP	POLYACRYLAMIDE (PAM)	16 LB		
007E	6071030000-E	SP	COIR FIBER BAFFLES	225 LF		
007E	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		
0077	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
007E	6087000000-E	1660	MOWING	1.5 ACR		
007E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
008C	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0081	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0082	6108000000-E	1665	FERTILIZER TOPDRESSING	1.75 TON		
008E	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0084	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
008E	6123000000-E	1670	REFORESTATION	1.4 ACR		

STRUCTURE ITEMS

008E	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (15 + 13.00-L-)	Lump Sum	L.S.	
0087	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (15 + 13.00-L-)	Lump Sum	L.S.	
008E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15 + 13.00-L-)	Lump Sum	L.S.	

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (15 + 13.00-L-)	Lump Sum	L.S.	
009C	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	60.6 CY		
0091	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15 + 13.00-L-)	Lump Sum	L.S.	
0092	8217000000-E	425	REINFORCING STEEL (BRIDGE)	9,188 LB		
009E	8364000000-E	450	HP12X53 STEEL PILES	525 LF		
0094	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	990 LF		
009E	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	355.5 LF		
009E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	642 TON		
0097	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	713 SY		
009E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
009E	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,951.14 LF		

0851/Feb02/Q51555.89/D432675710000/E99

Total Amount Of Bid For Entire Project :

Contract No **C202100**

County (ies): **Davidson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General