

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (14 + 92.02)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	600 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	200 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	45 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0011	0199000000-E	SP	TEMPORARY SHORING	402 SF		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	35 TON		
0013	0344000000-E	310	18" SIDE DRAIN PIPE	144 LF		
0014	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	108 LF		
0015	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	56 LF		
0016	0995000000-E	340	PIPE REMOVAL	316 LF		
0017	1121000000-E	520	AGGREGATE BASE COURSE	370 TON		
0018	1220000000-E	545	INCIDENTAL STONE BASE	250 TON		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	530 TON		
0020	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	460 TON		
0021	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	53 TON		
0022	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	100 TON		
0023	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
0024	2033000000-E	815	SUBDRAIN FINE AGGREGATE	35 CY		
0025	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0026	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0027	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0028	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0029	2209000000-E	838	ENDWALLS	4 CY		
0030	2570000000-N	SP	MODIFIED CONCRETE FLUME	1 EA		
0031	3030000000-E	862	STEEL BM GUARDRAIL	237.5 LF		
0032	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	87.5 LF		
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0034	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	3 EA		
0035	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0036	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	137.5		
				LF		
003E	3389000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (350 TL-2)	4		
				EA		
003E	3436000000-N	862	GENERIC GUARDRAIL ITEM GUARDRAIL ANCHOR UNIT, TYPE TEMPORARY RETROFIT	1		
				EA		
004C	3574000000-E	867	GENERIC FENCING ITEM LANDSCAPE FENCE RESET	305		
				LF		
0041	3628000000-E	876	RIP RAP, CLASS I	2		
				TON		
0042	3649000000-E	876	RIP RAP, CLASS B	110		
				TON		
0043	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	650		
				SY		
0044	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	144		
				SF		
004E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96		
				SF		
004E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	30		
				SF		
0047	4430000000-N	1130	DRUMS	80		
				EA		
004E	4445000000-E	1145	BARRICADES (TYPE III)	40		
				LF		
004E	4450000000-N	1150	FLAGGER	960		
				HR		
005C	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	11,586		
				LF		
0051	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	81		
				LF		
0052	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	3,302		
				LF		
005E	6000000000-E	1605	TEMPORARY SILT FENCE	1,780		
				LF		
0054	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	200		
				TON		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	445 TON		
005E	6012000000-E	1610	SEDIMENT CONTROL STONE	145 TON		
0057	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
005E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
005E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2.25 TON		
006C	6024000000-E	1622	TEMPORARY SLOPE DRAINS	150 LF		
0061	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
006E	6029000000-E	SP	SAFETY FENCE	500 LF		
006E	6030000000-E	1630	SILT EXCAVATION	840 CY		
0064	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,400 SY		
006E	6037000000-E	SP	COIR FIBER MAT	20 SY		
006E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	125 SY		
0067	6042000000-E	1632	1/4" HARDWARE CLOTH	125 LF		
006E	6071030000-E	SP	COIR FIBER BAFFLES	135 LF		
006E	6071050000-E	SP	*** SKIMMER (1-1/2")	3 EA		
007C	6084000000-E	1660	SEEDING & MULCHING	3.5 ACR		
0071	6087000000-E	1660	MOWING	1 ACR		
0072	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
007E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
007E	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
007E	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0077	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
STRUCTURE ITEMS						
007E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+92.50-L-)	Lump Sum	L.S.	
007E	8096000000-E	SP	PILE EXCAVATION IN SOIL	80 LF		
008C	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (14+92.50-L-)	Lump Sum	L.S.	
0081	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	27.9 CY		
0082	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14+92.50-L-)	Lump Sum	L.S.	
008E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	4,342 LB		
0084	8364000000-E	450	HP12X53 STEEL PILES	880 LF		
008E	8391000000-N	450	STEEL PILE POINTS	16 EA		
008E	8503000000-E	460	CONCRETE BARRIER RAIL	125.04 LF		
0087	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	180 TON		
008E	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	200 SY		
008E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
009C	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	687.67 LF		

1505/Feb02/Q35180.86/D373884580000/E90

Total Amount Of Bid For Entire Project :

Contract No **C202071**

County (ies): **Haywood**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General