

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	3,000 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	4,725 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	72 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	5,000 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	1,215 TON		
0011	0344000000-E	310	18" SIDE DRAIN PIPE	56 LF		
0012	0974000000-E	SP	*** WELDED STEEL PIPE, ***** THICK, GRADE B, (UNDER RR) (15", 0.500")	88 LF		
0013	0995000000-E	340	PIPE REMOVAL	552 LF		
0014	1110000000-E	510	STABILIZER AGGREGATE	1,000 TON		
0015	1220000000-E	545	INCIDENTAL STONE BASE	1,500 TON		
0016	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 4")	1,200 SY		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	775 TON		
0018	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	11,500 TON		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	925 TON		
0020	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	4,200 TON		
0021	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,150 TON		
0022	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	7,150 TON		
0023	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	838 TON		
0024	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	430 TON		
0025	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	725 TON		
0026	2000000000-N	806	RIGHT OF WAY MARKERS	86 EA		
0027	2022000000-E	815	SUBDRAIN EXCAVATION	115 CY		
0028	2033000000-E	815	SUBDRAIN FINE AGGREGATE	85 CY		
0029	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0030	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
0031	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0032	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0033	2253000000-E	840	PIPE COLLARS	2 CY		
0034	2264000000-E	840	PIPE PLUGS	3 CY		
0035	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	89 EA		
0036	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	11 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0038	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	6 EA		
0039	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	5 EA		
0040	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	25 EA		
0041	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	32 EA		
0042	2396000000-N	840	FRAME WITH COVER, STD 840.54	10 EA		
0043	2418000000-E	SP	FRAME WITH GRATES, DRIVEWAY DROP INLET	32 LF		
0044	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLETS	1 EA		
0045	2535000000-E	846	***X*** CONCRETE CURB (8" x 18")	270 LF		
0046	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	9,780 LF		
0047	2591000000-E	848	4" CONCRETE SIDEWALK	3,800 SY		
0048	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	60 EA		
0049	2612000000-E	848	6" CONCRETE DRIVEWAY	1,550 SY		
0050	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	1,000 SY		
0051	2739000000-E	852	GENERIC PAVING ITEM 6" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	300 SY		
0052	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	6 EA		
0053	2830000000-N	858	ADJUSTMENT OF MANHOLES	11 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	46 EA		
0055	2893000000-N	SP	CONVERT EXISTING CATCH BASIN TO JUNCTION BOX WITH MANHOLE COVER	2 EA		
0056	3030000000-E	862	STEEL BM GUARDRAIL	250 LF		
0057	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0058	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	1 EA		
0059	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	1 EA		
0060	3500000000-E	866	WOVEN WIRE FENCE, *** FABRIC (48")	330 LF		
0061	3506000000-E	866	4" TIMBER FENCE POSTS, ***** LONG (8')	20 EA		
0062	3512000000-E	866	5" TIMBER FENCE POSTS, ***** LONG (8')	7 EA		
0063	3628000000-E	876	RIP RAP, CLASS I	7 TON		
0064	3649000000-E	876	RIP RAP, CLASS B	23 TON		
0065	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	905 SY		
0066	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	1,374 LF		
0067	4096000000-N	904	SIGN ERECTION, TYPE D	5 EA		
0068	4102000000-N	904	SIGN ERECTION, TYPE E	47 EA		
0069	4108000000-N	904	SIGN ERECTION, TYPE F	22 EA		
0070	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	53 EA		
0071	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	2,138 SF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	1,010 SF		
0073	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	346 SF		
0074	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0075	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	4 EA		
0076	4430000000-N	1130	DRUMS	510 EA		
0077	4435000000-N	1135	CONES	95 EA		
0078	4445000000-E	1145	BARRICADES (TYPE III)	424 LF		
0079	4450000000-N	1150	FLAGGER	9,180 HR		
0080	4480000000-N	1165	TMIA	2 EA		
0081	4507000000-E	SP	WATER FILLED BARRIER	2,581 LF		
0082	4508000000-E	SP	RESET WATER FILLED BARRIER	1,304 LF		
0083	4510000000-N	SP	POLICE	540 HR		
0084	4516000000-N	1180	SKINNY DRUM	170 EA		
0085	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	613 EA		
0086	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	7,041 LF		
0087	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	19,483 LF		
0088	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,088 LF		
0089	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	960 LF		
0090	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	414 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	702 LF		
0092	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	26 EA		
0093	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	103 EA		
0094	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (I)	1,367 LF		
0095	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	4,101 LF		
0096	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL, TYPE ** (I)	5 EA		
0097	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL, TYPE ** (IV)	10 EA		
0098	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	68,048 LF		
0099	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	4,096 LF		
0100	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	828 LF		
0101	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,404 LF		
0102	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	52 EA		
0103	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	206 EA		
0104	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	27,500 LF		
0105	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	800 LF		
0106	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	368 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	40 EA		
0108	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	60 EA		
0109	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	428 EA		
0110	5325600000-E	1510	6" WATER LINE	2,772.5 LF		
0111	5325800000-E	1510	8" WATER LINE	1,013 LF		
0112	5540000000-E	1515	6" VALVE	9 EA		
0113	5546000000-E	1515	8" VALVE	1 EA		
0114	5648000000-N	1515	RELOCATE WATER METER	34 EA		
0115	5649000000-N	1515	RECONNECT WATER METER	11 EA		
0116	5666000000-E	1515	FIRE HYDRANT	6 EA		
0117	5709200000-E	1520	4" FORCE MAIN SEWER	365 LF		
0118	5800000000-E	1530	ABANDON 6" UTILITY PIPE	1,831 LF		
0119	5815500000-N	1530	REMOVE FIRE HYDRANT	6 EA		
0120	5882000000-N	SP	GENERIC UTILITY ITEM ABANDON WATER VAULT	1 EA		
0121	6000000000-E	1605	TEMPORARY SILT FENCE	4,750 LF		
0122	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	915 TON		
0123	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	550 TON		
0124	6012000000-E	1610	SEDIMENT CONTROL STONE	1,200 TON		
0125	6015000000-E	1615	TEMPORARY MULCHING	10.5 ACR		
0126	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	350 LB		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0127	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	3.25 TON		
0128	6024000000-E	1622	TEMPORARY SLOPE DRAINS	410 LF		
0129	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0130	6030000000-E	1630	SILT EXCAVATION	3,165 CY		
0131	6036000000-E	1631	MATTING FOR EROSION CONTROL	6,500 SY		
0132	6037000000-E	SP	COIR FIBER MAT	15 SY		
0133	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,200 SY		
0134	6042000000-E	1632	1/4" HARDWARE CLOTH	2,650 LF		
0135	6071030000-E	SP	COIR FIBER BAFFLES	470 LF		
0136	6071050000-E	SP	*** SKIMMER (1-1/2")	2 EA		
0137	6084000000-E	1660	SEEDING & MULCHING	11.5 ACR		
0138	6087000000-E	1660	MOWING	6.5 ACR		
0139	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		
0140	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0141	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	225 LB		
0142	6108000000-E	1665	FERTILIZER TOPDRESSING	6.25 TON		
0143	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0144	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	27 EA		
0145	7000000000-E	1705	PEDESTRIAN SIGNAL HEAD (**, ** SECTION) (16", 1)	4 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0146	7060000000-E	1705	SIGNAL CABLE	2,070	LF	
0147	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	20	EA	
0148	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	4	EA	
0149	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	3	EA	
0150	7264000000-E	1710	MESSENGER CABLE (3/8")	950	LF	
0151	7288000000-E	1715	PAVED TRENCHING (*****) (1, 2")	60	LF	
0152	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	475	LF	
0153	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	9	EA	
0154	7360000000-N	1720	WOOD POLE	8	EA	
0155	7372000000-N	1721	GUY ASSEMBLY	16	EA	
0156	7408000000-E	1722	1" RISER WITH WEATHERHEAD	2	EA	
0157	7420000000-E	1722	2" RISER WITH WEATHERHEAD	8	EA	
0158	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	6,150	LF	
0159	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	10,690	LF	
0160	7636000000-N	1745	SIGN FOR SIGNALS	10	EA	
0161	7675000000-N	SP	LED BLANKOUT SIGN	2	EA	
0162	7684000000-N	1750	SIGNAL CABINET FOUNDATION	2	EA	
0163	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	2	EA	
0164	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	12	EA	

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0165	7901000000-N	1753	CABINET BASE EXTENDER	2	EA	
0166	8436000000-E	453	GRAVITY RETAINING WALLS	1,202	SF	
0167	8839000000-E	SP	GENERIC RETAINING WALL ITEM PEDESTRIAN SAFETY HANDRAIL	379	LF	
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0168	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	4,144	LF	
AA1						
0169	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,368	LF	
AA1						
0170	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	1,148	LF	
AA1						
0171	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	116	LF	
AA1						
*** OR ***						
0172	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	3,980	LF	
AA2						
0173	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,260	LF	
AA2						
0174	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	1,016	LF	
AA2						
0175	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	64	LF	
AA2						
0176	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	164	LF	
AA2						
0177	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	108	LF	
AA2						
0178	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	132	LF	
AA2						
0179	0536000000-E	SP	**** HDPE PIPE CULVERTS (30")	52	LF	
AA2						

*** OR ***

County : Montgomery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0180 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	3,980	LF	
0181 AA3	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,260	LF	
0182 AA3	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	1,016	LF	
0183 AA3	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	64	LF	
0184 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (15", 0.064")	164	LF	
0185 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (18", 0.064")	108	LF	
0186 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (24", 0.064")	132	LF	
0187 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (30", 0.079")	52	LF	

***** END SCHEDULE AA *****

0814/Feb04/Q296585.75/D718490680000/E187

Total Amount Of Bid For Entire Project :

Contract No **C202043**

County (ies): **Montgomery**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General