

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (15+37.5)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA-TION	600 TON		
0008	0106000000-E	230	BORROW EXCAVATION	1,450 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0011	0199000000-E	SP	TEMPORARY SHORING	1,503 SF		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE-RIAL, MINOR STRS	19 TON		
0013	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	80 LF		
0014	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	64 LF		
0015	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0016	0995000000-E	340	PIPE REMOVAL	24 LF		
0017	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	160 TON		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	160 TON		
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	18 TON		
0021	2000000000-N	806	RIGHT OF WAY MARKERS	7 EA		
0022	2022000000-E	815	SUBDRAIN EXCAVATION	68 CY		
0023	2033000000-E	815	SUBDRAIN FINE AGGREGATE	51 CY		
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	300 LF		
0025	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	9 EA		
0026	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0027	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0028	2275000000-E	SP	FLOWABLE FILL	5 CY		
0029	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0030	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0031	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0032	2535000000-E	846	***X*** CONCRETE CURB (9" X 12")	30 LF		
0033	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	85 LF		
0034	3000000000-N	SP	IMPACT ATTENUATOR UNIT, TYPE 350	1 EA		
0035	3030000000-E	862	STEEL BM GUARDRAIL	25 LF		
0036	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (350 TL-2)	3 EA		
0038	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (RETROFIT)	1 EA		
0039	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	3 EA		
0040	3649000000-E	876	RIP RAP, CLASS B	42 TON		
0041	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,725 SY		
0042	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	44 LF		
0043	4102000000-N	904	SIGN ERECTION, TYPE E	5 EA		
0044	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	6 EA		
0045	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	2 EA		
0046	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	214 SF		
0047	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0048	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	20 SF		
0049	4435000000-N	1135	CONES	27 EA		
0050	4445000000-E	1145	BARRICADES (TYPE III)	36 LF		
0051	4455000000-N	1150	FLAGGER	100 MD		
0052	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0053	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	2 EA		
0054	4485000000-E	1170	PORTABLE CONCRETE BARRIER	191 LF		
0055	4500000000-E	1170	RESET PORTABLE CONCRETE BAR- RIER	100 LF		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	135	LF	
0057	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	6,352	LF	
0058	6000000000-E	1605	TEMPORARY SILT FENCE	900	LF	
0059	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	250	TON	
0060	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	100	TON	
0061	6012000000-E	1610	SEDIMENT CONTROL STONE	415	TON	
0062	6015000000-E	1615	TEMPORARY MULCHING	2.5	ACR	
0063	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0064	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.25	TON	
0065	6024000000-E	1622	TEMPORARY SLOPE DRAINS	110	LF	
0066	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2	EA	
0067	6029000000-E	SP	SAFETY FENCE	200	LF	
0068	6030000000-E	1630	SILT EXCAVATION	320	CY	
0069	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,250	SY	
0070	6037000000-E	SP	COIR FIBER MAT	30	SY	
0071	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	50	SY	
0072	6042000000-E	1632	1/4" HARDWARE CLOTH	80	LF	
0073	6070000000-N	SP	SPECIAL STILLING BASINS	16	EA	
0074	6071030000-E	SP	COIR FIBER BAFFLES	185	LF	

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	6071050000-E	SP	*** SKIMMER (1-1/2")	5 EA		
0076	6084000000-E	1660	SEEDING & MULCHING	3.5 ACR		
0077	6087000000-E	1660	MOWING	1 ACR		
0078	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0079	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0080	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0081	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
0082	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0083	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0084	6123000000-E	1670	REFORESTATION	0.1 ACR		
STRUCTURE ITEMS						
0085	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (15+37.50-L-)	Lump Sum	L.S.	
0086	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+37.50-L-)	Lump Sum	L.S.	
0087	8105520000-E	SP	3'-0" DIA DRILLED PIERS IN SO IL	133.5 LF		
0088	8105620000-E	SP	3'-0" DIA DRILLED PIERS NOT IN SOIL	65 LF		
0089	8111200000-E	SP	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	61 LF		
0090	8113000000-N	SP	SID INSPECTION	1 EA		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0092	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVATION	550 CY		
0093	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	52.1 CY		
0094	8217000000-E	425	REINFORCING STEEL (BRIDGE)	20,709 LB		
0095	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	4,589 LB		
0096	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	266 LF		
0097	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	290 TON		
0098	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	320 SY		
0099	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0100	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	930.23 LF		

1137/Feb04/Q47452.68/D431316920000/E100

Total Amount Of Bid For Entire Project :

Contract No **C201809**

County (ies): **Watauga**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General